

<b><u>Name of Work :</u></b>		<b>S.R. to Electrical Work for LT &amp; HT Panel Cleaning by Liquid Technology &amp; Thermal Scanning at Civil Hospital Asawa, Ahmedabad.</b>					
<b>Schedule B</b>							
<b>SR.No</b>	<b>ARC 2026-27 SR No</b>	<b>Item Description</b>	<b>Qty</b>	<b>Unit</b>	<b>Rate</b>	<b>Rate In Words</b>	<b>Amount</b>
1	10-3-3(A)	Servicing, overhauling, cleaning of the panel board LT by liquid EPNF-065™ technology , after scanning the single side of panel by thermal scanning technology. Thermal scanning technology includes measuring temperature before and after servicing by each & every space of the panel board. One side of panel must be cleaned by Air Compressor Capacity 2.5 to 3.5 HP Motor, 1 or 3 phase, 230v, Air tank having capacity approx 50 kg with latest moisture filter, spray gun having EPNF-065™ liquid. The work having time constraints of 2 to 5 minutes single side of the panel. After finishing work agency has to provide 3 photographs or to provide 2 minutes video. Dust or any waste material must be collected by agency in the bottom of panel board by non woven fabrics material or any scientific materiel. Agency has to carry out work in presence of site in charge engineer & to complete the work as per site in charge engineer. ( Consider Measurement MIN. Sq.Mtr. ) Scope Of Work :-a) liquid Cleaning, b) blowing by compressor & Cleaning, c) Thermal Scanning,d) Photograph & Videos e) Supervision by authorized Engineer	202.40	Sq.Mtr.	4816.00	Rupees Four Thousand Eight hundred Sixteen Only	<b>974755.029</b>

2	10-3-3(B)	Servicing, overhauling, cleaning of the panel board HT by EPNF-065™ technology , after scanning the single side of panel by thermal scanning technology. Thermal scanning technology includes measuring temperature before and after servicing by each & every space of the panel board. One side of panel must be cleaned by Air Compressor Capacity 2.5 to 3.5 HP Motor, 1 or 3 phase, 230v, Air tank having capacity approx 50 kg with latest moisture filter, spray gun having EPNF-065™ liquid. The work having time constraints of 2 to 5 minutes single side of the panel. After finishing work agency has to provide 3 photographs or to provide 2 minutes video. Dust or any waste material must be collected by agency in the bottom of panel board by non woven fabrics material or any scientific materiel. Agency has to carry out work in presence of site in charge engineer & to complete the work as per site in charge engineer.	32.33	Sq.Mtr.	5645.00	Rupees Five Thousand Six hundred Forty Five Only	<b>182515.269</b>
			Estimate Amount				<b>1157270.30</b>

- Note –1** All work shall be carried out as per specification attached and relevant I.S. standards or as directed.
- Note –2** All the columns in schedule should be filled in by ball pan or ink and the total of the entries in the last column should be stated by the
- Note –3** Rates quoted include clearance of site (Prior to commencement of work and at its closure) in all respects and held good for the work
- Note –4** Tenderer must be Follow make list
- Note –5** To be continued on additional sheets, if found necessary.

**Asst. Eng ( Elect )**  
**Piu, Ahmedabad**

**Dy. Executive Engineer ( Elect )**  
**Piu, Ahmedabad**

**Executive Engineer ( Elect )**  
**Piu, Ahmedabad**