

Name of Work :- Constructing C.C. Road Village : Bhaload (Near Moxnath Mandir to Narmada Ghat) Ta: Jhagadiya Dist.Bharuch

BILL OF QUANTITIES

Memorandum showing item of works to be carried out.

It. No.	Description of Item	Qty.	Unit	Rate in figures	Total Amount
1	2	3	4	5	6
1	Box cutting the road surface to proper slope and camber for making a base of road work including removing the excavated stuff and depositing on the road side slopes directed up to 50 mts. Lead.	145.00	Cum	104.20	15109.00
2	Providing and laying compacted WBM of Grading-II MCBT metal of size 53 to 22.4mm in required layers including using 24% stone screening, 11.2mm size and 8% stone dust as filler including spreading watering & consolidation by vibratory roller	69.30	Cum	1255.43	87001.30
3	Providing and filling in foundation with ordinary cement concrete 1 cement : 3 Course sand : 6 Crushed Stone aggregate 20mm nominal size mix & providing necessary vertical pin headers including form work, vibrating, ramming & curring & complete	58.00	Cum	3105.11	180096.38
4	Providing and Casting in Situ Controlled Concrete M-200 for approach slab including formwork curing and finishing complete.	87.00	Cum	4048.08	352182.96
5	Providing Trimixed Machine For Leveling Smooth Finishing including channel fixing electric supply etc & dewatering of excess water through vacuum pump including transportation of machine etc completed directeed.	578.00	sqmt	65.65	37945.70
			TOTAL Rs.		672335.34

i.e. Rs Six lacs Seventy Two thousand Three hundred Thirty Five and Thirty Four paisa only.

I/We am/are willing to carry out the work @ _____ % above/below percent (Should be written in figures and words) of the estimated rate mentioned above. Amount of my /our tender works out as under.

Estimated amount put to tender	Estimated amount put to tender
Deduct.....% below	Add.....% Above
Net Rs. _____	Total Rs. _____
In words _____	In words _____

Note :-

- The Contractor shall exhibit a board with detailed specification and details of work as directed by the Engineer-In-Charge for which no extra payment shall be made.
- The labour cess will be deducted as per prevailing rules i.e. 1% of the work done.
- GST and Income tax TDS will be deducted at a source while making payments of bills.
- In all R.C.C. Items in Rate Analysis Standard Cement Consumption has been taken as per Govt. G.R.: PRC-10/2017 Cement Consumption/16/C, Date:11/05/2017 as stated in S.O.R. therefore in R.C.C. items where there is a change as per actual mix design the cost of difference of cement consumption have been deducted from the rate of original item at the rate of input rate mentioned in all the tender.

Above all items of "Schedule-B" with Item Description, Unit, Rate & Amount have verified by me and found order.