

THE AGRICULTURAL PRODUCE MARKET COMMITTEE- RAJULA**DIST :- AMRELI****SCHEME :- DMF (DISTRICT MINERAL FOUNDATIONS) GRANT****NAME OF WORK :- CONSTRUCTION WORK OF CEMENT CONCRETE ROAD****Location : S.No. 110/1 and 110/2, Rajula - Savarkundala road, New A.P.M.C. Campus,****SCHEDULE - B1**

I. No.	Item Description	Qty.	Rate	Per	Amount
1	Box cutting the road surface to proper slope and camber for making a base for road work including removing the excavated stuff and depositing on the road side slope as directed upto 50Mt.lead.				
		1881.00	109.41	Cumt.	205800.21
2	Earthwork for embankment including breaking clods, dressing with all lead and lift (excluding watering and consolidation)(E) From Borrow area within 3.0 Km. lead.				
		1881.00	169.28	Cumt.	318415.68
3	Rolling of earthwork in layers with power roller including filling in depressions which occur during the process.				
		1881.00	13.42	Cumt.	25243.02
4	Watering of earth work as directed.				
		1881.00	9.53	Cumt.	17925.93
5	Providing and laying of wet mix base course macadam of 150mm each layer using machine crushed chips as per required gradation mixing with required optimum quantity of water conveying the mix to site and spreading in to grade and camber with machinery paver, consolidation with vibratory road rolling including materials In Two Layers.				
		627.00	833.25	Cumt.	522447.75
6	Rolling and consolidation of soiling including filling in depression which occur during the process, with power roller 8 tonne to 12 tonne.				
		2090.00	22.75	Sqmt.	47547.50
7	Providing and laying cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 Machine cut stone aggregate 40mm nominal size) and curbing complete excluding cost of formwork in (a) Foundation and plinth.				
		306.90	3293.61	Cumt.	1010808.91

I. No.	Item Description	Qty.	Rate	Per	Amount
8	Providing and laying in position Ready Mixed M-200 grade concrete for reinforced cement concrete work , using cement content as per approved Design Mix manufactured in fully automatic batching plant and transported to site of work in transit mixer for a lead up to 10 kms having continuous agitated mixer, manufactured as per mix design of specified grade for reinforced cement concrete work including pumping of R.M.C. from transit mixer to site of laying, excluding the cost of centering shuttering finishing and reinforcement including cost of admixtures in recommended proportions as per IS: 9103 to accelerate/ retard setting of concrete, improve workability without impairing strength and durability as per direction of the Engineer - in - charge. Without Fly Ash (Min cement level as per latest IS 456 shall be maintained) (Cement level 400 kg).				
		297.00	5024.79	Cumt.	1492362.63
9	Providing and using of quartz base non metallic, dry shake natural aggregate Concrete Surface Hardner of approved make and manufacture @ 2 kg/ Sq.mt.				
		3960.00	30.30	Kg.	119988.00
10	Providing and using Polyester Fiber (12mm) with triangular or equivalent cross section with specific gravity 1.35 to 1.40 (as a secondary reinforcement) in concrete of any grade at the rate of 125 gms. (1-Packet of 125 gms.) per 50 kg. of cement consumption.				
		2380.00	60.60	Packet	144228.00
11	Providing and using Polyester Fiber (12mm) with triangular or equivalent cross section with specific gravity 1.35 to 1.40 (as a secondary reinforcement) in concrete of any grade at the rate of 125 gms. (1-Packet of 125 gms.) per 50 kg. of cement consumption.				
		6930.00	77.29	KG.	535619.70
Total Amount Rs..					4440387.33
Roundup Amount Rs..					4440388.00

NOTE: Rate given in Price schedule are excluding GST. Contractor shall have quote the tender without GST.

Stamp with Signature of Contractor

Cons. Engineer
Vanraj K. Patel
Neha Consultancy (PMC)

Secretary
APMC - RAJULA
Rajula

Chairman
APMC - RAJULA
Rajula