

EXI. 66KV H/F KHEDA - SAMADRA LINE ON ACSR_DOG TO ACCC DAMAN CONDUCTOR CONVERTED.

SECTION	HTI'S	Single	Single	Double	Double	Vibration	Mid Span	Repair	T	Jumper
---------	-------	--------	--------	--------	--------	-----------	----------	--------	---	--------

[illegible]

EXI. 66KV H/F KHEDA - SAMADRA LINE ON ACSR DOG TO ACCC DAMAN CONDUCTOR CONVERTED.																			
TENTETIVE TOWER SCHEDULE																			
SR. NO.	LOC. NO.	DEVIATION ANGLE	TYPE OF TOWER	SPAN	SECTION LENGTH	REMARKS / CROSSING DETAILS	HTLS Conductor	Suspension SRI	Tension SRI	Single Tension H/W	Single Suspension H/W	Double Tension H/W	Double Suspension H/W	PA Rod	Vibration Damper	Mid Span Joints for HTLS Conductor	Repair Sleeve for HTLS Conductor	T connector with pad	Jumper terminal without hole with suitable
				(IN MTR.)															
32	EXI LOC.NO.-29	26°35'4"LT	"B" TYPE DP		463		0	0	6	6					6				
				102		LT LINE	321.3	0	0										
33	PRO. LOC.NO.-30	16°10'52"RT	PS+3		102	EXI. LOC.NO.-30 "B" TYPE DP TO BE DISMANTLE	0	0	9	3		3			6				
				222		VATRAK RIVER, CART TRACK	699.3	0	0										
34	PRO. LOC.NO.-31	31°3'2"RT	PS+3		222	EXI. LOC.NO.-31 "B" TYPE DP TO BE DISMANTLE 13.00 MTR.	0	0	9	3		3			6				
				187		LT LINE, 11KV LINE, CART TRACK	589.05	0	0										
35	EXI LOC.NO.-32	3°33'3"RT	"B" TYPE DP		187		0	0	9	3		3			6				
				179		CART TRACK, TAR ROAD HARIYALA TO VASNA-KHURD, 11KV LINE	563.85	0	0										
36	EXI LOC.NO.-33 & 25	63°6'38"RT 115°45'49"LT	DS+0		179	COMMON TOWER (EXI. 66KV H/F HARIYALA - SAMADRA LINE)	0	0	9	3		3			6				
				139			437.85	0	0										
37	EXI LOC.NO.-34 & 26	19°27'46"RT	DS+0		139		0	0	6	6					6				
				231		LT LINE, CART TRACK	727.65	0	0										
38	EXI LOC.NO.-35 & 27	44°28'3"RT	DS+6		231		0	0	9	3		3			6				
				113		TAR ROAD HARIYALA TO VASNA-KHURD, 11KV LINE, CART TRACK	355.95	0	0										
39	EXI LOC.NO.-36 & 28	0°56'31"LT	DS+6		113		0	0	9	3		3			6				
				247		11KV LINE, CART TRACK	778.05	0	0										
40	EXI LOC.NO.-37 & 29	1°38'19"LT	DS+0		247		0	0	6	6					6				
				199		2 NOS. CART TRACK, 2 NOS. 11KV LINE, KANDLA - GORKHAPUR PETROLEUM GAS PIPE LINE	626.85	0	0										
41	EXI LOC.NO.-38 & 30	0°36'47"RT	DS+0		199		0	0	6	6					6				
				201		LT LINE	633.15	0	0										
42	EXI LOC.NO.-39 & 31		DP+0				0	6	0				3	3	6				
				189		CART TRACK, 2 NOS. 11KV LINE, LT LINE, RCC ROAD, TAR ROAD HARIYALA TO VASNA-KHURD	595.35	0	0										
43	EXI LOC.NO.-40 & 32		DP+6				0	6	0				3	3	6				
				274		11KV LINE, LT LINE	863.1	0	0										
44	EXI LOC.NO.-41 & 33		DP+6				0	3	0		3			3	6				
				219		11KV LINE	689.85	0	0										
45	EXI LOC.NO.-42 & 34	49°50'16"RT 31°20'41"RT	DS+0		883	COMMON TOWER (EXI. 66KV H/F HARIYALA - SAMADRA LINE)	0	0	6	6					6				
				80		11KV LINE	252	0	0										
46	EXI LOC.NO.-43	11°33'0"LT	"B" TYPE DP		80		0	0	6	6					6				
				85		CART TRACK	267.75	0	0										
47	EXI LOC.NO.-44	4°24'42"LT	"B" TYPE DP		85		0	0	6	6					6				
				163			513.45	0	0										
48	EXI LOC.NO.-45		"A" TYPE DP				0	3	0		3			3	6				
				135			425.25	0	0										
49	EXI LOC.NO.-46	0°29'58"LT	"B" TYPE DP		298		0	0	9	3		3			6				
				138		CART TRACK, 2 NOS. LT LINE, 11KV LINE, RCC ROAD	434.7	0	0										
50	EXI LOC.NO.-47	21°43'32"LT	"B" TYPE DP		138		0	0	12			6			6				
				150		LT LINE, RCC ROAD	472.5	0	0										
51	EXI LOC.NO.-48		"A" TYPE DP				0	6	0				3	3	6				
				152			478.8	0	0										
52	EXI LOC.NO.-49		"A" TYPE DP				0	3	0		3			3	6				
				128		11KV LINE	403.2	0	0										
53	EXI LOC.NO.-50		"A" TYPE DP				0	3	0		3			3	6				
				129		CART TRACK	406.35	0	0										
54	EXI LOC.NO.-51		"A" TYPE DP				0	3	0		3			3	6				
				125			393.75	0	0										
55	EXI LOC.NO.-52	6°41'51"RT	"B" TYPE DP		684		0	0	6	6					6				
				142		11KV LINE	447.3	0	0										
56	EXI LOC.NO.-53		"A" TYPE DP				0	3	0		3			3	6				
				138		CART TRACK	434.7	0	0										
57	EXI LOC.NO.-54		"A" TYPE DP				0	3	0		3			3	6				
				162			510.3	0	0										
58	EXI LOC.NO.-55		"A" TYPE DP				0	3	0		3			3	6				
				131		CART TRACK	412.65	0	0										
59	EXI LOC.NO.-56		"A" TYPE DP				0	3	0		3			3	6				
				151			475.65	0	0										
60	EXI LOC.NO.-57	19°18'18"LT	"B" TYPE DP		724		0	0	6	6					6				
				146		LT LINE, 11KV LINE, CART TRACK	459.9	0	0										
61	EXI LOC.NO.-58		"A" TYPE DP				0	3	0		3			3	6				
				116		CART TRACK	365.4	0	0										
62	EXI LOC.NO.-59		"A" TYPE DP				0	3	0		3			3	6				
				146			459.9	0	0										
63	EXI LOC.NO.-60		"A" TYPE DP				0	3	0		3			3	6				

EXI. 66KV H/F KHEDA - SAMADRA LINE ON ACSR_DOG TO ACCC DAMAN CONDUCTOR CONVERTED.																			
TENTETIVE TOWER SCHEDULE																			
SR. NO.	LOC. NO.	DEVIATION ANGLE	TYPE OF TOWER	SPAN	SECTION LENGTH	REMARKS / CROSSING DETAILS	HTLS Conductor	Suspension SRI	Tension SRI	Single Tension H/W	Single Suspension H/W	Double Tension H/W	Double Suspension H/W	PA Rod	Vibration Damper	Mid Span Joints for HTLS Conductor	Repair Sleeve for HTLS Conductor	T connector with pad	Jumper terminal without hole with suitable
				(IN MTR.)															
				131		11KV LINE	412.65	0	0										
64	EXI. LOC.NO.-61		"A" TYPE DP				0	3	0		3			3	6				
				136		CART TRACK	428.4	0	0										
65	EXI. LOC.NO.-62		"A" TYPE DP				0	3	0		3			3	6				
				136		LT LINE	428.4	0	0										
66	EXI. LOC.NO.-63		"A" TYPE DP				0	3	0		3			3	6				
				132			415.8	0	0										
67	EXI. LOC.NO.-64		"A" TYPE DP				0	3	0		3			3	6				
				117			368.55	0	0										
68	EXI. LOC.NO.-65	25°53'5"LT	"B" TYPE DP		1060		0	0	6	6					6				
				96			302.4	0	0										
69	EXI. LOC.NO.-66		"A" TYPE DP				0	3	0		3			3	6				
				73		CART TRACK	229.95	0	0										
70	EXI. LOC.NO.-67		"A" TYPE DP				0	3	0		3			3	6				
				86		TAR ROAD VASNA-KHURD TO SAMADRA	270.9	0	0										
71	EXI. LOC.NO.-68	9°52'17"LT	"B" TYPE DP		255		0	0	9	3		3			6				
				94		CART TRACK	296.1	0	0										
72	EXI. LOC.NO.-69		"A" TYPE DP				0	3	0		3			3	6				
				101		CART TRACK	318.15	0	0										
73	EXI. LOC.NO.-70	20°24'12"LT	"B" TYPE DP		195		0	0	6	6					6				
				30			94.5	0	0										
0	EXI. 66KV SAMADRA GANTRY				30	EXI. 66KV SAMADRA(GETCO) S/S.	0	0	12			6			3	9	9	3	6
Total Length in (mt)				10792	10792														
Total Length in (km)				10.792															
							33994.8	141	273	135	105	69	18	123	444	9	9	6	12
							Additional Quantities	6		5	6	2	2	3	3				
							Final Quantities	147	273	140	111	71	20	126	447	9	9	6	12