



DAKSHIN GUJARAT VIJ COMPANY LIMITED		
	Rander (O&M) Division, DGVCL	
	Plot No. 37, T. P. No. 32,	
	B/H New Jalaram Mandir	
	Near Saurabh Police Station,	
	LP Savani Road, Adajan, Surat.	
	Ph .NO.0261-2737455	
		

TENDER ID:**E-URJA Purchase Requisition No:****RFQ No:**

Executive Engineer, DGVCL, RANDER DIVISION Office invites On-line Tenders for the ARC for Erection and labor work of supply, laying, testing & commissioning of 11/22 KV Underground XLPE cable (XLPE cable will be supplied by DGVCL) with cable end termination & straight through jointing kit (To be supplied by contractor) on ARC basis under ND and Misc for Palanpore sub division under Rander division and if required work to be carried out at other sub division under Rander Division. Tender Papers & Specifications may be downloaded from web site <https://tender.nprocure.com> (To view, download and on-line submission). Tender fee & EMD must be paid along with submission of tender online only, for respective tender. "All the relevant documents of tenders to be submitted online only not required physically if you have any query addressed to Executive Engineer, Dakshin Gujarat Vij Company Limited, Rander Division Office, Plot No:37, TP-32, B/h Jalaram Mandir, Near Saurabh Police Chawki, L.P. Savani Road, Adajan, Surat -395009

1	Tender No. / Type of Tender	
2	Tender Item	ARC for Erection and labor work of supply, laying, testing & commissioning of 11/22 KV Underground XLPE cable (XLPE cable will be supplied by DGVCL) with cable end termination & straight through jointing kit (To be supplied by contractor) on ARC basis under ND and Misc for Palanpore sub division under Rander division and if required work to be carried out at other sub division under Rander Division.
3	Estimated Cost	Rs. 30,00,000.00
4	Tender Fees (Non Refundable) with 18% GST	Rs. As per Clause mentioned in Instruction to Bidders Clause No. 9
5	Earnest Money Deposit	Rs. As per Clause mentioned in Instruction to Bidders Clause No. 10
6	Date & Place of Pre-Bid Meeting (If required)	Not applicable
7	Last Date of On Line (E-Tendering) submission of Tender (Between > 7 to 21 days)	Date: 23.06.2026 on Time : Up to 18.00 Hrs.
8	Submission of Tender Fee & EMD & other documents	Submitted online only
9	Date of opening of Preliminary Stage (Tender Fee & EMD)	Date: 24.06.2026 on Time : Up to 11.00 Hrs.
10	Tentative Date of opening of Technical Bid	Date: 25.06.2026 on Time : Up to 11.00 Hrs.
11	Tentative Date of On line Opening of Price Bid	Date: 29.06.2026 on Time : Up to 11.00 Hrs.
12	Validity of Tender	Maximum period of 180 Days
13	Work Completion Period / Time Limit	12 Months (As per quantum of work)

DGVCL GSTIN No. is 24AABCD8912C1Z3**Every Bidder has to inform their GSTIN No. at the time of payment of applicable fees.****IMPORTANT:**

- Interested Bidders can view these tender documents online. The bidders who are interested in bidding in these tenders can download tender documents from website www.tender.procure.com
- Bidders, who wish to participate in this tender, will have to register on www.tender.procure.com. Further, Bidders who wish to participate in online tenders will have to procure Digital Certificate as per Information Technology Act-2000 using which they can sign, their electronic bids. Bidders can procure the same from GNFC, Ahmedabad, who are licensed certifying authority by Government of India and they will assist them in procuring the same as below mentioned address. Bidders who already have a valid Digital Certificate need not procure a new Digital Certificate.

301, GNFC Info tower, S.G. Road, Bodakdev
 Ahmedabad – 380054 (Gujarat)
 Toll Free: 1-800-233-1010 (Ext. 501, 512,516, 517, 525)
 Phone No. 079-26857315 / 316 / 317
 Fax: 079-26857321 / 40007533
 Email: nprocure@gnvfc.net

File No: DGVCLDRND/OTH/e-file/4458/2026/3175/Technical

Approved By: Deputy Engineer, Technical, DGVCLSDAD

Open the document in Adobe Acrobat DC to verify the E-sign



- c. However, no physical documents required if payment of tender Fee and EMD made through, RTGS & NEFT (upload receipt online on <https://tender.nprocure.com>).
- d. Further bidders are requested to submit price bid (Schedule: B) on-line only and not to submit the price bid in physical form. This is mandatory. If price bid is submitted in physical form, such offer shall be out rightly rejected.
- e. It is mandatory for all the bidders to submit their tender documents with all relevant documents as desired in participation of this bid through on-line (e-tendering) in schedule time. If tender documents with all relevant documents submitted in physical form, in that case the online submitted documents shall be considered.
- f. Bidders should be in touch with websites <https://tender.nprocure.com> intimation regarding revision/corrigendum/Amendment in tender till due date of online submission and thereafter. No separate information shall be sent in this regard and also not publish in newspaper. The directives and amendments issued by DGVCL will have superseding effect to relevant section and specifications.
- g. Any technical questions, information & clarification that may be required pertaining to this inquiry should be referred to Executive Engineer Rander Division Office, "Dakshin Gujarat Vij Company Limited"
- h. DGVCL reserves the right to reject any OR all tenders without assigning any reasons thereof.
- i. Bank Details:
Name of Bank: Bank of Baroda
Account Number: 07400200000930
Branch Name: Navyug College Branch, Surat
Type of Account: Non-Operative
IFSC Code: BARB0RANSUR (Fifth Digit is Zero)

Executive Engineer (O&M)
DGVCL, Rander Division

Download Tender Documents in (PDF Format) which consists of:

Schedule – A
Instructions to Bidder
General Conditions of Contract
Schedule "B" indicating the quantities, rates & items, drawing if any.
Appendix and Annexure
Technical Specifications & GTP's

To view the PDF file please use "Acrobat Reader" software which can be downloaded from "Adobe" website.

NOTE:

In case bidder needs any clarification or if training required for participating in online tender, they can contact the following office:

(n) Procure Cell
(n) Code solutions- GNFC Ltd.,
301, GNFC Info tower, S.G. Road, Bodakdev
Ahmedabad – 380054 (Gujarat)
Toll Free: 1-800-233-1010 (Ext. 501, 512, 516, 517, 525)
Phone No. 079-26857315 / 316 / 317
Fax: 079-26857321 / 40007533
Email: nprocure@gnfc.net
Other terms & conditions are as per tender documents



Schedule-B

Schedule-B for ARC for Erection and labor work of supply, laying, testing & commissioning of 11/22 KV Underground XLPE cable (XLPE cable will be supplied by DGVCL) with cable end termination & straight through jointing kit (To be supplied by contractor) on ARC basis under ND and Misc for Palanpore sub division under Rander division and if required work to be carried out at other sub division under Rander Division.

Sr. No.	Item Code	Description	Unit	Rate for FY 2024-25 (Rs.)
1	9925000001	Labour charge for excavation of cable trench of 400mm width x 1200mm depth , in any type of soil for laying of cable of size up to 240 mm² (For additional cable 200 mm additional width shall be considered i.e. half trench length is to be considered)	Meter	72
2	9925000002	Labour charge for excavation of cable trench of 600mm width x 1200mm depth , in any type of soil for laying of cable of size up to 240 mm² (For additional cable 200 mm additional width shall be considered i.e. half trench length is to be considered)	Meter	109
3	9925000003	Labour charge for excavation of cable trench of 400mm width x 1500mm depth , in any type of soil for laying of cable of size up to 240 mm² (For additional cable 200 mm additional width shall be considered i.e. half trench length is to be considered)	Meter	91
4	9925000004	Labour charge for laying of 11kV / 22 kV XLPE Cable of size up to 240 mm² & preparation of sand layer 100mm thick, in the cable trench & covering the cable with 150 mm dia (Inner), thickness 25 mm , 1.0 meter long RCC half round muffs and providing and fixing of 4inch width yellow colour polyethylene tape with printing "CAUTION ELECTRIC CABLE BELOW" at 0.75 m depth from ground surface after laying cable in trench. This will provide indication that electric cable is passing underground so as to protect cable from mechanical injuries, refilling the same, as per Instruction of Engineer in Charge (EIC).	Meter	171
5	9925000005	Labour charge for horizontal drilling using Auger machine without damage to surface road at max 2.0 mtrs depth & putting of 6.11 kg/cm ² , class-4, Green color, 110mm O.D., 8.5mm thickness H.D.P.E. pipe conforms to IS 4984-1987(3rd revision) and BIS certification and laying of 11KV/22KV XLPE cable of size up to 240 mm ² in HDPE pipe, as per Site Condition (excluding cost of pipe). The detail map obtained from HDD machine and excell sheet(hard and soft copy) indicating the respective depth and distance from adjacent landmark for each segment for HDD is must required to be submitted. HDD to be carried out at depth 1.5 mtrs to 2.0 mtrs as per site conditions and as per instruction of EIC.	Meter	860



6	9925000006	Labour charge for horizontal drilling manually without damage to surface road at max 2.0 mtrs depth & putting of 6.11 kg/cm ² , class-4, Green color, 110mm O.D. , 8.5mm thickness H.D.P.E. pipe confirms to IS 4984-1987(3rd revision) and BIS certification and laying of 11KV/22KV XLPE cable of size up to 240 mm ² size, as per Site Condition (excluding cost of pipe). The detail map and excell sheet(hard and soft copy) indicating the respective depth and distance from adjacent landmark for each segment of cable to be submitted. Drilling to be carried out at depth Minimum 1.2 mtrs to 2.0 mtrs as per site conditions as per instruction of EIC.	Meter	615
7	9925000007	Supply of 6.11kg/cm ² , class-4, Green color, 110mm O.D. , 8.5 mm thickness H.D.P.E. pipe confirms to IS 4984 and BIS certification for laying of underground 11KV / 22KV XLPE cable up to 240 mm² size.	Meter	430
8	9925000008	Labour work for RCC concreting on disputed location and repairing of damage portion of road crossing for the work carried out for roads crossing as well as concreting & muffing of poles including all materials (1:2:4)	CMT	3189
9	9925000009	Providing & fixing concrete stone route marker of 300 mm width x 150 mm thick x 650 mm height embedded in earth at least 300 mm below & 350 mm above ground level respectively at distance approx 50 meters along the length of cable. The RCC concreting (1:2:4)(all necessary materials will be in bidder's scope) of route marker is to be carried out 300 mm width x 150 mm thick x 300 mm below ground level as per instruction of EIC. The route marker should be with name of company with approved yellow colour-DGVCL. The distance from marker to cable and cable depth with feeder name etc., marked with arrow sign is to be painted on it. The route marker is to be fixed at location near to any fixed permanent location (not necessary to fix exact on top of cable) as per instruction of EIC.	No.	446
10	9925000010	Erection of D.P. (double pole) structure using 9 / 11 Mtr. RSJ pole with cable connection arrangement along with fitting of necessary fabrication for 11KV cable including excavation of pit & refilling of earth as per instruction of EIC. (Exclusive of concreting & muffing of poles)	No.	2026
11	9925000011	Erection of Single pole structure using 9 / 11 Mtr RSJ pole with cable connection arrangement along with fitting of necessary fabrication for 11KV/22 KV cable including excavation of pit & refilling of earth as per instruction of EIC. (Exclusive of concreting & muffing of poles)	No.	1047
12	9925000012	Erection of D.P. (double pole) structure using 8.0 Mtr. PSC pole with cable connection arrangement along with fitting of necessary fabrication for 11KV cable including excavation of pit & refilling of earth as per instruction of EIC. (Exclusive of concreting & muffing of poles)	No.	1416
13	9925000013	Erection of Single pole structure using 8.0 Mtr PSC pole with cable connection arrangement along with fitting of necessary fabrication for 11KV/22 KV cable including excavation of pit & refilling of earth as per instruction of EIC. (Exclusive of concreting & muffing of poles)	No.	613
14	9925000014	Labour charge for erecting of 11kV / 22 kV XLPE cable of size up to 240 mm² on DP Structure with fixing of 02 Nos polymer cleats on top and middle part . Polymer cleats, nut bolts etc. fixing material to be provided by contractor.	Per Job	591



15	9925000015	Providing & fixing of 6.11kg/cm² , class-4, Green color, 110mm O.D. , 8.5mm thickness H.D.P.E. pipe confirms to IS 4984 and BIS certification on the erected DP structure for the mechanical protection of cable by inserting the cable inside HDPE pipe. The HDPE pipe shall be erected in such a way that 300mm shall be below the ground level and the rest 2700 mm shall be supported on the DP Structure with 01 No Polymer cleat. All materials including polymer cleat and Nut bolt to be provided by contractor.	Per Job	1461
16	9925000016	Providing and fixing of pipe type earthing from 80 mm dia class-B GI pipe with pit to be filled with salt & coke and construction of chamber as per DGVCL Drg. No. dg /100 for DP and cable. The earthing pit should be joined with cable by G.I. strip of size 1" width & 2 mm thick. All material GI pipe, Coke, Salt etc will be supplied by bidder.	No.	3635
17	9925000017	Supply & fixing of heat shrink type end terminations (outdoor) for upto 11kV 3C x 185 mm² size XLPE cable as per DGVCL technical specification	No.	3635
18	9925000018	Supply & fixing of heat & shrinkable end terminations (outdoor) for upto 22 kV 3C x 185 mm² size XLPE cable as per DGVCL technical specification)	No.	6231
19	9925000019	Supply & fixing of heat shrink type end terminations (indoor) for upto 11kV 3C x 185 mm² size XLPE cable as per DGVCL technical specification)	No.	3635
20	9925000020	Supply & fixing of heat & shrinkable end terminations (indoor) for upto 22 kV 3C x 185 mm² size XLPE cable as per DGVCL technical specification	No.	6231
21	9925000021	Supply & fixing of heat shrinkable straight through joint for upto 11kV 3C x 185 mm² size XLPE cable as per DGVCL technical specification.	No.	6774
22	9925000022	Supply & fixing of heat shrinkable straight through joint type for upto 22kV 3C x 185 mm² size XLPE cable as per DGVCL technical specification	No.	11590
23	9925000023	Labour charge for excavation of 2100mm long x 1200mm wide x 1200 mm deep joint pits for installation of 11kV / 22kV Straight through joints as per instruction of engineer-in-charge & covering the cable with 150 mm dia (Outer), thickness 25 mm , 1.0 meter long RCC half round muffs & refilling same as per instruction of EIC .	No.	399
24	9925000024	Providing and fixing of insulating bus bar , made from 11KV/22KV XLPE cable after removal of semi conducting layer and applying of PVC heat shrinkable anti-tracking core insulating tubing (1.1KV), on both end terminal using Aluminium long barrel heavy duty up to 240 sq mm lugs, Aluminium bus connector. Taping with PG- clamp for bus conductor as per drawing and as per instruction of EIC. The Aluminium lugs and PG clamp shall be covered with 11KV/22KV HT insulating tapes. (11KV/22KV XLPE cable will be in scope of DGVCL while all other materials will be in bidder's scope)	No.	1661
25	9925000025	Testing of cable at various points and commissioning the feeder as per instruction of engineer-in-charge. Test result shall be submitted by contractor with bill.	No.	2125
26	9925000026	Preparation and submission of 6 (six) copies , of complete layout drawings with GIS mapping as per actual cable routing showing road crossing, HDPE pipe sleeving, jointing locations, markers etc.	Set	2338



27	9925000027	Providing and fixing of Sign Board at junction point Made out of 2 mm aluminium sheet size 750x300 mm (2.5 x 1ft) rectangle, as per design, pre treated with phosphate process and acid etching coated with one coat of epoxy primer and two coats of best quality paints, reflectorised with Hi-Intensity retro – reflective sheeting as per the latest and frame fabricated from suitable size iron angle. The Sign Board is to be fixed on the base prepared from channel and bracing angles which is grouted by means of cement concreting of 1:2:4 for size of 300 mm dia x 800 mm height (500 mm to be grouted in ground). The details to be displayed on sign board will be given by In-charge Engineer. (a) Hi intensity Micro prismatic Grade	No.	10023
28	9925000028	Providing and fixing of Sign Board (Danger Board) on Distribution Transformer Centers Made out of 2mm aluminium sheet size 300x300mm (1x1ft) as per design, pre treated with phosphate process and acid etching coated with one coat of epoxy primer and two coats of best quality paints, reflectorised with Hi-Intensity retro-reflective sheeting as per the latest and frame fabricated from suitable size iron angle. The Sign Board (Danger Board) is to be fixed at the location as per instruction of In-charge Engineer. (a) Hi intensity Micro prismatic Grade	No.	2805
29	9925000029	Providing & fixing of aluminium tag of size 250 mm (L) x 75 mm (W) from 3 mm aluminium sheet along with 1.0 mm dia aluminium binding wire for fixing of aluminium tag near end termination joint at DP structure for identifying the cable. The details of feeder i.e. 11 / 22 KV with feeder name should be punched on the tag by letter punch of size 16 mm as per instruction of In-charge Engineer.	No.	83
30	9925000030	Supply & fixing of heat shrink type end terminations (outdoor) for 11kV 3C x 240 mm² size XLPE cable as per DGVCL technical specification	No.	4427
31	9925000031	Supply & fixing of heat & shrinkable end terminations (outdoor) for 22 kV 3C x 240 mm² size XLPE cable as per DGVCL technical specification)	No.	6231
32	9925000032	Supply & fixing of heat shrink type end terminations (indoor) for 11kV 3C x 240 mm² size XLPE cable as per DGVCL technical specification)	No.	4338
33	9925000033	Supply & fixing of heat & shrinkable end terminations (indoor) for 22 kV 3C x 240 mm² size XLPE cable as per DGVCL technical specification	No.	6231
34	9925000034	Supply & fixing of heat shrinkable straight through joint for 11kV 3C x 240 mm² size XLPE cable as per DGVCL technical specification.	No.	6829
35	9925000035	Supply & fixing of heat shrinkable straight through joint type for 22kV 3C x 240 mm² size XLPE cable as per DGVCL technical specification	No.	11590
36	9925000038	Installation, Testing and commissioning of 11 KV,630 A SCADA Compatible, RRL type- 3 Way RMU including Two numbers of earthings as per Drawing (material is in bidder's scope) and as per DGVCL Technical specification.	No.	42000
37	9925000039	Installation, Testing and commissioning of 11 KV,630 A SCADA Compatible, RRL type- 4 Way RMU including Two numbers of earthings as per Drawing (material is in bidder's scope) and as per DGVCL Technical specification.	No.	42000
38	9925000040	Installation, Testing and commissioning of 22KV,630 A SCADA Compatible, RRL type-3 Way, RMU including Two numbers of earthings as per Drawing (material is in bidder's scope) and as per DGVCL Technical specification.	No.	53000
39	9925000041	Installation, Testing and commissioning of 22KV,630 A SCADA Compatible, RRL type-4 Way, RMU including Two numbers of earthings as per Drawing (material is in bidder's scope) and as per DGVCL Technical specification.	No.	54500



40	9925000042	Construction of plinth for 11KV, RRL type- 3 Way (i.e Two numbers of Isolator & One number of Breaker) Ring Main Unit as per DGVCL's technical specification mentioned in drawing no: Drg. 11kv-01. All required material will be supplied by contractor.	No.	28043.22
41	9925000043	Construction of plinth for 11KV, RRL type- 4 Way (i.e Two numbers of Isolator & Two number of Breaker) Ring Main Unit as per DGVCL's technical specification mentioned in drawing no: Drg. 11kv-02. All required material will be supplied by contractor.	No.	32345.76
42	9925000044	Construction of plinth for 22KV, RRL type- 3 Way (i.e Two numbers of Isolator & One number of Breaker) Ring Main Unit as per DGVCL's technical specification mentioned in drawing no: Drg. 22kv-01. All required material will be supplied by contractor.	No.	32345.76
43	9925000045	Construction of plinth for 22KV, RRL type- 4 Way (i.e Two numbers of Isolator & Two number of Breaker) Ring Main Unit as per DGVCL's technical specification mentioned in drawing no: Drg. 22kv-02. All required material will be supplied by contractor.	No.	37090.68
44	9925000046	Modifications e.g. Providing and fixing of Terminal protectors i.e. Re-use able boot (HT Side 11/22KV, LT Side 1.1KV) including 11/22 KV insulating taps and L.T. (1.1 KV) insulating taps, Busbar, Tapping from Bus Bar (11/22 KV XLPE cable) through P.G. Clamp for H.T. Jumper to D.O. Fuse to bushings of Transformer Center, providing & Fixing of jumper and providing & fixing of Heat Shrinkable Anti Tracking Core Insulating Tubing (Insulation Level 11/22 KV) in H.T. jumper, Clamping arrangement of cable support frame on both side of existing Over Head type Distribution Transformer to utilize in Under Ground cable network as per drawing & as per instruction of Engineer incharge. All live parts i.e. PG-Clamp, connections of D.O.fuses, HT bushings etc. shall be covered with fixing of 11/22 KV HT insulating tapes. (11/22 KV XLPE cable will be in scope of DGVCL while all other materials will be in bidder's scope).	No.	10152
45	9925000047	Laying of any size of 11/ 22 KV XLPE /PILC Cable in redaymade trench or in open space	Per Cable Per Mtr	27
46	9925000060	Labour charges for Lying of O/H XLPE cable pole to pole	KM	70320
47	9925000064	Supply of 150 mm dia (Inner), thickness 25 mm, 1.0 meter long RCC half round pipe	No.	135
Total				3000000.00
In Words :- Thirty Lakh Rupees Only				
			Executive Engineer(O & M)	
			DGVCL, Rander Division	

