



Government of Gujarat

**Dakshin Gujarat Vij Company Limited**


( A Government of Gujarat Undertaking )

**Bharuch (O&M) Rural Division Office**

Maktampur, Opp. C-Division Police station, Maktampur

Bharuch – 392012: Ph. No: 02642-245775

E-mail:eebrhom.dgvcl@gebmil.com (CIN U40102GJ2003SGC042909)



**DGVC**  
**Schedule-B**

**Name of work: Providing FRP Fencing at transformer centres at various location of Any Sub Division under the jurisdiction of Bharuch Rural Division.**

Sr. No.	Item	Qty.	Rates/unit in Rs.	Unit	Amount in Rs.
1	Providing and fixing of FRP fencing of 1600mm (1500+100) mm height above ground at Distribution Transformer Centre with necessary excavation, concreting for grouting vertical posts up to 450 mm ground, hardware, accessories, fittings, lock etc complete as shown in specifications and drawing enclosed. The fencing shall comprise of one gate 2000 mm wide having two flaps and payment for the same shall be measured on Rmt basis.		3000/-	RMT	25,00,000/-
2	Inside fencing area to be finished with 6" thick 1:2:4 cement concrete & cement plaster supported with 6" brick wall on surrounding. (All materials required being use like cement bags, Bricks, sand, Kapchi is to be brought by the contractor at his own cost.) (Payment will be given in sq. foot for which concrete is done inside FRP fencing including wall.) (size 3x3 mtr)		81/-	Sq. foot	
<b>Total Value (Twenty Five Lakhs Only)</b>					<b>25,00,000/-</b>

- FRP Fencing for 1 Transformer center is approximately 12 RMT.(60 Transformers)
- Cement concrete approximately 72 Sq. foot per Transformer. (60 Transformers)

Deputy Engineer

DGVC, \_\_\_\_\_ Sub Division

File No: DGVCLDBHR/TEN/e-file/4444/2026/1936/Technical

Approved By: Executive Engineer, Technical, DGVCLDBHR

Open the document in Adobe Acrobat DC to verify the E-sign

