

# OFFICE OF THE EXECUTIVE ENGINEER E/M DIVISION

## PWD RAIPUR (C.G.)


### ANNEXURE-E

### TERMS & CONDITION

**Name of work :-** Providing E/F Work to Govt. Law College Building at-Kurud, Distt.-Dhamtari (C.G.)

- 1.. Electric installation shall be carried out in accordance with the General specification for Electrical Works (Part - I Internal) & (Part - II External) 1972 of C.P.W.D. adopted by E-In-C M.P.W.D. Bhopal & also : Confider with Indian Electrical Rule 1956 as amended. up to Date
2. Civil contractor should sublet the Electrical Work only those Electrical contractor who are Registered in PWD for Electrical Work as following class
  - (I) PAC Amount (Up to 100.00 Lacks) - "D" Class Electrical Contractor & above.
  - (II) PAC Amount (Up to 200.00 Lacks) - "C" Class & above.
  - (III) PAC Amount (Up to 1000.00 Lacs) - "B" Class & above.
  - (IV) PAC Amount (Above 1000.00 Lacs) - "A" Class.
3. Contractor will submit along with final bill.
  - (a) Completion Certificate in Appendix "E"
  - (b) Completion Plan drawn to a suitable scale on tracing cloth with ink, Indicating Location of main switch, D.B. Circuit fitting and their Location
4. The Contractor will be fully responsibility for any accident damages and losses occurred due to negligence of Work. The amount of the losses and damages etc. will be recovered from the Contractor.
5. The Contractor shall have his own tools and plants, helmet, hand gloves, first aid box and other safety measures, in good working condition for staff. No Extra payment shall be made for this arrangement and no Claims shall be paid by the department.
6. The Contractor himself shall be fully responsibility for any accident casualty of the staff if occurs due to Electrical fault or any other reason during the work and no claim will be paid for such accident of causality by the department.

7. The Contractor will be fully responsibility for taking all of safety measures during contract period.
  - (a) Electrical power supply arrangement temporarily at will be made by contractor No payment will the made by PWD Department.
8. Earthing system should be installed in presence of A.E. (E/M) / Sub. Engineer (E&M)
9. Earth continuity conductor of required size & material should be installed with entire run of wiring Earth nut bolt must be provided at all switch boards All metallic parts Ceiling fan tube fitting socket out let should be essentially connected to earth.
10. All connection of ceiling fan tube fixture street light fixture shall be made by 3 core PVC / Rubber sheathed cable of required.
11. The Civil contractor should have a Electrical Supervisor for Electrical works at site as per Norms of C.G. / M.P Govt. who Electrical Diploma / Degree Holder as Required as per PAC Amount.

  
**EXECUTIVE ENGINEER**  
**EM DIVISION RAIPUR (C.G.)**