

BoM for Demolition & Providing and laying cement concrete					
Demolition & Providing and laying cement concrete 1:3:6 (1-Cement: 3- coarse sand: 6- hand broken stone aggregates 40 mmnominal size) and curing complete excluding cost of formwork (For 0.15m thick concrete) (Rate for Surat City)					
Rate Analysis for 0.15 m thick concrete					
Sr. No.	Description	Qty	Rate	Unit	Amount
1	Demolition Including stacking of serviceable materilas and disposal of unserviceable materials with all lead and lift. (i) R.C.C. work (20002)	1	1099.75	CMT	
	For 1 Sq Mt Area with 0.15m Thick Concrete	0.15	1099.75	Sqmt	164.96
2	Providing and laying controlled cement concrete M.150 for curing complete excluding cost of formwork and reinforcement for reinforced concrete work In (A) Foundations, footings, Base of columns and Mass concrete (05023AA)	1	3919.06	CMT	
	For 1 Sq Mt Area with 0.15m Thick Concrete	0.15	3919.06	Sqmt	587.86
		Total Cost			752.82
		Grand Total Cost/Sqmt Considering 0.15m thick concrete			752.82
				Say	753.00

BoM for Removing & Re-fixing Paver block /pre-cast Rubber Dye / steel Dye Inter locking concrete block					
Removing & Re-fixing pre-cast Rübber Dye / steel Dye Inter locking concrete block 60mm thick with grade of concrete M300 pnumatic compressed/ vibrated mechanically and as per approved design Confirming to IS 15658: 2006 including 35 mm Sand layer for levelling and filling the joint with sand In proper line and level as per guldlines of IRC: SP. 63-2018 etc. Complete in true line and level as directed by EIC. (Rate for Surat City)					
Rate Analysis for 1 Sqmt					
Sr. No.	Description	Qty	Rate	Unit	Amount
1	Cost of Providing & Fixing Paver Block (SOR 14033)	1	699.93	Sqmt	699.93
2	Paver Block (SOR M910)	-1	377.12	Sqmt	-377.12
3	Dismantaling tiled of stone floors laid in mortar Including stacking of serviceable materilas and disposal of unserviceable materials with all lead and lift (SOR 20005)	1	49.61	Sqmt	49.61
		Total Cost			372.42
		Grand Total Cost/Sqmt Considering 0.15m thick concrete			372.42
				Say	372.00