

SCHEDULE-B					
	Supply for labour charge for XLPE with UV coating on 55 SQ MM conductor (1.2 MM thick) including labour charge for Any Sub Division under Vapi Rural Division .				
(A) CAPITAL WORK LABOUR RATES FOR FY 2024-25 (WITHOUT GST)					
Sr No.	Description	UNIT	Qty	RATE	TOTAL
1	Providing of Wooden Drum for insulated Conductor (Minimum 3Km Coated Conductor Per Drum)	Nos.			
2	Providing of XLPE+ UV coating on 55 sq mm conductor (thickness 1.2 mm) including Labour charge.	Mtr.			
	TOTAL A TO D				30,00,000.00
	TOTAL ESTIMATE-THIRTY LAKH Only				

Note :- All Rates are Excluding of GST.

Executive Engineer (O&M),
D.G.V.C.L.,Vapi Rural Division.

1. DGVCL will provide key material like M.S. materials,ABC/Bare conductors,PSC/RSJ Poles,Insulators,Fabricated materials etc. to the contractor.2.All fabricated items shall be fabricated as per DGVCL approved drawing and by welding rods confirming to the relevent ISI specification and as directed by Engineer in charge.3.Necessary electricity connection for fabricatated items shall be provided by DGVCL on payment of required charge for connection & electricity bill of the same shall be paid by the agency.4.All the rates are inclusive of PF and Exclusive of GST applicable time to time.5.All steel material are to be painted as below:(a) Scrubbing of rusted surface properly before applying the paints on to the RSJ poles & steel fabricated materials of RSJ/PSC poles is must required.(b) Two coats of approved ISI mark red oxide (primer) is to be properly painted for the RSJ poles & steel fabricated materials of RSJ/PSC poles. (c) Two coats of approved ISI mark silver paint (i.e. triple mangoes or equivalent quality silver paint) is to be properly painted on to the RSJ poles &