

**ERECTION OF HT LT & TC WORK AT VARIOUS VILLAGE OF ND,VKY-2 & VARIOUS SCHEME  
UNDER DAHOD RURAL 2 S/DN UNDER DAHOD DIVISION PURCHASE REQUISITION 225614**

Line No.	Item Code	Item Description	Category	UOM	Quantity	Price (INR)	Amount (INR)
1	9901000001	TAPPING FROM EXISTING HT POLE	99.01	Number	40	511	20440
2	9902010001	ERECTION OF PSC POLE 8 MTR	99.01	Number	150	1225	183750
3	9902010001	ERECTION OF PSC POLE 8 MTR	99.01	Number	150	1207	181050
4	9902010003	ERECTION OF RSJ 8 TO 10 MTR POLE	99.01	Number	20	1949	38980
5	9902010006	ERECTION OF SUPPORT POLE - PSC POLE	99.01	Number	10	735	7350
6	9902010007	ERECTION OF SUPPORT POLE - RSJ POLE	99.01	Number	10	735	7350
7	9902020001	ERECTION OF DP STRUCTURE USING PSC POLE WITHOUT HG FUSE/AB SWITCH	99.01	Number	15	2920	43800
8	9902020007	ERECTION OF DP STRUCTURE USING 9 MTR RSJ POLE WITHOUT HG FUSE/AB SWITCH	99.01	Number	8	3891	31128
9	9902020006	ERECTION OF DP STRUCTURE USING PSC POLE WITH DO FUSE & AB SWITCH	99.01	Number	10	3533	35330
10	9902030001	ERECTION OF XMER CENTRE COMPLETELY EXCLUDING GUY & EARTHING FOR 25 KVA XMER USING PSC POLES	99.01	Number	20	9785	195700
11	9902020012	ERECTION OF DP STRUCTURE USING 9 MTR RSJ POLE WITH DO FUSE & AB SWITCH	99.01	Number	10	4525	45250
12	9902030012	ERECTION OF XMER CENTRE COMPLETELY EXCLUDING GUY & EARTHING FOR 200 KVA XMER USING RSJ 11 MTR POLES	99.01	Number	10	11320	113200
13	9902040001	ERECTION OF GUY SET	99.01	Number	100	576	57600
14	9905010001	CONCRETING/MUFFING OF POLE,GUY ETC INCLUDING COST OF CEMENT,SAND,METAL(1:3:6) & WATER AS PER STD SPECIFICATION.	99.01	Cubic Meter	10	7445	74450
15	9902040002	ERECTION OF COIL TYPE EARTHING	99.01	Number	150	788	118200
16	9903000001	STRINGING OF 30/34/50/55 MM2 CONDUCTOR FOR 11/22 KV & LT LINE INCLD FIXING OF INSULATORS,ETC	99.01	Kilo Meter	15	2141	32115
17	9903000002	STRINGING OF 100 MM2 CONDUCTOR FOR 11/22 KV & LT LINE INCLUDING FIXING OF INSULATORS,BINDING,JUMPERING ETC	99.01	Kilo Meter	5	5004	25020
18	9903000006	STRINGING OF LT AERIAL BUNCH CABLE 4 WIRE [ALL SIZE]	99.01	Kilo Meter	15	24057	360855
19	9903000005	STRINGING OF LT AERIAL BUNCH CABLE CABLE 2 WIRE (ALL SIZE) INCLUDING BINDING AND JUMPERING	99.01	Kilo Meter	2	9625	19250

20	9903000007	STRINGING OF HT AERIAL BUNCH CABLE 3 WIRE [ALL SIZE]	99.01	Kilo Meter	2.5	48117	120292.5
21	9906000001	PROVIDING GUARDING TO LT LINE ON ROAD/RAIL CROSSING	99.01	Meter	50	103	5150
22	9906000002	PROVIDING GUARDING TO HT LINE ON ROAD/RAIL CROSSING	99.01	Meter	50	103	5150
23	9901000002	TAPPING FROM EXISTING LT LINE SINGLE PHASE	99.01	Number	10	51	510
24	9901000003	TAPPING FROM EXISTING LT LINE THREE PHASE	99.01	Number	20	93	1860
25	9907000005	DISMANTLING OF MS GIRDER POLE 9 MTR. LONG INCL. CREDITING IN STORE.	99.01	Number	4	974.5	3898
26	9907000002	DISMANTLING OF PSC POLE INCLUDING CREDITING IN STORE.	99.01	Number	8	581.5	4652
27	9907000009	DISMANTLING OF LT CONDUCTOR FROM LINE INCL. CREDITING TO STORE	99.01	Kilo Meter	5	1055.5	5277.5
28	9907000012	DISMANTLING OF DP STRUCTURE OF PSC POLE 8 TO 13 MTR. LONG. INCL. CREDITING IN STORE.	99.01	Number	10	1696	16960
29	9907000013	DISMANTLING OF DP STRUCTURE OF RSJ POLE 8 TO 13 MTR. LONG. INCL. CREDITING IN STORE.	99.01	Number	5	2156	10780
30	9907000025	Dismantalling of Aerial Bunch Cable	99	Kilo Meter	5	12029	60145
31	9907000025	Dismantalling of Aerial Bunch Cable	99	Kilo Meter	6	4812.5	28875
32	9909000001	CARTING OF PSC POLES AT DESTINATION	99.01	Number	20	378	7560
33	9909000006	CARTING OF RSJ POLES AT DESTINATION	99.01	Number	20	536	10720
34	411000071	HEAT SHRINKABLE TYPE CABLE JOINTING KIT SUITABLE FOR 11 KV 1C x 95 SQMM AB CABLE FOR OUTDOOR TERMINATION APPLICATION	0	Number	10	2333	23330
37	9908000002	REPLACEMENT OF 11 KV PIN INSULATOR & BINDING.	99.01	Number	20	52	1040
38	9911000229	PIN BINDING OF 11KV/22KV PIN INSULATOR	99	Per Pol	30	47	1410
39	9911000230	PIN BINDING OF LT LINE PIN OR SHACKLE INSULATOR	99	Per Pol	30	47	1410
40	9908000166	REPLACEMENT OF LT PIN/SHACKLE INSULATOR ONLY	99	Number	51	37	1887
41	9908000001	REPLACEMENT OF V X ARM/LT X ARM INC. PAINTING & TRANSPORTATION	99.01	Set	40	244	9760
42	9908000051	REPLACEMENT OF TOP FITTING	99.01	Number	60	60	3600
43	9908000001	REPLACEMENT OF V X ARM/LT X ARM INC. PAINTING & TRANSPORTATION	99.01	Set	21	73	1533
44	9908000011	REPLACEMENT OF 100 KVA (OR LESS THAN 100 KVA)) DIST. BOX COMP. INCL. TRANSPORTATION AS PER SPECIFICATION.	99.01	Number	20	1224	24480
45	9913000016	WIDENING & REFILLING WITH EARTH PER MTR	99.01	Meter	20	44	880

46	9913000038	Laying/Relaying of cable in Cable trench & from ground level to pole structure for providing outdoor cable joints.	99	Meter	35	60	2100
47	9913000039	Laying / Relaying XLPE/PILC cable by digging of pits, removal of old cable and laying of new cable on sand bad (The cable should be laid on bed of sand and to cover cable with half round RCC pipe 6" internal dia and length of one meter along with each bottom and top.) The entire trench there after should be refilled with earth dully rammed up to ground level	99	Meter	30	148	4440
48	9913000041	Charges for digging of tar road for laying of cables over and above digging of pit in normal soil	99	Meter	30	50	1500
49	9913000036	EXCAVATION OF TRENCH FOR SINGLE CABLE BY PROVIDING HALF ROUND RCC PIPE 6" LAYING OF RCC HUME PIPE 6" PER MTR.(The cable should be laid on bed of sand and to cover cable with half round RCC pipe 6" internal dia and length of one meter along with each bottom and top.) The entire trench there after should be refilled with earth dully rammed up to ground level	99	Meter	30	109	3270
50	9908000169	"PROVIDING D.O.FUSE OR A.B.SWITCH ON DP ( FOR ONE SET) WITH FABRICATION &	99	Number	20	856	17120
51	9911000057	INSTALLATION OF ENERGY METER,MM BOX ETC ON T/C	99.01	Number	10	793	7930
52	9911000001	NUMBERING OF POLE WITH MATERIAL	99.01	Number	50	60	3000
53	9902040007	ERECTION/PROVIDING LIGHTENING ARRESTOR	99.01	Number	25	123	3075
54	9911000007	REPAIRING/ADJUSTING TENSION OF EXISTING GUY/STAY SET INCLUDING PROVIDING/REPLACEMENT OF STAY INSULATOR	99.01	Number	28	183	5124
55	9911000002	PLUMBING/STRAIGHTENING OF PSC POLE	99.01	Number	20	312	6240
56	9902040009	EXTRA LABOUR CHARGES FOR ERECTION OF STAY IN HARD MURRUM/SOFT ROCK	0	Number	20	370	7400
57	9902040008	EXTRA LABOUR CHAGES FOR ERECTION OF POLE/GIRDER IN HARD MURRUM/SOFT ROCK	0	Number	20	370	7400
58	9902040010	EXTRA CHARGES FOR ERECTION OF EARTHING IN HARD MURRUM/SOFT ROCK	0	Number	20	370	7400
59	9911000224	RE-STRINGING OF 11KV A.B.CABLE (ALL SIZE)	99	Per Span	10	389	3890
60	9903000004	RESTRINGING OF ACSR/AAC SPAN	99.01	Kilo Meter	10	307	3070
61	9908000003	REPLACEMENT OF 11 KV DISC INSULATOR WITH H/W AS PER SPECIFICATION.	99.01	Number	10	159	1590
62	9903000004	RESTRINGING OF ACSR/AAC SPAN	99.01	Kilo Meter	50	111	5550

63	9911000009	CUTTING/TRIMMING OF TREE BRANCHES	99.01	Number	50	60	3000
64	9904010002	PROVIDING SINGLE PHASE SERVICE CONNECTION WITH PVC CABLE FROM TERMINAL POLE TO METERING POINT COMPLETELY	99.01	Number	100	397	39700
65	9904010001	PROVIDING THREE PHASE FOUR WIRE SERVICE CONNECTION WITH PVC CABLE FROM TERMINAL POLE TO METERING POINT COMPLETELY	99.01	Number	50	546	27300
66	9902050001	ERECTION OF CABLE JOINT FOR PILC CABLE (STRAIGHT/INDOOR/OUTDOOR)	99.01	Number	10	2229	22290
67	9902050002	ERECTION OF CABLE JOINT FOR XLPE CABLE (STRAIGHT/INDOOR/OUTDOOR)	99.01	Number	10	2750	27500
68	411000006	11 KV OUTDOOR CABLE BOX FOR 185 SQMM XLPE CABLE	2	Number	10	1073	10730
69	411000015	11 KV INDOOR CABLE BOX FOR 185 SQMM XLPE CABLE	2	Number	15	1445	21675
70	413000020	11KV STRAIGHT THROUGH JOINT FOR 185 SQMM XLPE CABLE	0	Number	15	3186	47790
71	9907000025	Dismantalling of Aerial Bunch Cable	99	Kilo Meter	3	22554	67662
72	9903000009	Un-Bundling of HT ABC 95/70 SQMM	99	Kilo Meter	3	12029	36087
74	9902030026	PROVIDING (PAINTING/MARKAR ) CONSUMER No ON SMC/MMB - Urban	99	Number	100	72	7200
75	9908000023	REPLACEMENT OF SINGLE PHASE METER WITH PROPER FITTING.	99.01	Number	90	98	8820
76	9911000222	FIXING OF SMC (1-Ph) AT CONSUMER INSTALLATION ( INCLUDING COST OF FASTNERS)	99	Number	28	98	2744
77	9911000223	FIXING OF SMC (3-Ph) AT CONSUMER INSTALLATION ( INCLUDING COST OF FASTNERS)	99	Number	18	148	2664
78	9902050002	ERECTION OF CABLE JOINT FOR XLPE CABLE (STRAIGHT/INDOOR/OUTDOOR)	99.01	Number	5	3258	16290
79	9902050002	ERECTION OF CABLE JOINT FOR XLPE CABLE (STRAIGHT/INDOOR/OUTDOOR)	99.01	Number	5	3957	19785
80	9908000453	Straightening of tilted PSC/RSJ Pole at tension point	99.01	Number	20	329	6580
81	9908000454	Straightening of tilted D.P. Set (PSC / Girder pole) etc with refilling of stones, morum etc.	99.01	Number	24	810	19440
<b>Total</b>						<b>Total</b>	<b>2419334</b>

The bidder shall quote FIRM PRICES only. The prices quoted will not be subject to any escalation till completion of work.

The above prices are inclusive of all taxes, levies Duties etc. except Goods & Service tax (GST). GST will be paid extra as applicable from time to time on a given taxable goods and/or services.

**NOTE: Work for any Sub Division within the jurisdiction of Dahod division.**

Signature of authorized Representative  
of Company / Agency

Name\_\_\_\_\_

Status\_\_\_\_\_

SEAL & SIGNATURE  
OF BIDDER

Name of bidder Company / Agency