

## **SCHEDULE – B**

**Subject:** - Providing & Fixing of FRP Fencing around Distribution Transformers center in all schemes at various locations of village under jurisdiction of Dharampur-1 Sub Division under Dharampur division.

<b>Sr. No.</b>	<b>Item Description</b>	<b>Rate in Rs.</b>	<b>Unit</b>	<b>Amount in Rs.</b>
<b>1</b>	Providing and fixing of FRP fencing of 1500 mm height at Distribution Transformer Centers with necessary excavation, concreting for grouting vertical posts up to 450 mm in ground, Hardware, accessories, fittings, lock, etc. complete as shown in specifications and drawing enclosed. The fencing shall comprise of one gate 2000 mm wide having two flaps and payment for the same shall be measured on RMT basis	<b>3000/</b>	<b>RMT</b>	
<b>2</b>	Inside fencing area to be levelled properly first by compaction above road level and then finished with 6" thick 1:2:4 cement concrete & cement plaster supported with 6" bricks wall on surrounding (material to be utilized Cement Bags, Bricks, Sand and Aggregates).	<b>81/</b>	<b>Sq.ft</b>	
	In words Rupees Thirty Lakh only.	<b>Total Amts.Rs.</b>		<b>30,00,000/-</b>
	GST Extra as per applicable and Govt rules.			

- Rate includes providing & fixing fencing at site.
- Tax if any should be mentioned separately.
- All accessories i.e. Nut, Bolt, washers shall be Galvanized.
- Generally the color of fencing shall be grey/white.
- Total running meter of the Tender quantity includes Two running meter (6') per gate per distribution Transformer is considered.
- It should be provided as per the instruction of concern in-charge engineer of Respective S/Dn.
- The tentative estimated quantity is considered 12.20 RMT (40Run.ft.) per distribution Transformer center which includes 2 RMT of shutter.
- It is to be carried out as per the drawing.
- Length of fencing around transformer may be varies as per site condition.
- Rates quoted by Bidder has to be on percentage above or below the estimated rates specified.
- The rates quoted by bidder will be exclusive of GST but inclusive of all other taxes as applicable. Any escalation in rate of GST during the tenure of the contract will be paid by DGVCL as part of statutory variation.

**CONTRACTOR SIGNATURE**

**EXECUTIVE ENGINEER (O&M)  
DGVCL, DHARAMPUR DIVISION**