

SURAT MUNICIPAL CORPORATION
New East Zone(Sarthana)

NAME OF WORK :- ITEM RATE TENDER FOR PREPARATION OF ARTIFICIAL PONDS INCL. EXCAVATION, LAYING OF HDPE SHEET, BANNERS, SUPPLY OF MACHINERY & MANPOWER ETC. FOR DASHAMA VISARJAN & GANESH VISARJAN - 2026 IN NEW EAST ZONE(SARTHANA), SURAT.

SCHDULE-B					
SR.NO	ITEM	QUANTITY	UNIT	QUATED RATE (Without GST)	AMOUNT
1	Excavation for foundation includ.sorting out & Stacking of useful materials & disposing of the excavated stuff upto 50 mt. Lead & all lift, Watering etc. Comp.(A) Loose or Soft soil				
	(A)Up to 1.5 M.t depth	1300	CM		
	(B)1.5 to 3.0 M.t depth	1000	CM		
2	Dressing of Earthwork (Black Cotton Soil) in the excavated pond including leveling, spreading, removing etc.	2650	SM		
3	Providing & Laying of HDPE Impervious Geomembrane 500 micron sheet (420 GSM, Black Color, 0.9 gm/CM, Woven Fabric) having properties like Chemical resistant, Free of leachable additives, Resistant to ultraviolet Degradation including welding, jointing, soldering etc. complete as per the instructions of Engineer in charge.	2650	SM		
4	Providing, Supplying and laying of 200 mm. thick compacted sand bags and placing it in position as instructed by engineer in-charge.	11500	Nos.		
5	Providing Crane on Artificial pond site (With Capacity) (A) 16 Tonne incl. all charges of Transport and Operator as per instruction of Engineer in charge.	200	hrs.		
6	Providing MS Platform on Artificial pond site (size 2 X 2 m) having frame MS C Chnells and Top made out of MS Sheets, capable of carrying 3 Tons of Load as per instruction of Engineer in charge.	9	Nos.		
7	Filling in trenches with available excavated earth in layer not exceeding 20 cm in depth consoildating each deposited layer by ramming & watering instruction of Engineer in charge.	2300	CM		
8	Labours/Majdurs for Immersion and Shifting of Ganesha Idols (shift = 8 hrs.)	1600	No./Shift		
9	Providing and fixing of flex signage made with flex frontlet board 240GSM/350 Micron thickness of normal quality using solvent printing. The graphic size is to be cross checked with the area available before printing.				
	A. Without Frame	2500	Sqft		
	B. With Frame of 1" * 1" MS Pipe Frame	3500	Sqft		
10	Carting and hauling of excavated soil for distance upto 1 km. to 2 km.	1200	CM		
11	Providing hiwa on Artificial pond site with Operator as per instruction of Engineer in charge.				
	1) MGV-4 CUMT	500	hrs.		
	2) HGV-8 CUMT/HIWA	6000	hrs.		
12	Providing JCB 3D/4CXL/BEML/HM or Equivalent on Artificial pond site with Operator as per instruction of Engineer in charge.	80	hrs.		
Total					

SIGNATURE OF THE CONTRACTOR.

**EXECUTIVE ENGINEER
NEW EAST (SARTHANA) ZONE
SURAT MUNICIPAL CORPORATION**