

SURAT MUNICIPAL CORPORATION

NEW EAST(SARTHANA) ZONE

NAME OF WORK:- DESILTING AND CLEANING OF SEWER DRAINAGE MACHINEHOLE OF EXISTING DRAINAGE LINE IN DIFFERENT SOCIETY TPS NO. 27 (UTRAN-KOSAD), TPS NO. 73 (UTRAN), TPS NO. 86 (KOSAD), BHARTHANA, UMRA AND GOTHAN(REST PART OF RAILWAY) IN NEW EAST (SARTHANA) ZONE, SURAT (3rd Attempt)

SR. NO.	ITEMS	QTY.	RATE Rs.	PER	AMOUNT
					Rs.
1	Desilting of garbage, rubbish, clay, silt, grit, industrial waste and any kind of waste from wet sump, screen chamber, inlet chamber etc of drainage pumping stations/ sewage treatment plants of any size and shape up to 3.00 mt. depth from G.L.by any means in dry or wet conditions in different areas of surat city as directed by the Engineer in charge including stacking and disposing of the desilted materials and other waste materials brought from silt chamber wet sumps, screen chamber etc. as per instruction and strictly directed by the Engineer in charge including dewatering required if any and taking all necessary precautions and safely measures against accident hazards such as test for gases, safety belt, breathing apparatus with air cylinder / blow man"s breathing apparatus with blower , dry cells, torches generating set for lighting in side the areas etc. complete as directed during day.	5121.00	298.00	CM	1526058.00
1 b	Desilting of garbage, rubbish, clay, silt, grit, industrial waste and any kind of waste from wet sump, screen chamber, inlet chamber etc of drainage pumping stations/ sewage treatment plants of any size and shape 3.10 MT. to 6.00 mt. depth from G.L. by any means in dry or wet conditions in different areas of surat city as directed by the Engineer in charge including stacking and disposing of the desilted materials and other waste materials brought from silt chamber wet sumps, screen chamber etc. as per instruction and strictly directed by the Engineer in charge including dewatering required if any and taking all necessary precautions and safely measures against accident hazards such as test for gases, safety belt, breathing apparatus with air cylinder / blow man"s breathing apparatus with blower , dry cells, torches generating set for lighting in side the areas etc. complete as directed during day.	1675.00	381.00	CM	638175.00
1 c	Desilting of garbage, rubbish, clay, silt, grit, industrial waste and any kind of waste from wet sump, screen chamber, inlet chamber etc of drainage pumping stations/ sewage treatment plants of any size and shape 6.10 MT. and more depth from G.L by any means in dry or wet conditions in different areas of surat city as directed by the Engineer in charge including stacking and disposing of the desilted materials and other waste materials brought from silt chamber wet sumps, screen chamber etc. as per instruction and strictly directed by the Engineer in charge including dewatering required if any and taking all necessary precautions and safely measures against accident hazards such as test for gases, safety belt, breathing apparatus with air cylinder / blow man"s breathing apparatus with blower , dry cells, torches generating set for lighting in side the areas etc. complete as directed during day.	50.00	452.00	CM	22600.00
TOTAL AMOUNT				RS.	2186833.00

Junior Engineer
New East (Sarhana) Zone
Surat Municipal Corporation

Deputy Engineer
New East (Sarhana) Zone
Surat Municipal Corporation

Executive Engineer
New East (Sarhana) Zone
Surat Municipal Corporation