

Surat Municipal Corporation					
South Zone - A (Udhna)					
Name of Work :- Item rate Tender for Repairing, Maintenance and Renovation of Carpentry works at Various Municipal Properties of South Zone - A (Udhna) , Surat.					
Schedule - B					
Sr. No.	Description	Approx Qty.	Unit	Rate (Without GST)	Amount (Without GST)
1	Providing & fixing Powder Coated Aluminium partly glazed and partly panelled partition using medium duty sections of Hindalco, Zindal, Narmada, Banco or Equivalent approved make having section 63.50 mm x 38.10mm (Frame-758 kg/rmt & Middle section- 0.819 Kg./rmt), Galzing Clip with 5 mm thick clear float glass of approved make including all other necessary fittings and fixtures. Entire work will have to be made water proof using necessary rubber sectioned wherever required. Gaps all round the frame to be filled with approved water proof sealant. Bottom portion of doors both side to be covered with 12mm thick prelaminated particle board of approved make and quality and as per design.	250.00	Sq.Mt.		
2	Providing & fixing partly panel & partly glass Powder Coated Aluminium doors with aluminium section of Hindalco, Jindal , Narmada,Banco or Equivalent approved make having Poder Coated outer frame Leg Partition section of 63.50 mm x 38.10 mm having weight 1.158 kg. / R.M. shutter section having size 83.5 mm x 44.45mm (top & bottom: 1.384 kg./rmt. and middle 1.139 kg./rmt.) door vertical 47.62mm x 44.45 mm (vertical:0.881 kg./rmt. & top hing side:0.974 kg./mt.), Glazing Clip (Jindal Section No. 19370 Wt. 0.109 Kg./ Mt.) with 5mm thick sheet glass in acid frogting and 12 mm thick prelaminated sheet of Greenlam, Panama or archid make as approved by Engineer-incharge including fixing brass pivot, handle, lock etc. complete.	100.00	Sq.Mt.		
3	Providing & Fixing window having extruded aluminium colour powder coated / colour anodize section frame main outer size 63.50 X 38.10 X 1.95 mm (of jindal section no.: 4605,@ Wt. 1.094Kg/mt.) horizontal Two track member size 61.85 mm X 31.75 mm X 1.20 mm (of jindal section no : 8687, @ Wt. 0.695 Kg/mt.) vertical member of size 61.85 mm X 31.75mm X 130mm (of jindal section no : 8758 @ wt. of 0.659 Kg/mt.) with sliding shutters of horizontal member size 40 mm X 18 mm X 1.29 mm (of jindal section no.:8947, @ Wt. of 0.456 Kg/mt/section 8948, @ Wt. of 0.457 Kg/mt) with 5 mm thick transparent silicon sealant glass fixing to frame as per details etc.	50.00	Sq.Mt.		
4	Providing & Fixing window having extruded aluminium colour anodize section frame main outer size 95 mm X 24 mm X 1.17 mm (of jindal section no.: 2459,@ Wt. of 0.738 Kg/mt.) horizontal Three track member size 92 mm X 31.75 mm X 1.30 mm (of jindal section no : 8688, @ Wt. 1.07 Kg/mt.), vertical member of size 92 mm X 31.75mm X 1.50mm (of jindal section no : 8933 @ wt. 1.06 Kg/mt.) with sliding shutters of horizontal member size 40 mm X 18 mm X 1.29 mm (of jindal section no.:8949, @ Wt. of 0.456 Kg/mt/) with 5 mm thick transparent bronze colour tinted float glass with powder coated aluminium fittings & fixtures and transparent silicon sealant glass fixing to frame as per details etc.	200.00	Sq.Mt.		

Sr. No.	Description	Approx Qty.	Unit	Rate (Without GST)	Amount (Without GST)
5	Providing and fixing standard extruded of aluminium section of size 61 x 37.0 x 0.90 mm (of Jindal section no.14080, @ Wt. 0.471 Kg per mt) with colour powder coated aluminium frame for Louvered Glass ventilation with 4 mm thick Figured glass as details etc. complete for ventilation.	20.00	Sq.Mt.		
6	Providing & Fixing Panels -12mm thick Indian Gypsum panels of saint Gobin Brand, screwed to G.I. gram at 200mm c/c, frame G.I. frame fabrication with 60 X 26 X 0.5mm perimeter channels as required, 155 X 5 X 0.55mm intermediate channel at 1220mm c/c, 25 X 10 X 0.55mm ceiling angle at 1220 mm C/C, securely fixed soffit hangers at 1220mm c/c, false ceiling angle shall not at more than 610 mm from adjan wall connecting clips, etc, as required complete as per manufacture specifications, joints all joints of panels field and finished with indian gypsum, jointing compound, Joining Tapes, etc. Complete including scaffolding as required complete in all respects by engineer in charge.	250.00	Sq.Mt.		
7	Supply & Fixing of 16mm.th.Armstrong classic Lite square edge mineral fiber ceiling with 24mm grid(local) G.I. Frame grid consist of 600mm x 600mm. tecno grid pre coated main runner 38x 24 x3600 mm, cross T 30x24x1200mm,cross runner 24x24x600mm,wall Angle 24 x 24 mm. required length suspension wire of 2.50mm G.I. and necessary hardware etc. comp.approved by engineer-in-charge	50.00	Sq.Mt.		
8	Supply & Fixing of 06mm.th.Textured E board ceiling with 24mm grid (local) G.I. Frame grid consist of 600mm x 600mm. tecno grid pre coated main runner 38x 24 x3600 mm, cross T 30x24x1200mm,cross runner 24x 24x600mm, wall Angle 24 x 24 mm. required length suspension wire of 2.50mm G.I. and necessary hardware etc. comp.approved by engineer-in-charge	600.00	Sq.Mt.		
9	Providing And applying plaster of paris on wall 12mm to 18mm thick in line and vertical plumb using good quality plaster of paris powder. The undulations of the existing surface would be levelled. The surface would be made absolutely smooth and even as per the architects instructions and drawing complete.	300.00	Sq.Mt.		
10	Providing & Fixing 35mm thick shutters for doors, windows, and clearstorey windows including anodised aluminium hinges with necessary screws (A) Indian teak wood				
	(1) Fully panelled	90.00	Sq.Mt		
	(2) Fully glazed	60.00	Sq.Mt		
	(3) Partly panelled and partly glazed	45.00	Sq.Mt		
11	Providing & Fixing flush door shutters first class hardwood with crossband and face veneer or plywood face panels, teakwood edge bidding including anodised aluminium butt hinges with necessary screws				
	(A) Non - decorative type and block board core anodised aluminium butt hinges in flush door shutters:	45.00	Sq.Mt.		
	(B) Decorative type with both side 1mm th. laminate finish and block board core anodised aluminium butt hinges in flush door shutters:	45.00	Sq.Mt.		
12	Repairing & servicing of existing door/window including cost of hardware (Fevicol, Nail and NF screw etc.) but excluding cost of fixtures as directed by Engineerin- charge				
	(A) Wooden door	100.00	Nos.		
	(B) Partly panelled and Partly glazed aluminium door	100.00	Nos.		
	(C) Wooden window shutter	100.00	Nos.		
	(D) Aluminium Window shutter	100.00	Nos.		
13	Providing and Replace door, Window S.S. Fixtures fix in wooden / Aluminium door - window with ISI marks as per approved by engineer in charge.				
	(A) 4" S.S. Hinge	100.00	Nos.		
	(B) 5" S.S. Hinge	100.00	Nos.		
	(C) 8" S.S. Aldraf	100.00	Nos.		

Sr. No.	Description	Approx Qty.	Unit	Rate (Without GST)	Amount (Without GST)
	(D) 10" S.S. Aldraf	100.00	Nos.		
	(E) 12" S.S. Aldraf	100.00	Nos.		
	(F) 4" S.S. Handle 4mm. Th.	100.00	Nos.		
	(G) 6" S.S. Handle 4mm. Th.	100.00	Nos.		
	(H) 4" S.S. Stopper 4mm. Th.	100.00	Nos.		
	(I) 8" S.S. Stopper 4mm. Th.	100.00	Nos.		
	(J) 6" S.S. Pavan Ankdi Heavy duty	100.00	Nos.		
	(H) Alluminium door lock	100.00	Nos.		
14	Dismantaling, Cutting & Refixing aluminium partition door Providing with necessary Hardware & Rubber gasket etc. complete as per instruction by engineer in charge.	120.00	Sq.Mt.		
15	Providing & Fixing of Bajari glass of 4 mm thick on the place of existing broken glasses with teakwood edge biding & necessary hardware materials etc. complete as per instruction by engineer in charge.	100.00	Sq.Mt.		
16	Providing & Fixing of 5mm thick clear glass fix in wooden door, window alluminium door / window partition on the place of existing broken glasses with teakwood edge biding & necessary hardware materials etc. complete as per instruction by engineer in charge.	60.00	Sq.Mt.		
17	Prov. & Fixing Glass Table Top using 08mm th. Clear glass with crystal edge & necessary hardware materials etc. complete as per instruction by engineer in charge.	60.00	Sq.Mt.		
18	Prov. & Fixing Glass Table Top using 12mm th. Clear glass with chamferd edges & necessary hardware materials etc. complete as per instruction by engineer in charge.	60.00	Sq.Mt.		
19	Providing & Fixing door closer Ozon / Dorma / Hyper / Hardwin / Godrej Alluminium body ISI brander equivalent make with necessary hardware materials etc. complete as per instruction by engineer in charge.	105.00	Nos.		
20	Providing & Fixing floor spring make Hyper / Hardwin / Godrej / Ozon / Dorma equivalent ISI make with necessary hardware materials complete as per instruction by engineer in charge.	40.00	Nos.		
21	Providing & Fixing 2.50mm thick PVC sheet fix on wooden door inside use SR adhesive, brass Nail & necessary hardware materials complete as per instruction by engineer in charge.	60.00	Sq.Mt.		
22	Providing & Replacing of existing gypsum board false ceilling at broken false ceilling using with 12mm th. India gypsum board, screw, joining tap, powder etc. complete as per instruction by engineer in charge.	90.00	Sq.Mt.		
23	Dismantalling doors, windows vantilators etc. (wood of steel) shutters inclu. Chowkhats, architraves,holdfasts, and other attachment etc.comp. and stacking then within all lead and lift (1) not exceeding 3 sq. mt. in area.	150.00	Nos.		
24	Desmentalling doors, windows vantilators etc. (wood of steel) shutters inclu. Chowkhats, architraves,holdfasts, and other attachment etc.comp. and stacking then within all lead and lift (1) exceeding 3 sq. mt. in area.	150.00	Nos.		
25	Desmentalling Partition, False Ceiling, Loft Shutter (wood, PVC or steel) shutters inclu. Chowkhats, architraves, holdfasts, and other attachment etc.comp. and stacking then within all lead and lift	150.00	Sq.Mt.		
26	Providing & Fixing water proof plywood (ISI marks 710grade) at the door, window and any space in the building. necessary hardware, serews materials etc. complete as per instruction by engineer in charge.				
	(A) 6 mm.	100.00	Sq.Mt.		
	(B) 9 mm.	100.00	Sq.Mt.		
	(C) 12 mm	100.00	Sq.Mt.		
	(D) 16 mm.	100.00	Sq.Mt.		
	(E) 19 mm.	100.00	Sq.Mt.		
	(F) 12mm BSL partical board green or Equalent make	100.00	Sq.Mt.		
	(G) 12mm plan E board Evrest or Equalent make	100.00	Sq.Mt.		

Sr. No.	Description	Approx Qty.	Unit	Rate (Without GST)	Amount (Without GST)
27	Providing & Fixing laminated sheet 1mm thick Suede Finished as per approved make with & necessary adhesive, hardware materials etc. complete as per instruction by engineer in charge.	50.00	Sq.Mt.		
28	Prov. & Fixing Laminated Door of Marble / wall storage shutter with teakwood frame using with 19mm th. BWP plywood, 1mm th. SF laminate, teakwood edge bidding, ss handles, hinges, magnate, lock & necessary hardware, serews materials etc. complete as per instruction by engineer in charge.	50.00	Sq.Mt.		
29	Prov. & Fixing Mortise Lock body with 70mm cylinder (make Godrej / Ozon / Inox) fix in wooden door with necessary hardware materials etc. complete as per instruction by engineer in charge.	50.00	Nos.		
30	Prov. & Fixing D type SS Mortise handle fix in wooden door with necessary hardware materials etc. complete as per instruction by engineer in charge. make Godrej / Ozon / Innox	50.00	Nos.		
31	Renovation of Laminated wooden storage using with Laminate, teakwood edge bidding, Plywood & necessary hardware materials complete as per instruction by engineer in charge.	50.00	Sq.Mt.		
32	Repairing & Servicing of existing revolving chairs with necessary hardware materials complete with all respects.	100.00	Nos.		
33	Replacement Of Revolving chair parts ISI marks with necessary hardware, serews materials etc. complete as per instruction by engineer in charge.				
	(A) P.V.C. moulded Hand rest	100.00	Nos.		
	(B) Hydraulic gas pump	100.00	Nos.		
	(C) Cushion Sheet, back with Fabric/ rexine.	100.00	Nos.		
	(D) Rubber Castor / wheels	150.00	Nos.		
34	Repairing & Servicing of M.S. Office tables using screws and necessary hardware materials complete as per instruction by engineer in charge.	110.00	Nos.		
35	Replacemets of M.S. office table parts ISI marks with necessary hardware, serews materials etc. complete as per instruction by engineer in charge.				
	(A) 20mm th. BWP Plywood top with 1mm th. laminate & teakwood edge bidding french polish finish.	50.00	Sq.Mt		
	(B) Drawer locks	50.00	Nos.		
	(C) Foot rest	50.00	Nos.		
	(D) Hinges/ handles	50.00	Nos.		
36	Repairing & Servicing of M.S. File storage using screws and necessary hardware materials complete as per instruction by engineer in charge.	50.00	Nos.		
37	Replacemets of M.S. file storage parts ISI marks with necessary hardware, serews materials etc. complete as per instruction by engineer in charge.				
	(A) Locks	50.00	Nos.		
	(B) Handles	50.00	Nos.		
38	Repairing & Servicing of Wooden Office Table / File storage using screws and necessary hardware materials complete as per instruction by engineer in charge.	50.00	Nos.		
39	Replacemets of Wooden Office Table / File storage parts ISI marks with necessary hardware, serews materials etc. complete as per instruction by engineer in charge.				
	(A) Drawer / Shutter Locks	100.00	Nos.		
	(B) SS 4" D Handles	100.00	Nos.		
	(C) Drawer Chanel	100.00	Nos.		
	(D) SS 3" Heavy Hinges	100.00	Nos.		
40	Providing & Fixing 4mm th. Natural veneer as per approved make with & necessary adhesive, hardware materials etc. complete as per instruction by engineer in charge.	15.00	Sq.Mt.		
41	Providing & laying commercial white marble for storage at all floor level, over 16mm av. Th. Base of C.M. 1:6 (1 cement : 6sand) laid over & joined with grey cement slurry incl. rubbing & polishing etc. comp. at all floor	15.00	Sq.Mt.		

Sr. No.	Description	Approx Qty.	Unit	Rate (Without GST)	Amount (Without GST)
42	Providing & laying Black granite with crystal edge at window sill all floor level, over 16mm av. Th.Base of C.M. 1:6 (1 cement : 6 sand) laid over & joined with grey cement slurry incl. Rubbing & polished comp. at all floor	15.00	Sq.Mt.		
43	Prov. & Fixing E board flush partition with aluminium pipe frame using 2.50" X 1.50" Sq. tube aluminium pipe Weight 0.650 Kg permt.), 09mm th. Plan evrest make eboard & necessary hardware material etc. complete in all respects by engineer in charge.	15.00	Sq.Mt.		
44	Prov., Making & Fixing wooden Door with 4" X 2" teakwood frame using 06mm th. BWP plywood, 01mm th. laminate, 3" X 1.5" teakwood shutter, 5mm th. acid frosted glass, mortise lock with ss D type mortise handle, 5" ss hinges, door closer & necessary hardware materials etc. complete as per your instruction and drawings details.	15.00	Sq.Mt.		
45	Prov. & fix. Wooden office table with all outer and all visible surface covered by 1mm th SF laminate finish using 18mm th. Vertical, horizontal and shutter, 12mm th. Back drawer, 06mm th. Drawer bottom commercial plywood approved make, 01 mm th. Sf. Finish laminate , teakwood liping, brass hinges, SS handle, lock abco make drawer chanel and powder coated key board, magnate & necessary hardware materials etc. inside and liping french polish finish complete in all respects by engineer in charge.	10.00	Sq.Mt.		
46	Prov. & fix. Wooden office table with all outer & inner plywood surface covered by 1mm th. laminate finish using 18mm th. Vertical, horizontal and shutter, 12mm th. Back drawer, 06mm th. Drawer bottom commercial plywood approved make, 01 mm th. Sf. Finish laminate , 8mm th. Back painted glass top, teakwood liping, brass hinges, SS handle, lock abco make powder coated key board, magnate & necessary hardware materials etc. inside and liping french polish finish complete in all respects by engineer in charge.	10.00	Sq.Mt.		
47	Prov. & Making Side Credenza using saras make commercial plywood, all outer and all visible surface covered by 1mm th. SF Laminate using 18mm th. Vertical, horizontal and shutter, 12mm th. Back drawer, 06mm th. Drawer bottom commercial plywood approved make, 01 mm th. Sf. Finish laminate , 8mm th. Back painted glass top, teakwood liping, brass hinges, SS handle, lock abco make drawer chanel, magnate & necessary hardware materials etc. inside and liping french polish finish complete in all respects by engineer in charge.	10.00	Sq.Mt.		
48	Prov. & Making Side Credenza using commercial plywood, All inner and outer surface finish with 1mm SF Laminate, using 18mm th. Vertical, horizontal and shutter, 12mm th. Back drawer, 06mm th. Drawer bottom commercial plywood approved make, 01 mm th. Sf. Finish laminate , teakwood liping, brass hinges, SS handle, lock abco make drawer chanel, magnate & necessary hardware materials etc. inside and liping french polish finish & necessary hardware materials etc. complete as per drawing and instructions by engineer in charge.	100.00	Sq.Mt.		
49	Prov. & Fixing Roller type Curtain as per aprooved complete as per instructions by engineer in charge.	20.00	Sq.Mt.		
50	Prov. & Laying sun control or frosted milky glass film as per aprooved colour, design, cutting complete as per instructions by engineer in charge.	20.00	Sq.Mt.		
51	Prov. & Fixing Fabric Curtain (three fould) with SS 1" pipe, socket, PVC ring (fabric Besic rate 200/- mtr.) necessary hardware as per aprooved fabric, designe complete as per instructions by engineer in charge.	20.00	Sq.Mt.		
52	Prov. & Fix. Wooden partition with laminate finish using 3" X 1.50" teakwood frame with 600mm c/c grid, 08mm th. Commercial plywood approved make, 01 mm th. SF finish laminate, teakwood liping & necessary hardware materials etc., liping french polish finish complete in all respects by engineer in charge.	20.00	Sq.Mt.		

Sr. No.	Description	Approx Qty.	Unit	Rate (Without GST)	Amount (Without GST)
53	Prov. & Fix. Partly Glassed wooden door with laminate finish using 4" X 1.50" teakwood frame and 3" X 1.50" shutter, with 300mm c/c, 06mm th. Commercial plywood approved make 01mm th. SF finish laminate, teakwood liping, 6mm th. Acid frosted glass, SS hinges & necessary hardware materials etc. liping french polish finish complete in all respects by engineer in charge.	15.00	Sq.Mt.		
54	Prov. & Fix. Wooden wall panelling and column clading with laminate finish using 2" X 1" teakwood frame and liping, 12mm th. Commercial plywood approved make & necessary hardware materials etc. liping french polish finish complete in all respects by engineer in charge.	15.00	Sq.Mt.		
55	Prov. & Fix. Wooden file storage with openable shutter with all outer surface laminate finish using 18mm th. Vertical, horizontal and shutter, 12mm th. Back, selves commercial plywood approved make, 01 mm th. SF finish laminate, teakwood liping , SS conciled handle, sliding lock & necessary hardware materials etc. inside and liping french polish finish complete in all respects by engineer in charge.	15.00	Sq.Mt.		
56	Prov. & Fix. Wooden file storage with openable shutter with all outer and inner plywood surface covered by 1mm th. SF laminate finish using 18mm th. Vertical, horizontal and shutter, 12mm th. Back, selves commercial plywood approved make, 01 mm th. SF finish laminate, teakwood liping , SS conciled handle, sliding lock & necessary hardware materials etc. inside and liping french polish finish complete in all respects by engineer in charge.	3.00	Sq.Mt.		
57	Prov. & Fix wooden Notice board with Righting laminate board finish using 12mm th. Back commercial plywood aprooved make, 01mm th. SF finish laminate, teakwood framing & necessary hardware materials etc. inside and liping french polish finish complete in all respects by engineer in charge complete.	9.00	Sq.Mt.		
58	Prov. & Fix wooden Notice board with 12mm th. soft board and fabric finish using 12mm th. Back commercial plywood aprooved make, teakwood framing & necessary hardware materials etc. inside and liping french polish finish complete in all respects by engineer in charge complete.	9.00	Sq.Mt.		
59	Making & Providing Full Covered sofa set with handle using wooden sofa Frame, 32 dencity U foam seat back, approved fabric (Besic rate 500/- Mtr.), SS Leg & necessary hardware etc. complete as per instruction by engineer in charge.				
	(A) Three Seater (6'-9" Long)	6.00	Nos.		
	(B) Two Seater (5'-0" Long)	3.00	Nos.		
60	Providing of Three Seater wooden Banches with laminate finish using Teakwood frame, 12mm th. Plywood, laminate & necessary hardware etc. complete as per instruction by engineer in charge.	9.00	Nos.		
61	Providing & making wooden partition using 08 mm thick commercial plywood with 01 mm thick laminate, 3" Ö 1" size teakwood frame, 3" Ö 0.5" molding patti, 08 mm clear glass & necessary hardware material etc., french polish finish complete respected by drawing & engineer-in-charge.(Plywood- Saras, Kitply, Uniply, Anchor, Green, Wood Stock, Everest, Euro or Century), (Laminate - Green Laminates, Century, New Mica make) (Size H 5'-0" x W 4'-0")	15.00	SFT		
62	Providing & making wooden book display rack with storage using 18, 12, 06 mm thick commercial plywood, 01 mm thick laminate finished all shutter, teakwood patti, M S sliding bracket lock, handle & necessary hardware fitting, fixture material etc. inside french polish finish complete respected by drawing & engineer-in-charge's instructions. .(Plywood- Saras, Kitply, Uniply, Anchor, Green, Wood Stock, Everest, Euro or Century), (Laminate - Green Laminates, Century, New Mica make) (Size - H 7'-0" x W 6'-0" x D 1'-6")	150.00	SFT		

Sr. No.	Description	Approx Qty.	Unit	Rate (Without GST)	Amount (Without GST)
63	Providing & making wooden reading table using 18 mm thick commercial plywood top with 1.50" thick edge, 01 mm laminate, 3" x 3" Leg, 4" x 1.50" teakwood framing, 1.50" x 0.50" patti, 1.50" x 1.50" M S Powder coated footrest & necessary hardware material etc. french polish finish complete respected by drawing & engineer-in-charge's instructions. .(Plywood- Saras, Kitply, Uniply, Anchor, Green, Wood Stock, Everest, Euro or Century), (Laminate - Green Laminates, Century, New Mica make) (Size - H 2'-6" x L 8'-0" x W 4'-0")	135.00	Nos.		
64	Providing & making wooden cubical reading unit using 18 mm, 12 mm thick commercial plywood, 01 mm thick laminate, teakwood molding, liping, M S Powder coated footrest & necessary hardware material etc. liping patti french polish finish complete respected by drawing & engineer-in-charge's instructions. .(Plywood- Saras, Kitply, Uniply, Anchor, Green, Wood Stock, Everest, Euro or Century), (Laminate - Green Laminates, Century, New Mica make) (Size - H 4'-0" x L 8'-0" x W 5'-6")	150.00	R.FT		
65	Providing & supplying PVC chair Cello/ supreme/ Nilkamal brand by approved colour & design etc. complete in all respects.	400.00	Nos.		
Total Amount					

Sign of Contractor

Executive Engineer
South Zone -A (Udhna)
Surat Municipal Corporation