

SURAT MUNICIPAL CORPORATION					
SOUTH WEST (ATHWA) ZONE					
Tender (On Line) Notice No. Dy.Commissioner/S.W.(Athwa)Zone/No.02/2026-27					
Work no.-01					
Name of Work:- Preparation of Artificial Ponds in South West (Athwa) Zone, Surat.					
ITEM. NO	ITEM DESCRIPTION	QTY.	UNIT	RATES	AMOUNT
1	Excavation for foundation includ.sorting out & Stacking of useful materials & disposing of the excavated stuff upto 50 mt. Lead & all lift, Watering etc. Comp. Loose or Soft soil (A)Up to 1.5 M.t depth	3000.00	CM		
1.1	(B) 1.5 to 3.0 M.t depth	2000.00	CM		
2	Dressing of Earthwork (Black Cotton Soil) in the excavated pond including leveling, spreading, removing etc.	6000.00	SM		
3	Providing & Laying of HDPE Impervious Geomembrane 500 micron sheet (420 GSM, Black Color, 0.9 gm/CM, Woven Fabric) having properties like Chemical resistant, Free of leachable additives, Resistant to ultraviolet Degradation incuding welding, jointing, soldering etc. complete as per the instructions of Engineer in charge.	6000.00	SM		
4	Providing, Supplying and laying of 200 mm. thick compacted sand bags and placing it in position as instructed by engineer in-charge.	14000.00	Nos.		
5	Providing Hydra on Artificial pond site (With Capacity) (A) 18-20 Tonne incl. all charges of Transport and Operator as per instruction of Engineer in charge.	210.00	hrs.		
5a	Providing Crane on Artificial pond site (With Capacity) (A) 16 Tonne incl. all charges of Transport and Operator as per instruction of Engineer in charge.	50.00	hrs.		
6	Providing MS Platform on Artificial pond site (size 2 X 2 m) having frame MS C Channels and Top made out of MS Sheets, capable of carrying 3 Tons of Load as per instruction of Engineer in charge.	2.00	Nos.		
7	Filling in trenches with available excavated earth in layer not exceeding 20 cm in depth consoildating each deposited layer by ramming & watering instruction of Engineer in charge.	5000.00	CM		
8	Labours / Majdurs for Immersion and Shifting of Ganesha Idols	600.00	Nos.		
9	Providing and fixing of flex signage made with flex frontlet board 240 GSM / 350 Micron thickness of normal quality using solvent printing. The graphic size is to be cross checked with the area available before printing. A. Without Frame	2000.00	Sqft		
9.1	B. With Frame of 1" * 1" MS Pipe Frame	2000.00	Sqft		
10	Carting and hauling of excavated soil for distance upto 1 km. to 2 km.	4000.00	CM		
11	Providing hiwa on Artificial pond site with Operator as per instruction of Engineer in charge. (1) MGV-4 CUMT	600.00	hrs.		
11.1	(2) HGV-8 CUMT/HIWA	100.00	hrs.		
12	Providing JCB 3D/4CXL/BEML/HM or Equivalent on on Artificial pond site with Operator as per instruction of Engineer in charge.	96.00	hrs.		
TOTAL AMOUNT Rs.					
Total Rs. in Words :-					

NOTE:- Price should be fill online only.

Executive Engineer
South West (Athwa) Zone
Surat Municipal Corporation