



SURAT MUNICIPAL CORPORATION
SCIENCE CENTRE



NAME OF WORK : SUPPLY AND INSTALLATION WORK OF NEW PUSH BACK SEATS, NEW FLOOR CARPET AND POLISHING OF SIDE SURFACE MARINE PLY PATTAS AND INSTALLATION OF NEW CCTV SYSTEM AND AS PER REQUIRED OTHER WORK IN THE PLANETARIUM FOR THE PURPOSE OF THE UPGRADATION OF THE PLANETARIUM OF THE SCIENCE CENTRE LOCATED ON CITY LIGHT ROAD MANAGED BY SURAT MUNICIPAL CORPORATION, SURAT. (3rd ATTEMPT)

WORK NO.01

E- Tender

**Tender Notice (On line) No.Dy. Commissioner/ Science Centre/
No.01/ 2026 - 2027**

VOLUME-II : PRICE BID

DOWNLOAD OF TENDER DOCUMENTS FROM website smc.nprocure.com	: From Dt.25/06/2026 to Dt.04/07/2026 upto 18.00 hrs.
DATE OF PRE-BID QURIE	: Bidder shall have to post queries on Email address exen.swz@suratmunicipal.gov.in on or before Dt.30/06/2026 up to 11.00 am
LAST DATE OF SUBMISSION OF ONLINE TENDER	: On or Before Dt.04/07/2026 upto 18.00 hrs
LAST DATE OF SUBMISSION OF TENDER FEES, EMD AND OTHER DOCUMENTS IN HARD COPY	: From Dt.06/07/2026 to Dt.13/07/2026, 18.00 hrs. to Chief Accountant, SMC, Tapiपुरa, Surat-395003 by R.P.A.D./Speed Post.
Opening of technical bids (online)	: on Dt.06/07/2026, 11.00 hrs.
Opening of Price Bid (On line)	: on Dt.14/07/2026, 11.00 hrs.
ESTIMATED AMOUNT	: Rs. ----- (ITEM RATE TENDER)
E.M.D.	: Rs.1,50,000.00 Ps. (EMD should be paid. 50 % (i.e. Rs. 75,000/-) shall be in the form of crossed Demand Draft of Nationalized Bank payable at Surat and remaining 50% (i.e. Rs.75,000/-) shall be in the form of Bank Guarantee of Nationalized Bank (revocable at Surat) or 100% EMD amount shall be in form of crossed Demand Draft of Nationalized Bank payable at Surat.)
DOCUMENT FEES	: Rs.4,248.00 Ps. [Rs.3,600.00 + 18% GST i.e. Rs.648.00]
CLASS	: "Experience of Similar Works"

TENDER TO BE SUBMITTED TO:
THE CHIEF ACCOUNTANT,
SURAT MUNICIPAL CORPORATION, TAPIPURA,
SURAT – 395 003.

SURAT MUNICIPAL CORPORATION

SCIENCE CENTRE



SUPPLY AND INSTALLATION WORK OF NEW PUSH BACK SEATS, NEW FLOOR CARPET AND POLISHING OF SIDE SURFACE MARINE PLY PATTAS AND INSTALLATION OF NEW CCTV SYSTEM AND AS PER REQUIRED OTHER WORK IN THE PLANETARIUM FOR THE PURPOSE OF THE UPGRADATION OF THE PLANETARIUM OF THE SCIENCE CENTRE LOCATED ON CITY LIGHT ROAD MANAGED BY SURAT MUNICIPAL CORPORATION, SURAT. (3rd ATTEMPT)

**Tender Notice (On line) No.Dy. Commissioner/ Science Centre/ No.01/ 2026-2027.
WORK NO.01**

SCHEDULE- B

Sr. No.	ITEM	Qty.	Unit	Rate (Without GST)	Amount
	Part - A CIVIL WORK				
	A-1 Demolition Work				
1	Removing of existing Carpet.	325.00	S.M.		
2	Removing of existing Planetarium Chair.	150.00	No.		
	A-2 Finishing Work				
3	Providing and fixing 3.5 mm. thick (min.), veneer sheet of approved quality and make as approved by the Architect and Engineer-in-charge, as per the drawing, design and direction, with necessary screws, nails and glue over wooden surface etc. complete.	150.00	S.M.		
4	CLEAR PU Providing and applying ICA clear PU upto finishing (min 3 coats) including all material, labour including scaffolding etc. And and measurement of beading Patti shall be in evaluated in square meters only , including work in grooves, paint should be green and voc free ,edges etc. complete the work satisfactorily as per instruction of architect or Engineer- in charge.	150.00	S.M.		
5	Supply and fixing of Synthetic nylon heat set commercial heavy duty carpet having a pile height of 7 to 9 mm of 800-850 grammage with woven polypropylene primary backing and synthetic action back secondary backing as approved by the architect with base armour bedding etc. complete. The carpets shall be washable and shall be with fire retardant characteristics. The supplier shall give 10 years warranty for wear and tear of the carpet.	325.00	S.M.		

Sr. No.	ITEM	Qty.	Unit	Rate (Without GST)	Amount
6	Providing and fixing floor in line and level as per drawing using 19mm + 4mm neoprene pad+19 mm thick BWP marine ply as per the pattern. Edges of ply panels shall be covered with 19 mm thick Balsad teak wood beading Patti. The ply shall be cut in size and supported on the MS framing. Framing shall be as per the drawing and it may be Indian teak wood or rolled steel sections like angles, teas. Framing will be measured and paid under relevant items. Rate shall be inclusive of making cut-outs for any services. One side of the ply panels shall be coated with two coats of wood primer and other side (outside) shall be coated with two coats of wood primer and three coats of enamel paint. The rate shall include making grooves around the walls/partitions with necessary hardware such as screws, coach bolt, anchor fasteners, nut bolts, clips, etc. All the wood shall be seasoned wood and proper ant termite treatment shall be done before fixing.	10.00	S.M.		
7	ANGLE TILTED CHAIR FOR PLANETARIUM Providing and fixing of PLANETARIUM CHAIR of brand amber, merryfair, innovative, Sunon.etc.or as per selection in fabric with tilt up frame on frontal pivot the handle top will e dicasted metal welded precisely seat will be in complete dicasted frame and edgebending back will be static as per model covering whole body high the bottom portion will be connected with fastners to the floor including all components,fixing,fastners,grouting work, material, labour,and hardwares, waste of materials etc and complete the work satisfactorily as per instruction of architect or Engineer-in charge. Also providing service, repairing and maintenance of Chair with necessary parts without any extra cost within 01 (One) year warranty period.	150.00	No.		
8	Providing covers for chairs to proctect against dust.	300.00	No.		
	Part - B ELECTRICAL WORK				
9	Reparing of Automatic Hydraulic Doors with all necessary equipments (like electric panel, pneumatic valve, air cylinder, air compressor) and other accessories. Also providing service, reparing and maintenance of Automatic Hydraulic Doors without any extra cost within 01 (One) year warranty period.	2.00	No.		

Sr. No.	ITEM	Qty.	Unit	Rate (Without GST)	Amount
10	Supply, Installation, testing & Commissioning of CCTV system with all necessary equipments and accessories like camera, camera LAN switches, NVR, NVR cabinet (rack) with cooling fan, CAT 6 UTP cable & other wiring accessories etc. Make and Vendor details of CCTV system : <ul style="list-style-type: none"> • Camera :- Hikvision, Honeywell, Panasonic, Dahua, Bosch or Equivalent • LAN Switch :- D-Link, Netgear or Equivalent • NVR :- Hikvision, Honeywell, Panasonic, Matrix, Dahua, Bosch or Equivalet • Cat 6 Cable :- Finolex, D-link, Commscope or Equivalent Also providing service, reparing and maintenance of CCTV system with necessary parts without any extra cost within 02 (Two) years warranty period.	7.00	No.		
	Part - C CONSULTANCY SERVICES				
11	Rate for Hiring of Consultancy Services for Drawing and Technical Details.	1.00	Lot		
		TOTAL AMOUNT (₹)			
	<u>Total Amount in words :-</u>				

Note :- G.S.T Will be Paid Extra On Above Mentioned Price As Per Applicable Government Rates.

Sd/-
EXECUTIVE ENGINEER
SCIENCE CENTRE
SURAT MUNICIPAL CORPORATION

SIGNATURE & SEAL OF CONTRACTOR
NAME & ADDRESS :-

DATE :-