

**PANCHAYAT IRRIGATION DIVISION - RAJKOT**

**Panchayat Irrigation Sub Division - Gondal**

Memorandum  
Showing Items To be  
carried out:-

**Construction of checkdam cum causeway at village Pedhla (from Mamadev Temple To Jetalsar (Jn) Road), Ta:- Jetpur, Dist.Rajkot**

**Schedule-B**

Quantities Estimated but may be more or less	Item of works	Estimated Rates		Unit	Total Amount according to estimated Quantities in Rs.
		In Figures	In Words(Rs)		
1	2	3(A)	3(B)	4	5
	<b>ITEM NO : 1</b>				
<b>136.00</b>	Excavation in all sorts of soil strata and formation including depositing the unuseful excavated stuff as and where directed including sorting and stacking useful material as require and directed upto lead 200mt. and all lift etc. completed. Including dewatering.(A) In Overburden Incl. Hard Murrum	79.00	Four Rupees Ten Paise Only	Cum	₹ 10,744.00
	<b>ITEM NO : 2</b>				
<b>2.30</b>	providing cutting bending, binding and fixing in position as per drawing TMT BAR reinforcement for R.C.C works and anchors bars inclu cost of black annealed 16 to 18 BWG M.S wire etc complete with all lead and lift. (B)Fe-500	76574.00	Seventy Six Thousands Five Hundred Seventy Four Rupees Only	M.T.	₹ 1,76,120.20
	<b>ITEM NO : 3</b>				
<b>45.00</b>	providing, supplying at site laying & fixing in position under ground RCC hume pipe of NP-2 class of BIS standard inclu. Filling the joints with cement mortar 1:1 with providing necessary collars etc. completed with inclusive of testing with working pressure and all lead and lift.(F) 900.00 mm	2214.00	One Thousands Three Hundred Fourty Four Rupees Only	M.T.	₹ 99,630.00

	ITEM NO : 4				
221.00	Prov. & Laying in position cement concrete using cement , sand and crushed metal coarse aggregate by mass and machine mix for PCC/RCC including necessary formworks compaction by vibrator,curing as directed with all lead & lift etc complete. (Excluding cost of steel ) FOR .BODY WALL, APRON, TRAINING WALL, SIDE WALL, SPLAY WALL, KEY WALL, CUT OF WALL ETC.(4/E) "NOMINAL MIX" Conc. grade 1:2:4 and MSA-40mm	3465.00	Three Thousands Four Hundred Sixty Five Rupees Only	Cum	₹ 7,65,765.00
	ITEM NO : 5				
202.00	providing murrum includding spreding the same and dressing the side slope & top surface in required grade and camber with lead up to 1.00 km etc complete.	166.00	One Hundred Sixty Six Rupees Only	Cum	₹ 33,532.00
	Total:-			₹ 10,85,791.20	
Rupees Ten Lacs Eighty Five Thousand Seven Hundred Ninty One and Twenty Paise Only					
I/We am/are willing to carry out the work at ..... % above / below percent (should be written in figure and words) of estimated rates mentioned above. Amount of my/our tender works out as under					
*Estimate amount put to tender Rs.		*Estimate amount put to tender Rs.			
Deduct.....% below Rs		Add .....% above Rs			
Net Rs		Net Rs			
In words .....		In words .....			
*(Please strikeout whichever is not applicable)					

Notes 1- All works shall be carried out as per public works Department Handbook and other specification of Division

Notes 2- All the columns in schedule should be filled in ink and the total of the entire in the last column should be struck by the contractor under his signature

Notes 3- Rate quoted include clearance of site (prior commencement of work and at its close) in all respect and hold good for work under all condition,site,moisture,weather etc.

Notes 4- to be continued on additional sheets,if found necessary

Signature of  
Contractor

Deputy Executive Engineer  
Panchayat Irrigation Sub Division  
Gondal