

<p style="text-align: center;">PANCHAYAT IRRIGATION DIVISION - RAJKOT Panchayat Irrigation Sub Division - Jasdan Construction of new Checkdam in Village Ambardi, Ta.Jasdan Dist.Rajkot.</p>					
Memorandum Showing Items To be carried out :-					
Schedule-B					
Quantities Estimated but may be more or less	Item of works	Estimated Rates		Unit	Total Amount according to estimated Quantities in Rs.
		In Figures	In Words(Rs)		
1	2	3(A)	3(B)	4	5
	ITEM NO : 1				
1360.00	Jungle clearance of specified category and bushes for canal/dam work as directed with depositing material etc complete.(excluding tree of grith above 0.5mt) (A) Upto 2 years old (b) for medium dence	₹ 2.00	Rupees Two and Zero Paisa Only	Sqmt	₹ 2,720.00
	ITEM NO : 2				
44.00	Excavation in all sorts of strata and formation including depositing the unusefull excavated stuff as and where directed including sorting and stacking usefull materials as directed upto 30mt lead etc. complete Including dewatering.(depth 0 to 3 mt) (A) In Overburden incl hard murrum	₹ 83.00	Rupees Eighty Three and Zero Paisa Only	Cum	₹ 3,652.00
	ITEM NO : 3				
27.00	Drilling 25 mm dia holes at distance as specified and depth up to 3.00 mt for check dam foundation & fixing anchor bars of specified diameter with cement grout inclu. Clearing holes as directed etc.(excludding cost of bars)	₹ 252.00	Rupees Two Hundred Fifty Two and Zero Paisa Only	Cum	₹ 6,804.00
	ITEM NO : 4				
0.99	Providing,cutting,bending,binding and fixing inposition as per drawing .TMT BAR , reinforcement for R.C.C. works and anchor bars incl cost of black annealed 16 to 18 BWG M.S..Wire etc.complete with all lead and lift.(Fe - 500)	₹ 76,574.00	Rupees Seventy Six Thousand Five Hundred Seventy Four and Zero Paisa Only	M.T.	₹ 75,902.87

	ITEM NO : 5				
63.00	Providing & Laying in position 'NOMINAL MIX' cement concrete using cement sand and crushed aggregate by machine mix incl. necessary formworks ,centering ,scaffolding compaction by mechanical vibrator curing as directed with all lead & lift etc E) Concrete grade 1:1.5:3 and MSA-20mm(Graded)	₹ 4,458.00	Rupees Four Thousand Four Hundred Fifty Eight and Zero Paise Only	Cum	₹ 2,80,854.00
	ITEM NO : 6				
412.50	Strengthening of existing earthen bund by obtaining earth from deepening Minor irrigation Scheme / Percolation Tank / Check Dam using watering / Pneumatic Temping work etc. Complete as suggested by Engineer in charge	₹ 104.90	Rupees One Hundred Four and Ninety Paise Only	Cum	₹ 43,271.25
			Total		₹ 4,13,204.12
Rupees Four Lacs Thirteen Thousand Two Hundred Four Rupees & Twelve Paise Only					
I/We am/are willing to carry out the work at % above / below percent					
*Estimate amount put to tender Rs.		*Estimate amount put to tender Rs.			
Deduct.....% below Rs		Add% above Rs			
Net Rs		Net Rs			
In words		In words			
*(Please strikeout whichever is not applicable)					

Notes 1- All works shall be carried out as per public works Department Handbook and other specification of Division

Notes 2- All the columns is schedule should filled in ink and the total of the entire in the last column should be struck by the contractor under his signature

Notes 3- Rate quoted include clearance of site (prior commencement of work and at its close) in all respect and hold good for work under all condition,site,moisture,weather etc.

Notes 4- to be continued on additional sheets,if found necessary

Signature of
Contractor

Deputy Executive Engineer
Panchayat Irrigation Sub Division
Jasdan

Executive Engineer
Panchayat Irrigation Division
District Rajkot