

SCHEDULE-B				
Madhya Gujarat Vij Company Limited				
Name of Work: Annual rate contract for General maintenance of Offices Under Borsad Division office.				
SN	DESCRIPTION	Rate	UNIT	Code
<b>Demolition &amp; Dismantalling</b>				
1	Demolition including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift. (i) R.C.C. work	1071.63	CMT	20002
2	Demolition of Brick work and stone masonry including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift.(ii) In Cement Mortar	557.32	CMT	20003B
3	Dismantling tiled of stone floors laid in mortar including stacking of serviceable materials and disposal of unserviceable materials with all lead and lift.	48.63	SMT	20005
4	Dismantling of sheet roofing including ridges, Hips, Valleys, Gutters etc. stacking of serviceable materials and disposal of unserviceable materials with all lead and lift.(ii) A.C. sheet roofing	54.09	SMT	20007B
5	Removing and scraping of old deteriorated plaster of any thickness from wall / R.C.C member including stacking of serviceable material and disposal of unserviceable from site of work with all lead and lift	19.69	SMT	20045
6	Scraping oil paint from steel and other metal surface and making the surface even (with Hand Scraping.)	51.27	SMT	20017
7	Dismantling doors, windows, ventilators etc. (wood or steel) shutters including chowkhats architraves,holdfasts and other attachment etc. complete and stacking them within all lead and lift.(i) Not exceeding 3 Sq.M. in area	190.19	No	20013A
8	Dismantling doors, windows, ventilators etc. (wood or steel) shutters including chowkhats architraves, holdfasts and other attachment etc. complete and stacking them within all lead and lift (ii) Exceeding 3 Sq.M. in area	254.68	No	20013B
9	Dismantling steel work including distempering and stacking the materials with all lead and lift.	3.81	KG	20012
10	Dismantling barbed wire in fencing including making rolls and also including dismantling fencing posts including all earth work concrete in base and making good the disturbed ground stacking useful materials as directed and disposing of the unserviceable materials with all lead and lift	67.47	RMT	20014
11	Dismantling sanitary fittings like wash basin . W.C. pan Indian and European type, flushing tank etc. including stacking the materials with all lead and lift.	410.13	NO	20016
12	Throwing away debried and unwanted material away from site at suitable locations by means of tractor and trailer trip upto any lead & lift.	700.00	Each	Approve rate RMU Plinth BCC item no.13
<b>Earth Work</b>				
13	Excavation for foundation upto 1.5 m depth including sorting out and stacking of useful materials and disposing off the excavated stuff upto 50 Meter lead.(B) Dense or Hard soil	269.87	CMT	04B001B
14	Excavation for foundation for depth from 1.5 m to 3.0 m including sorting out and stacking of useful materials and disposing off the excavated stuff upto 50 Meter lead.(B) Dense or Hard soil	292.18	CMT	04B002B
15	Filling in foundation and plinth with murrum or selected soil in layers of 20cm. thickness including watering, ramming and consolidating etc. complete.	291.47	CMT	04008A
16	Filling in plinth with sand under floors including watering ramming, consolidating and dressing complete	477.03	CMT	04007A
17	Filling in foundation and plinth with brick Bats Chhara in layers of 20cm. thickness including watering, remming and consolidating etc. complete.	615.31	CMT	04009A
18	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm. in depth consolidating each disposed layer by ramming and watering	135.56	CMT	4006.00
19	Collecting, Carting and unloading materials like crushed stonegreet, chipping, quarry spill./grit, etc of appd.Quality from quarry and spreading in required layers leveling etc.camber etc.complete with all lead and lift as directed by EIC.	1100.00	CMT	Nadiad CO item no.158
<b>Concrete Work</b>				
20	Providing and laying cement concrete 1:3:6 (1-Cement : 3- coarse sand : 6- hand broken stone aggregates 40 mmnominal size) and curing complete excluding cost of formwork in (A) Foundation and Plinth	3064.60	CMT	05003A
21	Providing and laying controlled cement concrete M.200 and curing complete including the cost of formwork and excluding reinforcement for reinforced concrete work in (A) Foundations, footings, Base of columns and Mass concrete	4361.78	CMT	05024AA+350 For Formwork
22	Providing and laying controlled cement concrete M.200 and curing complete including the cost of formwork and excluding reinforcement for reinforced concrete work in (C) Slabs,landing,shelves,Balconies Lintels, Beams, Girders and Cantilever upto floor two level	4881.97	CMT	05024CA + 350 for formwork
23	Providing TMT Bar FE 500D reinforcement for R.C.C. work including bending, binding and placing in position complete upto floor two level	76.52	KG	05014C
<b>Brick Work</b>				
24	Brick work using common burnt clay building bricks having crushing strength not less than 35 kg./Sq.Cm. in foundation and plinth in Cement Mortar 1:5. (1- Cement : 5 -fine sand)(B) Conventional	4203.06	CMT	06001BA
25	. - Do as above - but for Brick work in superstructure above plinth level up to floor two level including parapet/ stair cabin.	4481.99	CMT	06001BA +06006B
26	(i) Half brick masonry in common brunt clay building bricks having crushing strength not less than 35 Kg/Sq.Cm. in Cement mortar 1:4 (1- Cement : 4 -coarse sand ) in superstructure above floor two level Conventional	665.61	SMT	06008A2A+06008E2 A
27	Brick work using common burnt clay building bricks having crushing strength not less than 35 kg./Sq.Cm. in foundation and plinth in Cement Mortar 1:5. (1- Cement : 5 -fine sand)(C) Fly Ash Bricks	5072.76	CMT	06001CA
28	. - Do as above - but for Brick work in superstructure above plinth level up to floor two level including parapet/ stair cabin.	5351.69	CMT	06001CA+06006C
29	ii) Half brick masonry in common brunt clay building bricks having crushing strength not less than 35 Kg/Sq.Cm. in Cement mortar 1:5 (1- Cement : 5 -coarse sand ) in foundation and plinth (C)Fly Ash Bricks	687.80	SMT	06008B3A
<b>Plaster</b>				
30	PProviding 15mm thick cement plaster in single coat on Rough (Similar)side of single or half brick walls for interior plastering upto floor two level and finished even and smooth in (i) Cement mortar 1:3 (1-cement:3-sand) finishing with a floating coat of neat cement slurry	201.76	SMT	17002A
31	Providing 20mm thick cement plaster in single coat on single or half brick walls for interior plastering upto floor two level and finished even and smooth in (i) Cement mortar 1:3 (1-cement:3-sand)	259.64	SMT.	17003A
32	Extra over above items for finishing with a floating coat of neat cement slurry.	50.12	SMT.	17004A
33	Extra over above items for plastering on ceilings and soffits of stairs upto floor two level instead of plastering on walls.	25.80	SMT.	17006
34	20mm thick sand faced cement plaster on walls upto height 10 metres above ground level consisting of 12mm thick backing coat of C.M. 1:3 (1-cement : 3-sand) and 8mm thick finishing coat of C.M. 1:1 (1-cement : 1-sand) etc. complete.	348.95	SMT.	17009
<b>Flooring</b>				
35	Providing & fixing granite in flooring, riser and Treads of steps, partition for drinking water, moulding the edges and grooving if directed, of size not less than1200mm in length and full width of treads in C.M.1:2 neatly finishing the joints, curing etc. comp as directed by EIC.	3000.00	SMT	Anand toilet renovation item no.16
36	Labour charge for providing river sand polishing to kotah stone / granite of required finishing as directed by EIC including all tools tackles labours etc complete.	250.00	SMT	Anand PH work item no.10

Madhya Gujarat Vij Company Limited				
Name of Work: Annual rate contract for General maintenance of Offices Under Borsad Division office.				
SN	DESCRIPTION	Rate	UNIT	Code
37	P & L 24" x 24" vitrified 8 mm thick tile flooring over 20 mm (average) base of cement mortar 1:6 (1 cement: 6 coarse sand) on new surface or fixing on existing flooring by adhesive material including dismantling of existing flooring and jointed with color cement slurry including finished with flush pointing & cleaning the surface etc. complete for antiskit Shade. Basic rate of tile is Rs. 60/Sq.ft	1453.19	SMT	14021A
38	Providing and laying coloured glazed tiles of the size 300 mm x 200 mm x 8 mm / 300 mm x 450 mm x 8 mm in skirting, risers of steps and dedo on 10 mm. thick cement plaster 1:3 (1 cement : 3 coarse sand) & jointed with white cement slurry. Basic rate of tile is Rs. 60/Sq.ft	1473.50	SMT	14036
39	Providing and fixing pre-cast concrete kerb stone of gray cement based concrete block 30cm length,30cm height and 15cm thick of M200 grade concret as per approved design and including excavation for fixing in proper line and level,filling the joint with C:M 1:3 (1cement:3fine sand) etc complete.	400.21	RMT	14023A
40	Providing and fixing pre-cast Rubber Dye / steel Dye inter locking concrete block 60mm thick with grade of concrete M300 pnumatic compressed / vibrated mechanically and as per approved design Confirming to IS 15658 : 2006 including 35 mm Sand layer for levelling and filling the joint with sand in proper line and level as per guidlines of IRC : SP 63-2018 etc. Complete.	699.93	SMT	14033
41	Removing & re-fixing pre-cast Rubber Dye / steel Dye inter locking concrete block 60mm thick with grade of concrete M300 pnumatic compressed / vibrated mechanically and as per approved design Confirming to IS 15658 : 2006 including 35 mm Sand layer for levelling and filling the joint with sand in proper line and level as per guidlines of IRC : SP 63-2018 etc. Complete.	322.81	SMT	14033 - M910
42	Providing China Mosaic water proofing treatment in Terrace of different levels preparing roof surface for laying brick bat on cement mortar (1:4) with special water proofing composed in necessary gradient for easy flow of rain water, brick bat coba is finally covered by China Mosaic Tikdi fixed by white cement base added with special water proofing compound. The treatment is carried along the vertical surface of the parapet and other joining wall up to height of about 300 mm in a shape of quarter round vata. The average thickness of the water proofing treatment is about 140 mm. Minimum thickness at rain water outlet points being 75 mm including curing etc. complete as per specification and instruction including water proofing test for minimum 3 days etc., complete as directed by E. I. C. Contractor should give guarantee for water proofing for 5 years. All the material including cement should be brought by the contractor at his own cost. 10% Amount	1348.52	SMT	14019A+ 14035
43	Providing and laying cement concrete flooring 1:2:4 (1-cement : 2-coarse sand : 4-graded stone aggregate 20mm nominal size) laid in one layer and finished with a floating coat of neat cement. (B) 50mm thick.	365.48	SMT	14015BA
44	Providing and laying polished Kota stone slab flooring over 20mm (Average) thick base of cement mortar 1:6 (1-cement : 6-coarse sand) or L.M. 1:1.5 laid over and jointed with grey cement slurry including rubbing and polishing etc. complete. (B) 30 mm thick	1098.09	SMT	14012BA
45	Providing and laying polished kota stone slab 25mm thick in risers of steps,skirting Dedo and pillars laid on 10mm thick cement mortar 1:3 (1-Cement : 3 coarse sand) and jointed with gray cement slury mixed with pigment to match the shade of slab including rubbing and polishing etc. complete	1172.51	SMT	14013A
<b>Wood &amp; Glass Work</b>				
46	Providing and fixing M.S. grills of required pattern to wooden frames of windows etc. with M.S. flats at required spacings and frame around, square or round bars with round headed bolts and nuts or by screws (A) Plain Grill	105.18	KG	10025AA
47	Providing and fixing 35 mm thick shutters for Doors, windows and clerestory windows including Indian teak wood frames 10 cm x 7 cm. size including anodized alluminium fixtures and fastenings including primer coat of approved quality and two coats of oil painting etc, complete. (i) Fully Glazed	4595.06	SMT	10030A
48	Providing and fixing 35 mm thick Decorative type Water proof flush door shutters, solid core construction with wood frame with Polish of first class hard-wood with cross band and face ply-wood face panels, 1.0 mm thick laminate on both sides including Stainless steel fixtures and fastening like tower bolt, stopper including for door shutters sides etc complete. as directed by engineer in charge (Measurement Shall be Consider L X H)	4000.00	smt	HO ARC item no.35
49	Providing and fixing FRP frame size 100x50 mm and 28mm thick FRP depress panel shutter having extra reinforcement on sides & edges in Gel coat finish. The core of the shutter & frame is to be filed up with injected fire retardant grade polyurethane foam done in situ alongwith embedded wooden pieces for stiffening & also taking hinges & fintures. The whole FRP frame & shutter is to be water proof weather proof, termite proof & resistance to mild acid/alkali. Rates are to be inclusive of S.S hinges with necessary screws & alluminium fixtures & fastenings & fastener sleeve.	2354.22	SMT	10037
50	Providing services of mason / fabrictor/ carpentaer for various types works for 08 hrs at directed by EIC.	791.00	Each	L018 SOR
51	Providing services of Helper for mason/fabrictor / carpenter / for maintenance and cleaning for various types of works for 08 hrs at directed by EIC.	593.00	Each	L026 SOR
	Providing and Fixing locks of godrej or equivalent make incl.All labour & materials as approved and directed by EIC For below.			
52	SS Drawer locks	250.00	Each	ARC HO WO.5048 Dt.11.05.23
53	Mortize lock	1400.00	Each	ARC HO WO.5048 Dt.11.05.23
54	Multi Drawer lock	375.00	Each	ARC HO WO.5048 Dt.11.05.23
55	Cylindrical lock	960.00	Each	ARC HO WO.5048 Dt.11.05.23
56	Steel Cupboard lock	661.00	Each	ARC HO WO.5048 Dt.11.05.23
57	Providing and Fixing Acrylic PVC Name plate of Size 12"x4" or as per requirment with printed/emboded letters in required colour including all material and labour as directed by EIC.	13.50	Sq. inch	ARC HO WO.5048 Dt.11.05.23
	Reparing of revolving chair with approved brand and make incl. All labour & mateirals as approved and directed by EIC. For below			
58	SS Base Stand	1400.00	Each	ARC HO WO.5048 Dt.11.05.23
59	Hydraulic Jumper	950.00	Each	ARC HO WO.5048 Dt.11.05.23
60	Cloth with maderpatt	650.00	Each	ARC HO WO.5048 Dt.11.05.23
61	Wheel	115.00	Each	ARC HO WO.5048 Dt.11.05.23
62	Handle	200.00	Each	ARC HO WO.5048 Dt.11.05.23
	Washing of chairs/sofa/curtains, etc. with all required chemicals, vecume m/c, tools & tackles incl. All labour & materials as directed by EIC. For Below			
63	Revolving Chair	130.00	Each	ARC HO WO.5048 Dt.11.05.23
64	Single Seater Sofa	230.00	Each	ARC HO WO.5048 Dt.11.05.23
65	Two Seater Sofa	460.00	Each	ARC HO WO.5048 Dt.11.05.23
66	Three Seater Sofa	690.00	Each	ARC HO WO.5048 Dt.11.05.23

<b>Madhya Gujarat Vij Company Limited</b> <b>Name of Work: Annual rate contract for General maintenance of Offices Under Borsad Division office.</b>				
SN	DESCRIPTION	Rate	UNIT	Code
67	Curtains ( Vertical/Roman/Rollar blinds, etc.)	161.00	Sqm	ARC HO WO.5048 Dt.11.05.23
	Repairing of office table with approved brand and make incl. All labour & materials as approved and directed by EIC. For below			
68	Drawer handle	120.00	Each	ARC HO WO.5048 Dt.11.05.23
69	5 mm table glass	104.00	Sqf	ARC HO WO.5048 Dt.11.05.23
70	6 mm table glass	115.00	Sqf	ARC HO WO.5048 Dt.11.05.23
71	8 mm table glass	126.00	Sqf	ARC HO WO.5048 Dt.11.05.23
72	Powder coated telescopic sliding channel (any size)	1200.00	Each	ARC HO WO.5048 Dt.11.05.23
73	600mm wide and 450 mm deep wooden keyboard tray made from 19mm thick all weather proof plywood and 1 mm thick coloured Laminates	996.00	Each	ARC HO WO.5048 Dt.11.05.23
74	Maintenance of existing aluminium windows (to be removed & refixed) with new ribbons, clear white gaskets, rollers, handles etc complete with applying silicon from outside to restrict the seepage of rain water. Aluminium sections shall be powder coating of approved shade and colour after sanding surface as per instruction.	500.00	Sqm	ARC HO WO.5048 Dt.11.05.23
75	Repairing, Servicing & Refitting the Existing Door as Per Site Situation as per Instruction of EIC.	50.00	Sqft	ARC HO WO.5048 Dt.11.05.23
76	Providing and fixing new frame for wooden door made of teakwood of 3' wide and 7' height including finishing with polish as directed by EIC	2200.00	Each	ARC HO WO.5048 Dt.11.05.23
77	Providing & Fixing Godrej or equivalent Door Closer with all tools and tackles.	2000.00	NO	Baroda circle ladies Rest room item no.25
78	Renovation of Existing storage below sill level with 18 mm ply top, based on vertical supports made by 18 mm Thk. Plywood with all necessary shutters & self (made by 18 mm thk ply) as per given in detail drawings. All exposed and internal surfaces covered with 1 mm thk approved shade laminates as instructed by Architect/Engineer In charge. Complete with all hardware like MS nails, screws, magnet, Stoppers, L - hinges, 18 mm multi locks, table chain, 4" mat finish SS handles etc. Laminates, plywood, shades & hardware Items shall be approved by EIC.	3766.00	SMT	ARC HO WO.5048 Dt.11.05.23
79	Roller Blind: Providing and fixing Roller Blind curtain of water proof greenguard fabric fixed on window level on wooden batten with curtain lift of ball chain and same color fabric heavy metal pelmet with white color & box type look, heavy bottom rail and with Eco black-out material with necessary hardware fitting, material and labour etc complete. design and colour as per instruction by E.I.C. (Basic Rate Rs. 110/Sft) inclusive of all material and labour and with transportation.	1300.00	SMT	Nadiad CO item no.98
80	Soft Board : Pro & fix soft board panel unit made from 15mm tk. Soft board & velvet cloth (basic rate 150 rs/smt) teak wood corner patti, to all over border polishing to t.w. patti, including fixing with fevicol, nail, etc. complete in size 4'x21" as directed by EIC.	1560.00	Sq.mt	Undel furniture item no.11
81	Providing approved quality of cloth in approved design & shed and colour with aster, baking as per selection by occupant including all as directed by EIC basic rate of cloth shell be RS. 400/ PER Rmt for 48" panna.	460.00	Rmt	Kadana sdn item no.89
82	Labor charges for stitching charges per part in elate pattern including backside madarpatt for 48" wide part if required with all tools and tasks to complete the work cloth required shall be utilize from item no 35 and rest material required to function shall be brought by contractor at his own cost. Payment of part shall be considered irrespective of length of part i.e. for door/window.	300.00	Part	Kadana sdn item no.90
83	Providing and fixing SS pipe of 25 mm dia including all taxes and as per selection as directed by EIC.	150.00	Rmt	Kadana sdn item no.91
84	Providing and fixing SS knob / side socket to suit the pipe of 25 mm dia including all taxes and as per selection of occupant as directed by EIC. The rate is per pair in central support is required than same will be paid RS100 per no and only end cap is required as per site condition than same will be paid Rs 150 per pair.	275.00	pair	Kadana sdn item no.92
<b>Roof covering</b>				
85	Providing & Fixing 0.60 mm thick corrugated pre painted galvalume sheet of Tata /Jindal/Monakshi/National make for roofing including laying in proper alignment fixing with nut bolt ,gusset ,tapping screw washer, silicon etc., complete as directed by EIC. The rate is inclusive of all materials, labours, tools tackles, all taxes etc., The payment shall be made for actual work executed. No extra payment for over lapping shall be paid	874.00	SMT	Nadiad CO item no.163
86	Providing and fixing 3 mm thick FRP Sheet of approved quality with Machine screw fitting etc completed as per directed by EIC.	1100.00	SMT	Undel Sdn item no.94
87	Providing corrugated G.I. sheet of class-3 roofing fixed with galvanised iron J or L Hooks, Bolts and nuts 8mm diameter with bitumen and G.I. limpet washer or G.I. limpet washer. filled with white lead complete excluding the cost of purlins, Rafters and Trusses.(1) 0.80 mm thick sheet.	726.92	SMT	15001A
88	Structural steel work ( Confirming to IS 4923-1997) riveted, bolted or welded in builtup for all type sections, in framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete as per the structural designs and directions of Engineer in charge.Column ( 122 x 61 x 3.6mm )	130.52	KG	20054
89	Providing , fabricating & erecting in position M.C. angle ,plate, chequered plate, channels , girders, plain bar for columns etc including welding the section as per instruction & drawing making holes & 3 coats of oil paintings with one coat of red oxide of approve shad and make as directed by the EIC	100.00	KG	Nadiad CO item no.76
90	Providing and fixing FRP tray for leakage area between slab and false ceiling to collect the leakage water with necessary aluminium framing in proper slope. Including provision of PVC pipe as outlet pipe as per site condition and instruction by engineer-in-charge.	350.00	RMT	ARC HO WO.5048 Dt.11.05.23
<b>Water Supply plumbing &amp; Sanitary fitting</b>				
91	Providing and fixing 15mm L&K make angle cock as directed by EIC.	800.00	No	Anand toilet renovation item no.18
92	Providing and fixing 15mm L&Kn make short body Bib cock as directed by EIC.	896.00	No	Anand toilet renovation item no.19
93	Providing and fixing L&K make Pillar cock as directed by EIC.	969.00	No	Anand toilet renovation item no.20
94	Providing and fixing L&K make Conceal stop cock including two nos of brass MFT as directed by EIC.	1500.00	No	Anand toilet renovation item no.21
95	Providing and fixing L&K make flush cock medium including two nos of brass MFT as directed by EIC.	1600.00	No	Anand toilet renovation item no.22
96	Providing and fixing L&K make two way bib cock as directed by EIC	1580.00	No	Anand toilet renovation item no.23
97	Providing and fixing Pilot brand make brass health faucet directed by EIC.	600.00	No	Anand toilet renovation item no.24

<b>Madhya Gujarat Vij Company Limited</b> <b>Name of Work: Annual rate contract for General maintenance of Offices Under Borsad Division office.</b>				
SN	DESCRIPTION	Rate	UNIT	Code
98	EWC: Providing and fixing Wall Hung water closet (European type W.C. pan) as per approved make of selection & shade with PP soft close seat cover, P OR S Trap M.S. or G.I bracket, CP brass hinges and rubber buffers and Jointing the trap with soil pipe in cement mortar : 1:1 (1 cement : 1 fine sand) including cutting and making good the walls and floors where required with all labour and materials. All works to be carried out as per instructions and direction of Engineer-in-charge. (Model Jaguar CNS-WHT-959SPP or Cera cordo - S1043108)	7085.00	No	Nadiad CO item no.129
99	Providing and fixing Urinal pan white color of Jaguar make 355x340x535mm (URS WHT 13261) including waste coupling, pipe and labour charges with all tools and tacks	6037.50	NO	Anand toilet renovation item no.13
100	Providing, laying & jointing in true line and level 15mm dia UPVC Pipe (SCH - 40) including fittings Ashirvad/finolex make and approved by engineer in charge. Pipe shall be fix on the wall with the help of clamp at every two mt c/c or shall be concealed as directed including necessary fittings etc. including testing of pipe and joints and fixing the same with adhesive solvent, including cost of materials	71.93	RMT	23061
101	Do as above but for 25 mm dia UPVC Pipe.	90.93	RMT	23062
102	Do as above but for 50 mm dia UPVC Pipe.	193.73	RMT	23065
103	Providing, laying and jointing in true line and level 110 diametre U.P.V.C (Type B) conforming to IS 13592-1992 with one end plain and other end socketed with rubber ring, & fittings conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant, pipe shall be fixed on wall using of PVC clamp of the size 110 mm diametre x 149 mm length x 145 mm high at every 2000 mm center to center or shall be concealed in walls as directed including necessary fittings such as bends, shoes etc. including testing of pipes and joints and jointed with adhesive solvent cement including cost of all materials	868.22	RMT.	23067
104	Providing and fixing Gun metal check or non-return fullway wheel valve.(B) 20mm dia.	201.80	NO	23031B
105	Providing and fixing Gun metal check or non-return fullway wheel valve.(E) 40mm dia.	656.86	NO	23031E
106	Providing and fixing 600mm x 450mm bevelled edge mirror of superior glass mounted on 6mm thick A.C. sheet or plywood sheet and fixing to wooden plug with C.P. brass screws and washers.	850.90	NO	23024
107	Providing and fixing C.P. brass towel rail complete with C.P. brass brackets fixed to wooden plugs with C.P. brass screws.(B) 600mm x 20mm size.	610.32	NO	23025
108	Providing and fixing 600mm x 120mm glass shelf with C.P. brass bracket and guard rail complete mixed to wooden plug with C.P. brass screws.	535.82	NO	23026
109	Providing and fixing washbasin with single hole for pillar tap with C.I. or M.S. brackets painted white including sutting holes and making good the same but excluding fittings.(A) Vitreous China:(ii) Flat Back washbasin 550 mm x v 400mm size (i) In white colour	1511.53	NO	23018
110	WASH BASIN : Providing and fixing table top washbasin suitable for pillar tap including fixing on granite with adhesive chemical, waste coupling Half / Full threaded and waste coupling up to 130mm compatible with table top basin including, o ring, rubber plug, nut, nipple, Angle valve 15 mm heavy duty with cap - flange, including fitting & fixing in socket in position with required accessories, making the hole in granite, including plumbing, transportation, tools tackles, fitting work and fixtures for the same etc. complete. Wash Basin : Kerovit KADIN - KS277 or Kohler / Jaquar / reputed make having base price more than ₹5,900.00 and Waste coupling code Kerovit KA870005/06 or Kohler / Jaquar / reputed make having base price more than ₹775.00, angle valve code kerovite KA 910001 or Kohler / Jaquar / reputed make having base price more than ₹775.00	9361.000	Each	HO Toilet Renovation item no.29
111	Bottle Trap : Providing and fixing Bottle trap including, o ring, rubber plug, fitting & fixing in position with required accessories, including plumbing, transportation, tools tackles, fitting work and fixtures for the same etc complete. Bottle Trap : Kerovit KA870002 or Kohler / Jaquar / reputed make having base price more than ₹1875.00	2368.000	Each	HO Toilet Renovation item no.30
112	Pillar tap: Providing and fixing Tall Pillar tap including making the core in granite, Long braided Hose suitable for tall basin, o ring, rubber plug, fitting & fixing in position with required accessories, , including plumbing, transportation, tools tackles, fitting work and fixtures for the same etc complete. Pillar tap : Kerovit KB811002 or Kohler / Jaquar / reputed make having base price more than ₹4,900.00	6215.000	Each	HO Toilet Renovation item no.32
113	PVC Ball Valve: Providing and fixing Ball valve including fitting & fixing in position with required accessories, chemical solution labour work , including plumbing, transportation, tools tackles, fitting work and fixtures for the same etc complete	450.000	Each	HO Toilet Renovation item no.38
114	Towel Hanger: Providing and fixing Towel Hanger including fitting & fixing in position with required accessories, , including transportation, tools tackles, fitting work and fixtures for the same etc complete. Catagory : Kerovit KA680005 or Kohler / Jaquar / reputed make having base price more than ₹800.00	1089.000	Each	HO Toilet Renovation item no.47
115	Nahni Trap / Floor Drainer: Providing and fixing floor drainer (6 x 6 inch) including fitting & fixing in position with required accessories, chemical solution, , including plumbing, transportation, tools tackles, fitting work and fixtures for the same etc complete. Pillar tap : Kerovit KA640001 or Kohler / Jaquar / reputed make having base price more than ₹1,025.00	1517.000	Each	HO Toilet Renovation item no.51
116	Providing and fixing 8 mm thick straight glass detachable urinal partition of heat strengthened glass with both side acid frost finish glass with all necessary frame, clamps, etc. finished in chrome including all tools, tackels, labour, material, etc. of size 900x 450 mm or as per site situatioin as approved and directed by EIC	6958.00	Each	HO Toilet Renovation item no.65
117	SS plate Signage: 150mm X 100mm - Stainless Steel satin finished flat etching plate Providing Making and fixing of various in-door signage, as & where basis. sign in ISI Brushed S.S. Grade 304 letters in English letter + All text and design in acid process, etching plates. Etching text & design with respective color coated complete plate. The SS mounted on glass or any non holes surfaced by 3M double sided tape with required chemical process, guidelines by 3M company. Whereas, Any other then glass surface, SS plate mounted by Two side screws with required grips nd holes on the wall with two SS spacer screws. The item should be as per instruction at site approved byf Engineer incharge. The rate shall be inclusive of scaffolding, drilling, adhesive material etc. at all height.	518.00	Each	HO Toilet Renovation item no.71
118	Providing and fixing 12.5 Litres low level flushing cistern with a pair, of C.I. or Mild brackets, complete with fittings such as lead valve less syphon, 15mm nominal size brass ball valve with polythene float, C.P brass handle unions and couplings for connections, with inlet, outlet and overflow pipes, 40mm dia. porcelain enamelled flush bend including cutting holes in walls and making good the same connecting the flush bend with cistern and closet (overflow pipe to be measured and paid for separately)(A) Vitreous China (i) In white colour	2346.92	NO	23013
119	Providing and fixing plastic seat and cover for wash down water closer with C.P. brass hinges and rubber buffers. (B) Black plastic seal and cover.	288.45	NO	23017
120	Providing and fixing C.I. Manhole cover 0.60 M. x 0.45M. size having weight not less than 35Kg.	948.68	NO	23038
121	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete.(A) 15 mm.	168.67	Rmt	23055

Madhya Gujarat Vij Company Limited				
Name of Work: Annual rate contract for General maintenance of Offices Under Borsad Division office.				
SN	DESCRIPTION	Rate	UNIT	Code
122	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. [B] 20 mm.	206.73	Rmt	23056
123	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. [C] 25 mm.	251.31	Rmt	23057
124	Providing and fixing to wall ceiling and floor 10.0 Kg. F/Cm2 working pressure polythene pipes of the following outside Dia. Low density, complete with special falnge compression type fittings, wall clipsetc. including making good the wall ceiling and floor (D) 40mm	130.65	RMT.	23004D
125	Providing and fixing to wall ceiling and floor 10.0 Kg. F/Cm2 working pressure polythene pipes of the following outside Dia. Low density, complete with special falnge compression type fittings, wall clipsetc. including making good the wall ceiling and floor (G)110 mm	335.69	RMT.	23004G
126	Providing and fixing in position cowl vent to pipes.(C) 100mm dia	500.17	NO	23006C
127	Providing, laying and jointing in true line and level 160 diametre U.P.V.C (Type B) conforming to IS 13592-1992 with one end plain and other end socketed with rubber ring, & fittings conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant, pipe shall be fixed on wall using of PVC clamp of the size 160 mm diametre x 210 mm length x 196 mm heigh at every 2000 mm center to center or shall be concealed in walls as directed including necessary fittings such as bends, shoes etc. including testing of pipes and joints and jointed with adhesive solvent cement including cost of all materials.	826.12	RMT	23066
128	Providing & fixing PVC Nanhi trap of Supreme / Finolex brand of approved size & make with additional S.S. perforated Jali Cover & PVC Pipe outside the wall with plug, bend, etc., complete as directed by E.I.C. 100 mm dia	580.47	NO	23068
<b>Drainage &amp; Sewerage Item</b>				
129	Providing and fixing S.W. gully trap with C.I. grating brick masonry chamber and water tight C.I. cover with frame of 300mm x 300mm size (inside) with standard weight.(i) Square mouth traps. (A) 100mm x 100mm size P type.	1279.40	NO	24006AA
130	Constructing brick masonry chamber for underground C.I. Inspection chamber and bends with bricks having crushing strength not less than 35Kg/Cm2 in C.M. 1:5 C.I. cover with frame (Light duty) 455mm x 610mm intenal dimensions total weight of cover with frame to be not less than 38Kg. (Wt. of cover 23 Kg.) and Wt. of frame 15Kg. ) (R.C.C. top slabe with 1:2:4 mix (1-cement :2- coarse sand :4-graded stone aggregate 20mm size) foundation concrete 1:5:10 inside plaster 15mm thick with cement mortar 1:3 finished smooth with a floating coat of neat cement on walls and bed concrete etc. complete.(i) Inside dimensions 455mmx 610mm and 450mm deep for single pipe line	2903.89	NO	24016AA
131	Extra over above items for every additional depth of 0.1M. of part thereof beyond 450mm depth for Brick masonry chamber (i) for 455mm x 610mm size.	239.99	NO	24017A
132	Constructing brick masonry chamber for underground C.I. Inspection chamber and bends with bricks having crushing strength not less than 35Kg/Cm2 in C.M. 1:5 C.I. cover with frame (Light duty) 455mm x 610mm intenal dimensions total weight of cover with frame to be not less than 38Kg. (Wt. of cover 23 Kg.) and Wt. of frame 15Kg. ) (R.C.C. top slabe with 1:2:4 mix (1-cement :2- coarse sand :4-graded stone aggregate 20mm size) foundation concrete 1:5:10 inside plaster 15mm thick with cement mortar 1:3 finished smooth with a floating coat of neat cement on walls and bed concrete etc. complete.(ii) Inside dimensions 500mm x 700 mm and 450mm deep for single line with one or two isolate	3624.51	NO	24016BA
133	Extra over items for every additional depth of 0.1M. of part thereof beyond 450mm depth for Brick masonry chamber (ii) for 500mm x 700mm size.	262.24	NO	24017B
<b>Steel Aluminum &amp; Iron Work</b>				
134	Providing and fixing slandered extruded fo aluminum section of size 63mm x 38.10mm x 1.2mm (Jindal Section :2434, @ Wt. 0.643 Kg/mt) with colour anodized aluminum frame for ventilation with 5 mm thick frosted glass as detailed etc complete for Ventilation.(The rate is inclusive of providing mosquito net with cleat on one side)	2200.00	SMT	Undel sdn item no.35
135	Providing and fixing Window having extruded alluminum colour annodized section frame main outer side 63.50 x 38.10 x 1.95 mm (of Jindal Section No 4605 @ Wt 1.094 Kg/Rmt) horizontal Two Track member size 61.85 x 31.75 x 1.2 mm (of Jindal Section No 8687 @ Wt 0.695 Kg/Rmt) vertical member of size 61.85 x 31.75 x 1.3 mm (of Jindal Section No 8758 @ Wt 0.659 Kg/Rmt) with sliding shutters of horizontal member size 40 x 18 x x 1.29 mm (of Jindal Section No 8949 @ Wt 0.456 Kg/Rmt) vertical member of size 40 x 18 x x1.29mm (of Jindal Section No 8947 @ Wt 0.456 Kg/Rmt / section 8948, @ wt 0.457 Kg/Rmt ) with 5mm thick tranparent Bronze Colour Tinted Float glass with powder coated alluminium fittings and fixtures and tranparent silicon sealant glass fixing to frame as per detail etc. complete for Window. Only mechanical joints shall be used, welding shall Not be permitted. Concealed lock of Indigo or equivalent and white PVC Gasket is to be utilized in the work. For window opening more than 2.00 in length equivalent	2021.00	SMT	Undel sdn item no.33
136	Providing & Fixing in position partly pannelled and partly glazed aluminum partition without door shutters using Colour anodized aluminum section. Panels shall be 9mm both side pre laminated MDF board of "Greenlam" make and glazing shall be 5mm thick tinted glass of "MODI" Saint Gobain" as per drawing or as directed. Rate including cost of all materials including gaskets, Aluminum clips having unit weight .097Kg/Rmt. and labour required to complete the job as per good practice Extruded Aluminum section of Jindal make available in ALLOY 63400 and Temper WP [HE9WP] corresponding to IS -733 and IS 1285 to be used for Frame single groove 4605,Frame double groove 4604. Only mechanical joints shall be used. welding shall not be permitted	2000.00	SMT	Undel sdn item no.82
137	Providing and fixing rolling shutters of approved make made of 80 mm wide M.S. laths inter-locked together through their entire length and jointed together at the ends by end locks mounted on specially designed pipe shaft with bracket plates, guide channels and arrangements for inside and outside locking with push-pull operation including the cost of hood cover and spring etc. complete (A) Shutters having width below 3.5 M	3519.21	Sqm	11005A
<b>Celling</b>				
138	Providing and fixing eco-friendly light weight calcium silicate false ceiling tiles having Tegular edge & 15 mm Thick Densified edges on the Tile Periphery for Extra Strength The Light weight calcium silicate ceiling tiles shall have , light reflection 85% non-ombustible as per B.S. 476 part IV, 100% humidity resistance and also having thermal conductivity0.043° w/m KC.for the best thermal Insulation . The Light weight calcium Silicate tile shall be of approved texture Fine fissured/ Spintone/Cosmos having NRC value of 0.5 & Globe having NRC value of 0.75 NRC or equivalent of size 595 X 595 mm to be laid on true horizontal level suspended inter locking metal grid of hot dipped galvanized steel sections (galvanizing @120 grams per sqm including both side) consisting of main 'T' runner suitably spaced at joints to get required length and size of 24X38mm made from 0.30 mm thick (minimum) sheet, 1200mm centre to centre, and cross 'T' of size 24X28mm made out of 0.33mm (Minimum) sheet spaced 1200mm along spaced between main 'T' at 600mm entre to centre to form agrid of 1200X600mm and secondary cross 'T' of length 600mm and size 24x28mm made of 0.30 mm thick (Minimum) sheet to be interlocked at middle of the 1200X600mm panel to form grid of size 600X600mm resting on periphery walls/partitions n a perimeter wall angle pre-coated steel of size (24X24X3000mm made of 0.40mm thick (minimum) sheet with the help of rawl plugs at 450mm centre to centre with 25mm long dry	1657.57	SMT	16006

Madhya Gujarat Vij Company Limited				
Name of Work: Annual rate contract for General maintenance of Offices Under Borsad Division office.				
SN	DESCRIPTION	Rate	UNIT	Code
139	Providing fixing suspended Gypsum false ceiling 12mm thick (as per design and pattern approved by the engineer-in-charge. As per includes of providing and fixing GI parameter channels of six 0.55 mm thick having flange of 30 mm and a web of 27 mm along with parameter of ceiling screw fixed to brick wall / partition with the help of nylon sleeves and screws at 600 mm centre then suspending GI channel of size 45 mm X 0.9 mm thick with two flanges of 15 mm each from soffit at 1220 mm centre with ceiling angle of width 25 X 10 mm X 0.5 mm thick fixed to soffit with GI and steal explanation fasteners. Ceiling section of 0.55 mm thickness having web of 51.5 mm and two flings of 26 mm each lips of 10.5 mm are then fixed to intermediate channel with the help of connection clips and indirection perpendicular to the channel at 457 mm centres 12.5 mm tapered edge zip board confirming to IS 2095- 1982 is confirming to IS 2095- 1982 is confirming to IS 2095- 1982 is ceiling section with 25 mm dry weight at 230 mm centres.Screw fixing is done mechanically either with screw driver of drilling machine and finish so as to have a flush look which includes filling with crack seal / tape and finishing the tapered / square edges of the board with jointing compound paper tape with finish level. Rates are inclusive with cut-out for ceiling fixtures& Measurement Shall be Consider L X B & Design Offset Patta shall be Paid Extra.	992.25	SMT	16007
<b>Color</b>				
140	Removing dry or oil bound distemper by a washing and scraping and sand papering the wall surface smooth including necessary repairs to scratches complete.	11.42	SMT	18014
141	Extra over item 33 for removing dry oil bound distemper on ceilings and sloping roofs.	1.66	SMT	18015
142	Distempeing (Two coats) with oil bound distemper of approved brand and manufacture and of required shade on wall surfaces to give an even shade, over and including a priming coat with distemper primer of aproved brand and manufacture after thoroughly brushing the surface free from mortar dropping and other foreign matter and also including preparing the surface even and sand papered smooth.	74.75	SMT	18021
143	Distempeing (One coats) with oil bound washable distemper of approved brand and of required shade on wall surfaces to give an even shade, after thorouhly brushing the surface clean of all grease dirt, loose pieces of scales and also including distempering with oil bound washable distemper of preparing the surface even and smooth.	28.29	SMT	18023
144	Wall painting (two coats) with plastic emulsion paint of approved brand and manufacture on undecorated wall surface to give an even shade including thoroughly brushing the surface free from mortar droppings and other foreign matter and sand papered smooth.	82.03	SMT	18031
145	Extra over above for every subsequent coat of wall painting with plastic emulsion pain of approved brand	42.13	SMT	18032
146	Applying two coats of putty & two coats of primer of approved brand and manufacture on new wall surface to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth	40.19	SMT	19032
147	Finishing wall with weather proof exterior emulsion paint on wall surface (two coats) to give an required shape even shade after thoroughly brushing the surface to remove all dirt, and remains of loose powdered materials.etc complete	119.07	SMT	19031
148	Applying priming coat over new steel and other metel surface after and including preparing the surface by thoroughly cleaning, oil,grease, dirt and other foreign matter and scoured with brushes fine steel wood, scrapers and sand paper with ready mixed priming paint brushing red lead.	36.56	SMT	19001
149	Painting two coats (excluding priming coat) on new steel and other metal surface with enamel paint, brushing, interior to give an even shade including cleaning the surface an even shade including cleanica the surface of all dirt, dust and other foreign matter.	91.29	SMT	19002
150	Painting one coats (excluding priming coat) on previously painted steel and other metal surface with enamel paint, brushing to give an even shade including cleaning the surface of all dirt, dust and other foreign matter.	57.39	SMT	19003
151	Extra over item no.237 & 239 for every subsequent coat of paint	56.69	SMT	19004
152	Applying priming coat over new wood and wood based surface after and including preparing the surface by thoroughly cleaning oil, grease, dirt and other foreign matter, sand papering and knotting. (C) Ready mixed paint brushing priming for enamel	42.18	SMT	19009C
153	Extra over item 241 for every subsequent coat of priming coat. (B) Ready mixed paint brushing wood primier pink.	42.70	SMT	19010B
154	Painting two coats (excluding priming coat) on new wood and wood based surface with enamel paint, interior to give an even shade including cleaning the surface of all dirt, dust and other foreign matter sand papering and stoping.	91.29	SMT	19011
155	Painting one coats (excluding priming coat) on previously painted wood and wood based surface with enamel paint, to give an even shade including cleaning the of all dirt, dust and other foreign matter.	57.73	SMT	19012
156	Extra over item 243 and 244 for every subsequent coat of paint.	56.69	SMT	19013
157	Providing and applying water proofing paint treatment with " ASIAN DAMP PROFF " Paint as per manufacturer's instruction including filling the cracks seal as per manufacture 's instruction including cleaning the terrece by wire brushing & acid washing including all labour & material required for the work	320.00	SMT	ARC Civil work DGVCL Item No. 181
<b>Miscellaneous Building Item</b>				
158	Carring out plinth treatment to post construction / existing structure by spraying chemical solution for termite control treatment including labour and material consistment with I.S.I specification. Using Chlordene and Chiopurpiles 20 EC. As Per 6131_paret-II Concentration Weight one percent is recommended i.e one litre 20 EC chemical emulsion with 19 liter give 1 % concentration inclusive of one litre chemical emulsion application at the rate of 5 L litre chemical / Sqm of surface is recommended as per I.S.	123.12	SMT	22007
159	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer 3 mm thick water proofing membrane, black finished reinforced with non-woven polyester matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 litre/sqm by the same membrane manufacture of density at 25°C, 0.87-0.89 kg/ litre and viscosity 70-160 cps. Over the primer coat the layer of membrane shall be laid using Butane Torch and sealing all joints etc, and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse direction at 23°C as 650/ 450N/ 5cm. Tear strength in longitudinal and transverse direction as 300/250N. Softening point of	442.000	SMT	HO Toilet Renovation item no.14
160	Filling sunk slab with light material like charu/boxite as directed including cement mortar Plaster 10 mm thick in CM. 1:3 in all Around Surface (sides of Beams and top of sunk slab) including adding water proofing material like SUNANDA, FOSROK or PIDILITE to be used as a 0.15 Litre to 1 cement bag and making the surface clean and attractive as design at any height etc complete as directed by Engineer in-Charge with all lead and lift upto height 30 mtr.	4194.000	Cmt	HO Toilet Renovation item no.15
161	Carrying out timber treatment to all wood work including drilling holes and spraying oil based chemical solution on surface of timber work for termite control including labor and material etc. complete. Using Chlorpyrphos20 EC as per 6313 2013 Part III (1% concentration by mass) is Rommended one litre chemical emulsion diluted with 19 liters of kerosene. Total diluted concentration will be 20 liters inclusive of 1 liter chemical emulsion application in drilled holes and 0.75 / Litre chemical per one Sqmt two coat on wood surface not protected by paint or varnish.	74.42	SMT.	22005

Madhya Gujarat Vij Company Limited				
Name of Work: Annual rate contract for General maintenance of Offices Under Borsad Division office.				
SN	DESCRIPTION	Rate	UNIT	Code
162	Providing & Fixing ready made <b>2000/5000 LITRE capacity P. V. C. water</b> tight storage <b>tanks</b> made from linear low density polyethylene & low density polyethylene LDPF product conforming to I. S. : 10146 - 1982 with cover including providing & fixing one float valve ball-cock, one of G. I. Waste pipe with plug one of G. I. Over flow pipe of length up to 0.30 mt. including making all connection for inlet /outlet supply with necessary fittings for outlet / inlet etc., complete as directed by EIC. (Syntex water tanks, white)	14.63	Liter	Nadiad CO item no.140
163	Providing and laying controlled cement concrete M20 for trimix RCC Excluding the cost of reinforcement & including of using 125 micron polythine sheet at base of concrete using approved quality of polyester fiber (12mm) during mixing of cement concrete @ 125 gm per bag) and or as per manufacturing ,s specification of cement concerte @ 125 gm per bag) and or as per manufacater's specification including preparing the sub base with form work of M.S Chhanel of requaired size to maintain level and slope of concrete with using surface vibrator ,finishing the surface with power floter and trove ,light brooming on the surface with providing construction joints of size 10 mm wide 25mm deep in transverse direction @ 4.5 m C/C with sealing the same with approved quality bitumen sealant and providing expansion joints of size 25 mm width and up to throught depth of concete using 25 mm thick dura board HD -100 of approved quality and sealing the same with approved quality bitumen sealant at 40 meter C/c and or as directed using concrete cutter machine with necessary equipments ,labours tools tackles etc complete as directed by EIC.	6656.40	SMT	Nadiad CO item no.152
164	Providing supplying and spreading / mixing " CHAPDUR" chemical for smooth and luster finish of top surface of road (Note: Chemical is to be used as per manufacturers specification and instruction given by EIC having consumption of 4.00 KG per SMT	80.00	SMT	Nadiad CO item no.153
165	Patching damaged concrete surface including building up surface profile structurer elements by using polymer concrete/ mortar/apoxy-latex modified air cured concrete/morta system conforming to ASTM- C1059-86 type II (01 cement : 03 welligraded cleaned pre packed river sand with 10% apoxy latex by weight of cement & water cement ratio as per 0.30 ) or recommended by manufactured of average of 25 mm thickness in damage areas including applying structural grade apoxy / latex bonds coat conforming to ASTM - C 88291 prior to application of polymar modified mortar/spray to ensure bond between old concrete & new systems by brush application levelling, profiling etc. inclusive of all labour, material equipment etc. comp as per specifications & instruction of E.L.C..the treated area shall be painted with exterior emulsions paints of approved quality.	592.00	SMT	BCC LBG comp Wall item no.27
166	Filling cracks with non expanding poleurothene PU Based elastometric filler material including cut the cracks by Grinder atleast 12 to 15 mm making V Notch ,Removing all loose Material by Depression.	200.00	RMT	BCC LBG comp Wall item no.29
167	Providing and fixing 450 mm effective dia.(after laying) Hot dip galvenised twin Razor type <del>concenterina</del> <b>concenterina</b> coil with all required clips ,pins,etc. as per specification. Concentrina coil shall be fixed to M.S. Angles with RBT (Razor barbed tape) with help of u- nails with split pin. Rate quoted on running meter of compound wall basis ( 1) Effective dia. of coil after steching shall be 600mm	350.00	RMT	Nadiad item no.160
168	Providing and fixing <b>Chain link</b> roll having 10 gauge wire & 50x50mm jali with appropriate height as directed and fixing the same to MS angle and providing and fixing MS flat bedding by means of MS nut & bolts etc. complete as directed by EIC.	270.00	SMT	Nadiad item no.161
169	Supply & laying of support <b>RBT</b> (Razor barbed tape) with the help of u- <del>nails/split pin</del> . Rate shall be quoted on running meters of RBT laid.	18.75	RMT	Nadiad item no.162
170	Providing and Fixing Stainless Steel 304 Grade 16 gauge railing with 38 MM Dia Pipe, & 20 MM Dia support Kitchen / Duplex make & flanges as per good engineering practice. The end condition of pipe shall be closed with SS Cap & properly grinded. This item is for pipe fixed in wall without any vertical support	1500.00	RMT	Anand PH item no.12
171	Providing and Fixing Stainless Steel 304 Grade 16 gauge railing with 38 MM Dia Top Pipe, 38 MM Dia Vertical upport at every 1.0 Mtr C/C maximum & Two Nos of 20 MM Dia horizontal pipe as per design as per good engineering practice, the end condition of pipe shall be closed with SS Cap & properly grinded. The measurement shall be on outside & not for no. required	2500.00	RMT	Anand PH item no.11
172	Facade such as walls and ceiling and projection by providing Aluminum hollow section of approved quality and make having section size 38mm x 25mm x 1.2mm thick at maximum spacing of 600mm both direction with necessary fittings same in line and level and foxing the frame work with anchor fasteners. The aluminum composite panel 4,00 mm thick be fixed on the frame work having thickness of 1.5mm as per details provided in drawing or as directed by EIC. The in between Grooves between Two panels shall be filled with colour Epoxy as directed by EIC. Necessary cutout for electrical switch board etc., may be made as per instruction without any extra cost.	2357.50	SMT	Undel Furniture item no.14
173	Providing & fixing letter for office made from 3mm thick acrylic sheet maximum up to 0.25 meter in height in English of approved colour including foding with ACP sheet with all tools and tackles as directed.	235.75	No	Undel Furniture item no.15
174	Providing & fixing signage for office made from 3mm thick acrylic sheet maximum up to 0.30 meter in height in Gujarati of approved colour including foding with ACP sheet with all tools and tackles as directed.	253.00	No	Undel Furniture item no.16
175	Acrylic name plate having size 1ft x 4 inch for name and designation	350.00	No	Undel Furniture item no.17
176	Providing & foxing MGVCCL LOGO made from 3mm thick acrylic sheet maximum up to 0.65 meter in height of approved colour including foxing with ACP sheet with all tools and tackles as directed. MS Cupboard shutter: Providing, Fabricating and Fixing in walls M.S. C.R.C. Japan Sheet Of 20 Gauge Frame Inside as Per Requirement On Wall, Floor, Ceiling all around and 20 Gauge Shutter for Cupboard As per Site Requirement with chromium plated fixtures & Fastenings, Loaking arrangement including applying Red Oxide priming coat and painting 2 coats of synthetic enemel paint of Asian make approved shade etc. complete as directed By E.I.C..	1200.00	No	Undel Furniture item no.18
177		4208.00	smt	Nadiad CO item no.93
178	Any item of SOR year 2023-24 of ROADS & BUILDINGS DIVISION Anand(GOG)/Approved PO/Approved rate analysis as per description of items with approved rate.	1.00	No	
	<b>Total Amount with out GST</b>	<b>2500000.00</b>		
	<b>Add 1% labour welfare cess</b>	<b>25000.00</b>		
	<b>Total with labour cess</b>	<b>2525000.00</b>		
	<b>Add 18% GST</b>	<b>454500.00</b>		
	<b>Total with L.C and GST</b>	<b>2979500.00</b>		
	Note:-			
	* I/We am/are willing to carry out the work at rate quoted by me on website www.tender.nprocure.com for the above cited work.			
	* I/We have read & clearly understood the terms, conditions, and Schedule-B & Technical specifications put by MGVCCL on web-site.			
	* GST at applicable rate will be reimbursed in actual to the contractor only after submission of sufficient proof of such payment made to the			
	* Labour welfare cess will be deducted from RA and final bill as per latest prevailing law.			
	* Security Deposit shall be released on successful completion of one year from actual date of completion or finalization of final bill whichever is			
	* work should be carried at <b>various office under Borsad Division office ,MGVCL,.</b>			
	<b>List of MGVCCL offices Borsad Division Office, Borsad City S/Dn Office, Borsad Rural S/Dn Office, Borsad Store, Borsad Lab, Ankilav S/Dn, RAS S/Dn, Vasad S/Dn, Asodar S/Dn</b>			

Madhya Gujarat Vij Company Limited				
Name of Work: Annual rate contract for General maintenance of Offices Under Borsad Division office.				
SN	DESCRIPTION	Rate	UNIT	Code
		Executive Engineer (O&M),		
		MGVCL, Borsad DO		