

Name of Work :- Providing and operating Paver finisher, Pneumatic Road roller, Milling Machine and Dumper for Laying Hot Mix material Supplied by palodar hot mix plant in jurisdiction of R&B Division Mehsana (Annual Rate)

SCHEDULE – B

Memorandum showing item of work to be carried out

Item No.	Quantity Estimated per Ton	Item Description	Estimated Rate (in Rs.) Cost for 8 hour		Unit	Total Amount according to estimated quantities
			In Figure Rs.	In Words Rs.		
1	2	3	4	5	6	7
1	1.00	Providing and operating sensor control Paver finisher having minimum screed size of 7.5 meter with automatic grade and slope control with all necessary sensors for Laying Hot Mix material Supplied by palodar hot mix plant at Road site work under Jurisdiction of R&B Division including all machinery, tools, labours, operating cost, overheads, oil, fuels etc with all lead and lift as directed by engineer in charge.	11027.18	Rupees Eleven Thousand Twenty Seven And Paise Eighteen Only	Hour	11027.18
2	1.00	Providing and operating sensor control Paver finisher having minimum screed size of 5.50 meter with automatic grade and slope control with all necessary sensors for Laying Hot Mix material Supplied by palodar hot mix plant at Road site work under Jurisdiction of R&B Division including all machinery, tools, labours, operating cost, overheads, oil, fuels etc with all lead and lift as directed by engineer in charge.	8780.94	Rupees Eight Thousand Seven Hundred Eighty And Paise Ninety Four Only	Hour	8780.94
3	1.00	Engaging Pneumatic Road Roller for rolling Hot Mix material Supplied by palodar hot mix plant including all machinery, tools, labours, operating cost, overheads, oil, fuels etc with all lead and lift	3247.15	Rupees Three Thousand Two Hundred Forty Seven And Paise Fifteen Only	Hour	3247.15
4	1.00	Engaging Vibrator Roller of 8 to 10 tonne capacity as per instructions of Engineer in charge. (SOR H020)	850.79	Rupees Eight Hundred Fifty And Paise Seventy Nine Only	Hour	850.79
5	1.00	Milling the existing bituminous pavement up to a depth of 50 mm by milling machine in a single cutting depth, to make a uniform surface without disturbing the base including diversion of traffic, removing milled materials and disposal of milled material to an approved dumping yard including loading and unloading, all leads and lift, fuel, lubricant charges etc complete.	78.78	Rupees Seventy Eight And Paise Seventy Eight Only	Cmt	78.78
6	1.00	Carting of Mix/Dry Materials from Government Hot Mix Plant @ Palodar to Various Paver Site including loading, Transporting the Mix/Dry materials and Unloading including the cost of Diesel, Oil, Driver etc. in own Dumper/Turbo as directed by Engineer in Charge.	10.91	Rupees Ten And Paise Ninety One Only	per MT/Km	10.91
Seperate GST will be paid by Department from here on as per the prevailing rate of GST.						

I/ We am / are willing to carry out the work Approve Rate the (Percentage should be written in figure and words only) Estimated rates as mentioned above. amount of my/our tender works out as under.

Estimated Amount

Estimated Amount

Put to tender

Put to tender

Deduct: _____ % below Rs. _____

Add: _____ % above Rs. _____

Net :Rs. _____

Total Rs. _____

In Words Rs. _____

In Words Rs. _____

(Please strike out whichever is not applicable)

Signature of Contractoeer

**Deputy Executive Engineer
R&B Sub Division
Mehsana**