

Name Of Work : Paver Work Labour Charges For Laying of different types of Hot Mix Material to Different site Prepared From Palodar Govt Hot Mix Plant Dist. : Mehsana (annual Rate)

INDEX FOR SPECIFICATION

Item No. in the Schedule B of the Tender.	Description of the item in the Schedule – B of Tender.	Sr. No. of the applicable enclosed Standard specification.	Remarks.
1	Labour Charges for Laying Mix Materials at Various Road Side of Mehsana Dist. And other Dist. where hot mix materials supplied from Govt Plant Palodar.It Includes Cleaning the surfaces by using Brushing with wire brushes for removing caked mud etc. sweeping with brooms on either black top surface or WBM by digging and rubbing the mud of murrum etc andalso remove scarifying materials .Applying track coat by Mechanical Sprayer .Rectifying the irregulaties not cover by Paver.After Consolidation Flusing and sweping of stone dust at 0.30 cum/10 Sq.m area as directed including making arrangement of Safety measures like Traffic Control Safety Instrument Sign Boards,Safety Cone Etc or Labour required to executing the complete work as directed by Engineer In Charge and as per Nomrs MORTH and directed and demanded by Engineer In Charge etc Comp (Paver And Roller & Mechanical Sprayer & Dust Supplied by Department)	As Per MoRTH 5th Revision Clause No 501 Page No149	General Requirements for Bituminous pavement layers shall be followed excluding provision of Hot Mix Material Transporatation , Paver finisher and Roller. Cleaning Existing Surface shall be done by means of Manual Methods. Rate Shall be Matric Tonns Basis on actual work done on site of work.
2	Labour Charges for Laying Mix Materials at Various Road Side of Mehsana Dist. And other District where hot mix materials supplied from Govt Plant Palodar.It Includes Cleaning the surfaces by means of Manual Or Mechanical Air compressor tractor/truck Mounted as required by Engineer in charge on either black top surface or WBM surface by digging and rubbing the mud of murrum etc and also remove scarifying materials with Applying tack coat by Mechanical Sprayer .Rectifying the irregulaties not cover by Paver.After Consolidation Flushing and sweeping of stone dust at 0.30 cum/10 Sq.m area as directed including making arrangement of Safety measures like Traffic Control Safety Instrument Sign Boards,Safety Cone Etc or Labour required to executing the complete work as directed by Engineer In Charge and as per Nomrs MORTH and directed and demanded by Engineer In Charge etc Comp (Paver And Roller & Mechanical Sprayer & Dust Supplied by Department)	As Per MoRTH 5th Revision Clause No 501 Page No150	General Requirements for Bituminous pavement layers shall be followed excluding provision of Hot Mix Material Transportation , Paver finisher and Roller. Cleaning Existing Surface shall be done by means of Manual or Mechanical tractor/truck mounted air compressor as required by engineer in charge. Rate Shall be Matric Tons Basis on actual work done on site of work.
3	laying asphalt painting on BT surface with bitumen grade at the rate of 5 Kg /10 Sqm. By mechanical sprayer and spreading the stone dust on prepared surface at the rate of 0.03 Cum. / 10 Sqm. etc. complete (Mechanical Sprayer & Dust Supplied by Department)	As per Separate Sheet Attached	Payment Should Be made on Sqm Basis on Complete Item

Signature of
Contractor.

DY.EXECUTIVE ENGINEER
R & B SUB DIVISION, Mehsana

EXECUTIVE ENGINEER
R & B DIVISION, MEHSANA