

**Name Of Work : Paver Work Labour Charges For Laying of different types of Hot Mox Material to Different site Prepared From Palodar Govt Hot Mix Plant Dist : Mehsana (Annual Rate)**

**SCHEDULE – B**

It. No.	Quantities estimated but may be more or less	Item of Work	Estimated rate		Unit	Total Amount according to estimated quantities
			In Figure	In words		
1	2	3	4	5	6	7
1	1.00	Labour Charges for Laying Mix Materials at Various Road Side of Mehsana Dist. And other Dist where hot mix materials supplied from Govt Plant Palodar.It Includes Cleaning the surfaces by using Brushing with wire brushes for removing caked mud etc. sweeping with brooms on either black top surface or WBM by digging and rubbing the mud of murrum etc andalso remove scarifying materials .Applying track coat by Mechanical Sprayer .Rectifying the irregulates not cover by Paver.After Consolidation Flusing and sweeping of stone dust at 0.30 cum/10 Sq.m area as directed including making arrangement of Safety measures like Traffic Control Safety Instrument Sign Boards,Safety Cone Etc or Labour required to executing the complete work as directed by Engineer In Charge and as per Nomrs MORTH and directed and demanded by Engineer In Charge etc Comp ( Paver And Roller & Mechanical Sprayer & Dust Supplied by Department )	127.79	Rupees One Hundred Twenty Seven And Paise Seventy Nine Only	MT	127.79
2	1.00	Labour Charges for Laying Mix Materials at Various Road Side of Mehsana Dist. And other District where hot mix materials supplied from Govt Plant Palodar.It Includes Cleaning the surfaces by means of Manual Or Mechanical Air compressor tractor/truck Mounted as required by Engineer in charge on either black top surface or WBM surface by digging and rubbing the mud of murrum etc and also remove scarifying materials with Applying tack coat by Mechanical Sprayer .Rectifying the irregulates not cover by Paver.After Consolidation Flushing and sweeping of stone dust at 0.30 cum/10 Sq.m area as directed including making arrangement of Safety measures like Traffic Control Safety Instrument Sign Boards,Safety Cone Etc or Labour required to executing the complete work as directed by Engineer In Charge and as per Nomrs MORTH and directed and demanded by Engineer In Charge etc Comp ( Paver And Roller & Mechanical Sprayer & Dust Supplied by Department )	139.61	Rupees One Hundred Thirty Nine And Paise Sixty One Only	MT	139.61
3	1.00	laying asphalt painting on BT surface with bitumen grade at the rate of 5 Kg /10 Sqm. By mechanical sprayer and spreading the stone dust on prepared surface at the rate of 0.03 Cum. / 10 Sqm. etc. complete ( Mechanical Sprayer & Dust Supplied by Department )	21.35	Rupees Twenty One And Paise Thirty Five Only	Smt	21.35

(A) I/We am/are willing to carry out the work at \_\_\_\_\_% above/below the (percentage should bewritten in figure and words only) Estimated rates as mentioned above,amount of my/our tender works out as under.

Signature of contract

Deputy Executive Engineer  
( R & B ) Sub Div.  
Mahesana

Executive Engineer  
( R & B ) Division  
Mehsana