

**UPLETA NAGARPALIKA - UPLETA
DIST.- RAJKOT**

**SCHEME:- SJMMSVY (UDP-88) YEAR-2023-24 & ROAD RESURFACING GRANT (YEAR-2025-26)
NAME OF WORK:- RESURFACING WORK OF C.C. TRENCH, AS PER LOCATION CHART, AT. UPLETA**

TOTAL AMOUNT PUT TO TENDER

PERCENTAGE RATE TENDER

Sr.No.	Schedule	Amount
1	Schedule - "B"- 1	22,92,267.73
2	Schedule - "B"- 2	33,27,328.57
Total Amount Rs.....		56,19,596.30
Say Rs.....		56,19,596.00

I/We am/are willing to carry out the work @ _____% Above / Below _____Percentage (should be written in figures and words) of the Estimated rates mentioned above amount of my / our Tender works out as under.

<u>Estimated Amount</u>	<u>Estimated Amount</u>
Put to Tender Rs. 56,19,596=00	Put to Tender Rs. 56,19,596=00
Add% Rs.	Deduct% Rs.
Total Rs.	Total Rs.
(In Words	(In Words

Stamp with Signature of Contractor

Consl.Engineer
"DESIGN POINT"
Amreli

Engineer
Upleta Nagarpalika
Upleta

Chief Officer
Upleta Nagarpalika
Upleta

President
Upleta Nagarpalika
Upleta

UPLETA NAGARPALIKA - UPLETA
DIST :- RAJKOT
SCHEME :- SJMMSVY (UDP-88) YEAR-2023-24
NAME OF WORK :- RESURFACING WORK OF C.C. TRENCH

Location Chart For Schedule "B-1"

No.	Location	Length	Width	Area
1	Bus Stand Chowk to Molla Patel Colony, Dhank Marg	1500.00	0.90	1350.00
2	Sarvoday Society, Behind Leva Patel Samaj	220.00	0.90	198.00
3	Mandap Road to Rajmotinagar Main Road	120.00	0.90	108.00
4	Rajmotinagar Garabi Sheri, Haribhai Thummar House	120.00	0.90	108.00
Total :-		1960.00		1764.00

Stamp with Signature of Contractor

Cons. Engineer
"DESIGN POINT"
Amreli

Municipal Engineer
Upleta Nagarpalika
Upleta

Chief Officer
Upleta Nagarpalika
Upleta

President
Upleta Nagarpalika
Upleta

UPLETA NAGARPALIKA - UPLETA
DIST.- RAJKOT
SCHEME:- SJMMSVY (UDP-88) YEAR-2023-24
NAME OF WORK : RESURFACING WORK OF C.C. TRENCH
LOCATION :- As Per Location Chart, At. Upleta

SCHEDULE - "B-1"

PERCENTAGE RATE TENDER				
Item No. & Description	Quantity	Rate	Per	Amount
Item No. 1				
Box cutting the road surface to proper slope and camber for making a base for road work including ramming the excavated stuff and despositing on the road side slope as directed up to all lead.	441.00	197.06	Cumt.	86,903.46
Item No. 2				
Supplying of crushed stone aggregate Chipping etc.of hard stone of following niminal size free of disintegrated pieces deleterious and orianic mater (for Bitumen surface dressing etc.) and grading as per I.R.C. code (ii) 40mm	264.60	639.33	Cumt.	1,69,166.72
Item No. 3				
Spreding the stone aggregate for rolling of W.B.M. including filling the interestices to required camber and gradient. (ii) 40mm to 63mm size aggregate (M.C.)	264.60	274.73	Cumt.	72,693.56
Item No. 4				
Providing and laying cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 Machine cut stone aggregate 40mm nominal size) and curring complete including cost of formwork in (a) Foundation and plinth	176.40	3260.28	Cumt.	5,75,113.39
Item No. 5				
Providing and casting in situ controlled cement concrete M- 200 for average 75 mm thick wearing coat laid as directed dincluding tamping, vibrating, finishing, curing and filling in joints with bitumen complete.	264.60	5247.13	Cumt.	13,88,390.60
Total Amount Rs.....				22,92,267.73

Stamp with Signature of Contractor

Consl.Engineer
"DESIGN POINT"
 Amreli

Engineer
Upleta Nagarpalika
 Upleta

Chief Officer
Upleta Nagarpalika
 Upleta

President
Upleta Nagarpalika
 Upleta

UPLETA NAGARPALIKA - UPLETA
DIST :- RAJKOT
SCHEME :- ROAD RESURFACING GRANT (YEAR-2025-26)
NAME OF WORK :- RESURFACING WORK OF C.C. TRENCH

Location Chart For Schedule "B-2"

No.	Location	Length	Width	Area
1	Royal Shoes to Kiritbhai Shah House, Vijadi Road	335.00	0.90	301.50
2	W-2, Jil Mill chowk to Muchada chowk	790.00	0.90	711.00
3	W-7, Tagor Road (Amber Pan to Jitubhai Bakthariya)	605.00	0.90	544.50
4	W-3, Dwarkadhis Society Main road (Yash Provision to Hiteshbhai Vyas House Cornar)	135.00	0.90	121.50
5	W-3,6,7, Sardar Patel Road, Shree Tailor to Nandanvan House	980.00	0.90	882.00
Total :-		2845.00		2560.50

Stamp with Signature of Contractor

Cons. Engineer
"DESIGN POINT"
 Amreli

Municipal Engineer
Upleta Nagarpalika
 Upleta

Chief Officer
Upleta Nagarpalika
 Upleta

President
Upleta Nagarpalika
 Upleta

UPLETA NAGARPALIKA - UPLETA
DIST.- RAJKOT
SCHEME:- ROAD RESURFACING GRANT (YEAR-2025-26)
NAME OF WORK : RESURFACING WORK OF C.C. TRENCH
LOCATION :- As Per Location Chart, At. Upleta

SCHEDULE - "B-2"

PERCENTAGE RATE TENDER				
Item No. & Description	Quantity	Rate	Per	Amount
Item No. 1				
Box cutting the road surface to proper slope and camber for making a base for road work including ramming the excavated stuff and despositing on the road side slope as directed up to all lead.	640.13	197.06	Cumt.	1,26,144.02
Item No. 2				
Supplying of crushed stone aggregate Chipping etc.of hard stone of following niminal size free of disintegrated pieces deleterious and orianic mater (for Bitumen surface dressing etc.) and grading as per I.R.C. code (ii) 40mm	384.08	639.33	Cumt.	2,45,553.87
Item No. 3				
Spreding the stone aggregate for rolling of W.B.M. including filling the interestices to required camber and gradient. (ii) 40mm to 63mm size aggregate (M.C.)	384.08	274.73	Cumt.	1,05,518.30
Item No. 4				
Providing and laying cement concrete 1:3:6 (1 cement : 3 coarse sand : 6 Machine cut stone aggregate 40mm nominal size) and curring complete including cost of formwork in (a) Foundation and plinth	256.05	3260.28	Cumt.	8,34,794.69
Item No. 5				
Providing and casting in situ controlled cement concrete M- 200 for average 75 mm thick wearing coat laid as directed dincluding tamping, vibrating, finishing, curing and filling in joints with bitumen complete.	384.08	5247.13	Cumt.	20,15,317.69
Total Amount Rs.....				33,27,328.57

Stamp with Signature of Contractor

Consl.Engineer
"DESIGN POINT"
 Amreli

Engineer
Upleta Nagarpalika
 Upleta

Chief Officer
Upleta Nagarpalika
 Upleta

President
Upleta Nagarpalika
 Upleta