

SCHEDULE-B

Sub:-ARC work for the Installation of Chemical Earthing at various Transformer Center Through out sourced agency for Existing DGVCL Network at jurisdiction of Kadodara-1 Sub division under Kadodara Division

Sr.No	Description Of Supply	Qty.	Unit	Rate	Total Amount
1	Model :- ETP/HDR/17/2 (or Similar) Type :- GI Solid earthing electrode (Rod) Diameter :- 17 mm Terminal Size :- 25mm * 6 mm Length :- 2 Mtr. With clamp and 2 nos of M10 Size SS nut & Bolts with connection of earthing terminal to T/C neutral separately using 25mm*3mm Hot dip GI strip (Per Transformer 04 Mtr GI patii) Installation of the earthing PIT work includes suppl and labours for connection in all Respect		No.	1400	
2	Ground conductivity improve material GCIM Hygrolite net weight : 15 Kg*1 bags		No.	220	
In Words:- Ten Lac only.					1000000/-

Deputy Engineer (O&M)
D.G.V. Co. Ltd.
Kadodara-1 Sdn.
DGVCL