


ಪುರಸಭೆ ಕಾರ್ಯಾಲಯ, ರಾಮದುರ್ಗ

ಮುಖ ಪುಟ

- ಸ್ಥಳೀಯ ಸಂಸ್ಥೆಯ ಹೆಸರು : ಪುರಸಭೆ ಕಾರ್ಯಾಲಯ ರಾಮದುರ್ಗ
- ಲೆಕ್ಕ ಶೀರ್ಷಿಕೆ : ಸ್ವಚ್ಛ ಭಾರತ್ ಮಿಷನ್ (ನ) 2.0 ಅಡಿಯ ಅನುದಾನ
- ಮುಖ್ಯ ಶೀರ್ಷಿಕೆ : ಸ್ವಚ್ಛ ಭಾರತ್ ಮಿಷನ್ (ನ) 2.0 ಅಡಿಯ ಅನುದಾನ
- ಇಲಾಖಾ ಶೀರ್ಷಿಕೆ : ಸ್ವಚ್ಛ ಭಾರತ್ ಮಿಷನ್ (ನ) 2.0 ಅಡಿಯ ಅನುದಾನ
- ಕೆಲಸದ ಹೆಸರು : ಪುರಸಭೆ ವ್ಯಾಪ್ತಿಯ ಮಿನಿ ವಿಧಾನಸೌದದ ಹತ್ತಿರ ಸಾರ್ವಜನಿಕ ಶೌಚಾಲಯ ನಿರ್ಮಾಣ ಮಾಡುವುದು
- ಅಂದಾಜು ಮೊತ್ತ ರೂ. : 19.50 ಲಕ್ಷ
- ಕ್ರಿಯಾ ಯೋಜನೆ : ಮಾನ್ಯ ಜಿಲ್ಲಾಧಿಕಾರಿಗಳು ಬೆಳಗಾವಿ ಇವರ ಆದೇಶ ಸಂಖ್ಯೆ :
ಮಂಜೂರಾತಿ ಪತ್ರ ಸಂ: ಬಿಜಿಎಂ/ಡಿಯುಡಿಸಿ/6/ಸಿಆರ್/2025-26 ದಿನಾಂಕ : 16-03-2026
- ಆಡಳಿತಾತ್ಮಕ ಮಂಜೂರಾತಿ : ಆಡಳಿತಾಧಿಕಾರಿಗಳು ಪುರಸಭೆ ರಾಮದುರ್ಗ ಇವರ ಠರಾವ ನಂ. 377
ದಿನಾಂಕ : 29-01-2026
- ಅಂದಾಜು ಪತ್ರಿಕೆ : ಎಂ.ಎನ್. ಪಾಟೀಲ ಕಿರಿಯ ಅಭಿಯಂತರರು [ಸಿಬ್ಬಿಲ್]
- ತಯಾರಿಸಿದವರು

ಸಾಮಾನ್ಯ ವಿವರಣೆ

ಸ್ವಚ್ಛ ಭಾರತ್ ಮಿಷನ್ (ನ) 2.0 ಅಡಿಯ ಅನುದಾನದಡಿಯಲ್ಲಿ ಪುರಸಭೆ ವ್ಯಾಪ್ತಿಯ ಮಿನಿ ವಿಧಾನಸೌದದ ಹತ್ತಿರ ಸಾರ್ವಜನಿಕ ಶೌಚಾಲಯ ನಿರ್ಮಾಣ ಮಾಡುವುದು ಕಾಮಗಾರಿಯನ್ನು ಸನ್ 2023-24 ನೇ ಸಾಲಿನ ಲೋಕೋಪಯೋಗಿ ಇಲಾಖೆಯ ದರಗಳನ್ನು ತೆಗೆದುಕೊಂಡು ಅಂದಾಜು ಪತ್ರಿಕೆಯನ್ನು ತಯಾರಿಸಿರುತ್ತದೆ ಹಾಗೂ ಸದರಿ ಕೆಲಸವನ್ನು ಬೇರೆ ಯಾವುದೇ ಅನುದಾನದಲ್ಲಿ ತೆಗೆದುಕೊಂಡಿರುವುದಿಲ್ಲ.


ಕಿರಿಯ ಅಭಿಯಂತರರು,
ಪುರಸಭೆ ರಾಮದುರ್ಗ

ಮುಖ್ಯಾಧಿಕಾರಿಗಳು
ಪುರಸಭೆ ರಾಮದುರ್ಗ

ಜಿಲ್ಲಾ ನಗರಾಭಿವೃದ್ಧಿ ಕೋಶ, ಬೆಳಗಾವಿ


ಸಹಾಯಕ ಕಾರ್ಯನಿರ್ವಾಹಕ ಇಂಜಿನಿಯರರು, ಜಿಲ್ಲಾ ನಗರಾಭಿವೃದ್ಧಿ ಕೋಶ
ಜಿಲ್ಲಾಧಿಕಾರಿಗಳ ಕಾರ್ಯಾಲಯ ಬೆಳಗಾವಿ ಇವರ ನಡುವಳಿಗಳು

ವಿಷಯ: ಸ್ವಚ್ಛ ಭಾರತ್ ಮಿಷನ್ (ನ) 2.0 ಅಡಿಯ ಅನುದಾನ

ಉಲ್ಲೇಖ: ಮಾನ್ಯ ಜಿಲ್ಲಾಧಿಕಾರಿಗಳು ಬೆಳಗಾವಿ ಇವರ ಆದೇಶ ಸಂಖ್ಯೆ :
ಬಿಜಿಎಂ/ಡಿಯುಡಿಸಿ/6/ಸಿಆರ್/2025-26 ದಿನಾಂಕ : 16-03-2026

||ಆದೇಶ||

ಬೆಳಗಾವಿ ಜಿಲ್ಲೆಯ ರಾಮದುರ್ಗ ತಾಲೂಕಿನ ಪುರಸಭೆ ವ್ಯಾಪ್ತಿಯ ಮಿನಿ ವಿಧಾನಸೌದದ ಹತ್ತಿರ
ಸಾರ್ವಜನಿಕ ಶೌಚಾಲಯ ನಿರ್ಮಾಣ ಮಾಡುವುದು ಕಾಮಗಾರಿಯ ಅಂದಾಜು ವೆಚ್ಚ ಪಟ್ಟಿ ಮತ್ತು ನಕ್ಷೆಗಳಿಗೆ. ರೂ.
19,50,000 (ಅಕ್ಷರದಲ್ಲಿ). ಹತ್ತೊಂಬತ್ತು ಲಕ್ಷ ಐವತ್ತು ಸಾವಿರ ಮಾತ್ರ ಶರತ್ತಿಗೊಳಪಟ್ಟ ತಾಂತ್ರಿಕ
ಮಂಜೂರಾತಿಯನ್ನು ಈ ಮೂಲಕ ನೀಡಲಾಗಿದೆ. ಸದರಿ ಕಾಮಗಾರಿಯ ವೆಚ್ಚವನ್ನು ಲೆಕ್ಕ ಶೀರ್ಷಿಕೆ: ಸ್ವಚ್ಛ
ಭಾರತ್ ಮಿಷನ್ (ನ) 2.0 ಅಡಿಯ ಅನುದಾನದಡಿ ಭರಿಸತಕ್ಕದು. ಸದರಿ ಕಾಮಗಾರಿಯ ಅಂದಾಜು
ಪಟ್ಟಿಯನ್ನು ಈ ಕಛೇರಿಯ ನೋಂದಣಿ ಸಂಖ್ಯೆ: ಬಿಜಿಎಂ/ಡಿಯುಡಿಸಿ/6/ಸಿಆರ್/2025-26 6/4/2026 ರಲ್ಲಿ
ನೋಂದಾಯಿಸಲಾಗಿದೆ.


6/4/26

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು,
ಜಿಲ್ಲಾ ನಗರಾಭಿವೃದ್ಧಿ ಕೋಶ, ಬೆಳಗಾವಿ.

ತಾಂತ್ರಿಕ ಟಿಪ್ಪಣಿ

1. ಕೆಲಸ ಪ್ರಾರಂಭಿಸುವ ಮೊದಲು ಕೆಲಸಕ್ಕೆ ಬೇಕಾಗುವ ಸ್ಥಳವು ನಗರಸಭೆ/ ಪುರಸಭೆ/ ಪಟ್ಟಣ ಪಂಚಾಯತಿ ಹೆಸರಿನಲ್ಲಿರಬೇಕು.
2. ಸದರಿ ಕೆಲಸ ಪ್ರಾರಂಭಿಸುವ ಮುನ್ನ ಯಾವುದೇ ಬದಲಾವಣೆ ಇದ್ದಲ್ಲಿ ಸಕ್ಷಮ ಅಧಿಕಾರಿಗಳಿಂದ ಮುನ್ನಣೆ ಪಡೆಯಬೇಕು.
3. ಐ.ಆರ್.ಸಿ. ಪ್ರಕಾರ ಅಣವೇಶನ್ ಮತ್ತು ಕೆಂಬರ್, ಹಾರಿಜಂಟಲ್ ಹಾಗೂ ವರ್ಟಿಕಲ್ ತಿರುವುಗಳನ್ನು ಅಳವಡಿಸಿ ಕೆಲಸವನ್ನು ಮಾಡಬೇಕು.
4. ಕೆಲಸ ಪ್ರಾರಂಭಿಸುವ ಮುನ್ನ ಎಲ್ಲ ಸಾಮಗ್ರಿಗಳು ಗುಣಮಟ್ಟ ಪರೀಕ್ಷಿಸಿಕೊಳ್ಳಬೇಕು.
5. ಕಟ್ಟಡ, ಸೇತುವೆಗಳ ತಳಪಾಯದ ಕಾಂಕ್ರೀಟ್ ಹಾಕುವ ಮುನ್ನ ಸದರಿ ಮಣ್ಣಿನ ಪರೀಕ್ಷೆ ಮಾಡಿಸಿ ಎಸ್.ಬಿ.ಸಿಯಂತೆ ವಿನ್ಯಾಸ ಮಾಡಿಸಿ ಸಹಾಯಕ ಕಾರ್ಯಕಾರಿ ಅಭಿಯಂತರರು ಮತ್ತು ಕಾರ್ಯಕಾರಿ ಅಭಿಯಂತರರಿಂದ ಸ್ಥಳ ಪರಿಶೀಲಿಸಿ ನಂತರ ಕಾಂಕ್ರೀಟ್ ಹಾಕುವುದು.
6. ಕಾಮಗಾರಿ ಪ್ರಾರಂಭದ ನಂತರ ಹಂತವಾಗಿ ಸಕ್ಷಮ ಅಧಿಕಾರಿಗಳಿಂದ ವೀಕ್ಷಣೆ ಮಾಡಿಸಿಕೊಳ್ಳಬೇಕು ಮತ್ತು ಸ್ಥಳದಲ್ಲಿ ಆದೇಶದಂತೆ ಕಾಮಗಾರಿಗಳನ್ನು ಕೈಕೊಳ್ಳಬೇಕು.
7. ಕೆಲಸ ಪ್ರಾರಂಭಿಸುವ ಪೂರ್ವದಲ್ಲಿ ಸ್ಥಳ ಪರಿಶೀಲನೆ ಮಾಡಿ ಸೂಕ್ತವಾಗಿ ನಕ್ಷೆ ಮತ್ತು ವಿವರವಾದ ವಿನ್ಯಾಸವನ್ನು ಸಲ್ಲಿಸಿ ಅನುಮೋದನೆಯನ್ನು ಪಡೆದುಕೊಳ್ಳುವುದು.
8. ಕಾಮಗಾರಿಯನ್ನು ಲೋಕೋಪಯೋಗಿ ಇಲಾಖೆ ನಿಮಾನುಸಾರ ಹಾಗೂ ಕರ್ನಾಟಕ ಪಾರದರ್ಶಕತೆ ಕಾಯ್ದೆಗನುಗುಣವಾಗಿ ಕೈಕೊಳ್ಳಬೇಕು.
9. ಕಾಮಗಾರಿಯ ವೆಚ್ಚವನ್ನು ತಾಂತ್ರಿಕ ವೆಚ್ಚಕ್ಕೆ ಸೀಮಿತಗೊಳಿಸಬೇಕು.
10. ಕೆಲಸ ಪ್ರಾರಂಭಿಸುವ ಮುಂಚೆ ತಾಂತ್ರಿಕ ಟಿಪ್ಪಣಿ ನಿಬಂಧನೆಯನ್ನು ಪಾಲಿಸಿ ವರದಿಯನ್ನು ಸಲ್ಲಿಸಬೇಕು.
11. ಅಂದಾಜು ಪಟ್ಟಿಯಲ್ಲಿ ಒದಗಿಸಿರುವ ಇಡಗಂಟು ಪ್ರಸ್ತಾವನೆಯ ಐಟಂಗಳಿಗೆ ವಿವರವಾದ ಅಂದಾಜು ಪಟ್ಟಿಗಳಲ್ಲಿ ಸಲ್ಲಿಸಿ ಅನುಮೋದನೆ ಪಡೆದುಕೊಳ್ಳಬೇಕು.
12. ಒಳಚರಂಡಿಗೆ ಸರಿಯಾದ ಇಳಿಜಾರು (Proper Slope) ಕೊಟ್ಟು, ನೀರು ಸಲೀಸಾಗಿ ಹರಿದು ಹೋಗುವಂತೆ ಮಾಡುವುದು ಹಾಗೂ ಪ್ರತಿ 30.00 ಮೀಟರಿಗೆ ಒಂದರಂತೆ ಲೇವಲ್‌ಗಳನ್ನು ತೆಗೆಕೊಳ್ಳುವುದು.

 6/4/26

ಸಹಾಯಕ ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು,
ಜಿಲ್ಲಾ ನಗರಾಭಿವೃದ್ಧಿ ಕೋಶ, ಬೆಳಗಾವಿ.

ಕಛೇರಿ ಟಿಪ್ಪಣಿ ಸಲ್ಲಿಸಲಾಗಿದೆ.

ವಿಷಯ : ಪುರಸಭೆ ವ್ಯಾಪ್ತಿಯ ಮಿನಿ ವಿಧಾನಸೌದದ ಹತ್ತಿರ ಸಾರ್ವಜನಿಕ ಶೌಚಾಲಯ ನಿರ್ಮಾಣ ಮಾಡುವುದು ಕಾಮಗಾರಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡುವ ಕುರಿತು.

ಉಲ್ಲೇಖ : 1) ಸ್ವಚ್ಛ ಭಾರತ್ ಮಿಷನ್ (ನ) 2.0 ಅಡಿಯ ಅನುದಾನ
2) ಮಾನ್ಯ ಜಿಲ್ಲಾಧಿಕಾರಿಗಳು ಬೆಳಗಾವಿ ಇವರ ಆದೇಶ ಸಂಖ್ಯೆ :
ಬಿಜಿಎಂ/ಡಿಯುಡಿಸಿ/6/ಸಿಆರ್/2025-26 ದಿನಾಂಕ : 16-03-2026

ಮೇಲ್ಕಾಣಿಸಿದ ಉಲ್ಲೇಖದ ಪ್ರಕಾರ: ಮಾನ್ಯ ಜಿಲ್ಲಾಧಿಕಾರಿಗಳು ಮಂಜೂರಾತಿ ನೀಡಿದ ಪ್ರಕಾರ :
ಪುರಸಭೆ ವ್ಯಾಪ್ತಿಯ ಮಿನಿ ವಿಧಾನಸೌದದ ಹತ್ತಿರ ಸಾರ್ವಜನಿಕ ಶೌಚಾಲಯ ನಿರ್ಮಾಣ ಮಾಡುವುದು
ಕಾಮಗಾರಿಯ ಅಂದಾಜು ವೆಚ್ಚ ಪಟ್ಟಿ ಮತ್ತು ನಕ್ಷೆಗಳಿಗೆ. 19,50,000.00 (ಅಕ್ಷರದಲ್ಲ). ಹತ್ತೊಂಬತ್ತ ಲಕ್ಷ
ಐವತ್ತು ಸಾವಿರ ಮಾತ್ರ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿಗಾಗಿ ಸಲ್ಲಿಸಿದೆ.

ಸದರಿ ಅಂದಾಜು ಪತ್ರಿಕೆಯಲ್ಲಿ ಈ ಕೆಳಗಿನ ಕೆಲಸಗಳನ್ನು ಅಳವಡಿಸಲಾಗಿದೆ.

ಮತ್ತು ಅವಶ್ಯವಿರುವ ವಿವರಗಳನ್ನು ಅಳವಡಿಸಿ ಅಂದಾಜು ಪಟ್ಟಿಯನ್ನು ರೂ. 19.50ಲಕ್ಷ ಗಳಿಗೆ
ಪರಿಶೀಲಿಸಿದ್ದು ಸದರಿ ಅಂದಾಜು ಪತ್ರಿಕೆಯನ್ನು ಅನುಮೋದಿಸಿದೆ.

ವಿಷಯ ನಿರ್ವಾಹಕ

ಸಹಾನಿ:

TOWN MUNICIPAL COUNCIL, RAMDURG

DIST: BELGAUM

ಯೋಜನೆ ಹೆಸರು :- ಸ್ವಚ್ಛ ಭಾರತ್ ಮಿಷನ್ (ಸ) 2.0 ಅಡಿಯ ಅನುದಾನ

ಕಾಮಗಾರಿ ಹೆಸರು :- ಪುರಸಭೆ ವ್ಯಾಪ್ತಿಯ ಮಿನಿ ವಿಧಾನಸೌಧದ ಹತ್ತಿರ ಸಾರ್ವಜನಿಕ ಶೌಚಾಲಯ ನಿರ್ಮಾಣ ಮಾಡುವುದು. (13 Seat)

DETAILED ESTIMATE:

Sl. No	Particulars of Items of Work	No's	Length, L in m	Breadth, B in m	Depth, D in m	Quantity	Unit	Rate in Rs.	Amount in Rs.
1	Earth work excavation by manual means for drains, canals, waste weir draft, approach channels, key trench, foundation of Bridges and such similar works, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, excavated surface leveled and sides neatly dressed disposing off or leveling the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage & other appurtenances required to complete the work. It No. 1.5.1 P.No. 6 In ordinary/soft rock without blasting upto 1.5 m depth S.R 2023-24 (Volume-I) Basic Rate 299.00 Add 5% AW* 14.95 Total 313.95								
	Septic Tank	1	9.50	5.30	1.50	75.53			
	Steps	1	2.30	1.20	0.30	0.83			
	Sewage Lene	1	15.00	0.45	1.00	6.75			
						83.10	Cum	313.95	26090.19
2	Providing and laying in position Cement Concrete for levelling course for all works in foundation. The granite/trap/basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed, laid in layers not exceeding 150 mm thickness, well compacted using plate vibrators, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing, and all the other appurtenances required to complete the work as per technical specifications. Mix 1:3:6 Using 40 mm nominal size graded crushed coarse aggregates No. 2.1.3 P.No. 15 S.R 2023-24 (Volume-I) Basic Rate 5989.00 Add 5% AW* 299.45 Total 6288.45								
	Septic Tank	1	9.50	5.00	0.15	7.13			
	Steps	1	2.30	1.20	0.15	0.41			
						7.54	Cum	6288.45	47408.62
3	Providing and laying in Cement Concrete for all Basement & surface level works, return walls, retaining walls, sunken floors etc. The granite/trap/ basalt crushed graded coarse aggregates and fine aggregates as per relevant IS Codes machine mixed with super plasticisers, laid in layers, well compacted using needle vibrators, providing weep holes wherever necessary, including all lead & lifts, cost of all materials of quality, labour, Usage charges of machinery, curing and all other appurtenances required to complete the work as per technical specifications. M20 Design Mix Using 20 mm nominal size graded crushed coarse aggregates PWD SR 2023-24 Page No 15 I No 2.3.1 Base Rate 6323.00 Add 5% 316.10 =6639.10 (Volume-I)								
	Septic Tank Raft	1	9.50	5.00	0.15	7.13			
	Long Wall	2	9.50	0.20	2.00	7.60			
	Short Wall	4	4.90	0.20	2.00	7.84			
	Septic Tank Slab	1	9.50	5.30	0.15	7.55			
	Lintal	4	9.50	0.23	0.15	1.31			
	Lintal	2	5.00	0.23	0.15	0.35			
	Beam	3	9.50	0.23	0.30	1.97			
	Beam	2	4.60	0.23	0.30	0.63			

	Slab	1	10.70	6.20	0.12	7.96			
						42.34	Cum	6639.10	281070.28
4	Addendum I – Percentage Additionalities for Formwork, Centering & Scaffolding As per recommendations of Technical working group, rates for formwork shall be added on percentage basis to the finished concrete item rate as per table below : Foundation, Sub structure (5%) SI No. 4 P.No. 111 S.R 2023-24 (Volume-I) Rate *35%/100=2323.68								
	Septic Tank Raft	1	9.50	5.00	0.15	7.13			
	Long Wall	2	9.50	0.20	2.00	7.60			
	Short Wall	4	4.90	0.20	2.00	7.84			
	Septic Tank Slab	1	9.50	5.30	0.15	7.55			
	Lintal	4	9.50	0.23	0.15	1.31			
	Lintal	2	5.00	0.23	0.15	0.35			
	Beam	3	9.50	0.23	0.30	1.97			
	Beam	2	4.60	0.23	0.30	0.63			
	Slab	1	10.70	6.20	0.12	7.96			
						42.34	Cum	2323.68	98374.39
5	Providing Brick work with common burnt clay Non Modular bricks of class designation 3.5 in superstructure above plinth level in all shapes and sizes in Cement mortar 1:6 (1 cement : 6 coarse sand) including cost of all materials, labour, scaffolding and usage charges of machinery & other incidental charges complete as per the direction of engineer incharge of work. PWD SR 2023-24 Page No 14 I No 6.8 Base Rate 7969.00 Add 5% 398.45 =8367.45 (Volume-I)								
	Ground Floor								
	L/W	4	9.50	0.23	2.60	22.72			
	S/W	2	4.50	0.23	2.60	5.38			
		8	1.20	0.23	2.60	5.74			
	Tank	2	4.50	0.23	1.20	2.48			
						36.33			
	Steps	1	2.00	1.20	0.15	0.36			
	Steps	1	2.00	0.90	0.15	0.27			
	Steps	1	2.00	0.60	0.15	0.18			
	Steps	1	2.00	0.30	0.15	0.09			
						37.23			
	Deduction Door	14	0.75	0.23	2.10	5.07			
						32.16	Cum	8367.45	269091.33
6	Providing 12 mm cement plaster with cement mortar 1:4 (1 cement: 4 fine sand) to brick masonry including rounding off corners wherever required smooth rendering, providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications and as per directions of Engineer-in-charge. SR 2023-24 Page No 41 I No 8.1.1 Base Rate 255.00 Add 5% 12.75 =267.75 (Volume-III)								
	Septc Tank	2	9.50		1.80	34.20			
		8	4.60		1.80	66.24			
	Out Side	2	9.50		3.50	66.50			
	Out Side	2	5.00		3.50	35.00			
	In Side	6	7.00		2.60	109.20			
	In Side	2	5.00		2.60	26.00			
	In Side	20	1.20		2.60	62.40			
	Tank	6	4.50		1.20	32.40			
	Septc Tank Slab	1	9.50		5.00	47.50			
	Roof Slab	1	10.70		6.00	64.20			
						543.64			
	Deduction Door	14	0.75		2.00	21.00			
						522.64	Sqm	267.75	139936.86

7	Providing & fixing 30mm thick factory made rigid foam Panelled Door Shutters made from M.S. tube of 19 gauge thickness, size 19x19mm for stiles and 15x15mm for top & bottom rails, covered with heat moulded PVC C channel of 5mm thick sheet & 30 x 50mm wide to form stiles & 5mm thick & 75mm wide PVC Sheets for top rail, lock rail & bottom rail on either side & 5mm thick 20mm wide PVC sheet as gap insert for top rail & bottom rail, Panelling of 5mm thick PVC sheet fitted in the M.S. Frame, Sealed to the stiles & rails with 5x30mm PVC sheet beading on either side & joined together with solvent cement adhesive etc., Complete as per manufacturers specification & direction of Engineer-in-charge fixed to frames with 3 nos of 75 mm Aluminium hinges. SR 2023-24 Page No104 I No 12.53 Base Rate 1588.00 Add 5% 79.40 =1667.40 (Volume-II)								
	Doors	14	0.75		2.10	22.05			
						22.05	Sqm	1667.40	36766.17
8	Providing & fixing factory made PVC Door frame of size 50x47mm with a wall thickness of 5mm, made out of extruded 5mm rigid PVC foam sheet metered cut at corners & jointed 2 No.s of 150mm long brackets of 15x15mm M.S Square tube, the entire door frame to be reinforced with 19x19mm M.S Square tube of 19 gauge. The door frame to be fixed to the wall using M.S. Screws of 65/80mm size complete as per manufacturers specification & direction of Engineer-in-charge. SR 2023-24 Page No 104 I No 12.54 Base Rate 318.00 Add 5% 15.90 =333.90 (Volume-II)								
		14	6.00			84.00			
						84.00	M	333.90	28047.60
9	Providing and fixing angle iron frames for doors, windows and ventilators of mild steel Angle sections of size 35x35x5 mm, joints mitred and welded by angle iron 35x35x5 mm or 35x 5 mm flat pieces to the existing T-iron frame or to the wall with dash fastener, including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer, all complete as per the direction of Engineer-In-charge including cost of materials, labour, usage charges of machinery complete as per specifications. SR 2023-24 Page No 86 I No 11.31 Base Rate 115.00 Add 5% 5.75 =120.75 (Volume-II)								
	Ventilators	14	0.45		0.30	1.89			
		1	0.75		0.45	0.34			
						2.23			
	1.69 Sqm 21 Kgs Per Sqm=35.49					35.49	Kgs	120.75	4285.42
10	Providing and fixing 1st quality ceramic glazed floor tiles conforming to IS : 15622 (thickness to be specified by the manufacturer) of approved make in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge in skirting, risers of steps and dados over 12 mm thick bed of cement Mortar 1:3 (1 cement: 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per m2 including pointing in white cement mixed with pigment of matching shade complete. SR 2023-24 Page No 60 I No 9.10 Base Rate 1106.00 Add 5% 55.30 =1161.30 (Volume-III)								
	Toilet Block	14	1.20	1.20		20.16			
	Passage	1	9.50	2.00		19.00			
		14	4.80		1.50	100.80			
						139.96	Sqm	1161.30	162535.55

11	Providing skirting, dadoing, rises of steps with colour glazed tiles 6mm thick on 10mm thick cement plaster 1:3 and jointed with white cement slurry over existing rough plaster surface using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. SR 2023-24 Page No 65 I No 9.39 Base Rate 1449.00 Add 5% 72.45 =1521.45 (Volume-II)								
	Steps	5	2.30		0.15	1.73			
						1.73	Sqm	1521.45	2624.50
12	Providing, laying & fixing cement base, precast, pre polished cement concrete, designer tiles 25mm thick conforming to IS 1237 heavy duty tiles for flooring, treads of steps and landing, laid on a bed of 12mm thick cement mortar 1:3 mis finished with flush pointing using white cement, including cost of materials, mortar, including cutting, griding the edge to half/full round wherever required, labour, curing complete as per specification. SR 2023-24 Page No 65 I No 9.40 Base Rate 932.00 Add 5% 46.60 =978.60 (Volume-II)								
	Steps	5	2.30		0.30	3.45			
						3.45	Sqm	978.60	3376.17
13	White Vitreous china Orissa pattern W.C. pan of size 580x440 mm with integral type foot rests SR 2023-24 Page No 131 I No 14.1.1 Base Rate 4884.00 Add 5% 244.20=5128.20 (Volume-II)								
		12				12.00			
						12.00	Each.	5128.20	61538.40
14	Providing and fixing white vitreous china pedestal type water closet (European type) with seat and lid, 10 litre low level white vitreous china flushing cistern & C.P. flush bend with fittings & C.I. brackets, 40 mm flush bend, overflow arrangement with specials of standard make and mosquito proof coupling of approved municipal design complete, including painting of fittings and brackets, cutting and making good the walls and floors wherever required W.C. pan with ISI marked white solid plastic seat and lid SR 2023-24 Page No 131 I No 14.3.1 Base Rate 5977.00 Add 5% 298.85=6275.85 (Volume-II)								
		2				2.00			
						2.00	Each.	6275.85	12551.70
15	Providing and fixing C.P. brass bib cock of approved quality conforming to IS:8931 SR 2023-24 Page No 119 I No 13.12 Base Rate 635 Add 5% 31.75=666.75 (Volume-III)								
		15				15.00			
						15.00	Nos	666.75	10001.25
16	Providing and fixing Brass full way valve gate with C.I. wheel of approved quality (screwed end) 25 mm nominal bore SR 2023-24 Page No 117 I No 13.4.1 Base Rate 549 Add 5% 27.45=576.45 (Volume-III)								
		2				2.00			
						2.00	Nos	576.45	1152.90
17	Distempering with oil bound washable distemper of approved brand and manufacture to give an even shade :New work (two coats) over and including water thinnable priming coat with cement primer after thoroughly brooming the surface to remove all dirt, dust, mortar drops and foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour complete as per specifications and as per directions of Engineer-in-charge. SR 2023-24 Page No 45 I No 8.25 Base Rate 137.00 Add 5% 6.85=143.85 (Volume-III)								
	Out Side	2	9.50		3.50	66.50			
	Out Side	2	5.00		3.50	35.00			
	In Side	6	9.50		3.00	171.00			

	In Side	2	5.00		3.00	30.00			
	In Side	20	1.20		3.00	72.00			
	Tank	4	4.50		1.20	21.60			
	Septc Tank Slab	1	7.50		5.00	37.50			
	Slab	1	10.70		6.00	64.20			
						497.80			
	Deduction Door	14	0.75		2.00	21.00			
						476.80	Sqm	143.85	68587.68
18	Extra for depth beyond 45 cm of brick masonry chamber : For 455x610 mm size With common burnt clay (non modular) bricks of class designation 3.5 SR 2023-24 Page No125 I No 13.55.1 Base Rate 6442.00 Add 5% 322.10=6764.10 (Volume-II)								
		2				2.00			
						2.00	1 chamber	6764.10	13528.20
19	Supplying, Fitting and Placing TMT Fe 500 & above Reinforcement in Foundation / Substructure / Superstructure complete as per Drawing and Technical Specifications. It No. 2.11 H P.No. 18 S.R 2023-24 (Volume-I) Basic Rate : 79011.00 Add 5% AW* 3950.55 Total 82961.55								
	Septic Tank Raft	1	9.50	5.00	0.15	7.13			
	Long Wall	2	9.50	0.20	2.00	7.60			
	Short Wall	4	4.90	0.20	2.00	7.84			
	Septic Tank Slab	1	9.50	5.30	0.15	7.55			
	Lintal	4	9.50	0.23	0.15	1.31			
	Lintal	2	5.00	0.23	0.15	0.35			
	Beam	3	9.50	0.23	0.30	1.97			
	Beam	2	4.60	0.23	0.30	0.63			
	Slab	1	10.70	6.20	0.12	7.96			
						42.34			
	42.34 Cum *70 Kg Per Cum					3.00	Tonne	82961.55	248884.65
20	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank. SR 2023-24 Page No123 I No 13.34 Base Rate 9.00 Add 5% 0.45=9.45 (Volume-II)								
		2000				2000.00			
						2000.00	L	9.45	18900.00
21	Providing and fixing G.I. Union in G.I. pipe including cutting and threading the pipe and making long screws etc. complete (New work) : 20mm nominal bore SR 2023-24 Page No.119 I No 13.102 Base Rate 243 Add 5% 12.15=255.15 (Volume-II)								
		1	14.00			14.00			
						14.00	No	255.15	3572.10
22	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall 20 mm nominal dia Pipes SR 2023-24 Page No.122 I No 13.31.2 Base Rate 242 Add 5% 12.10=254.10 (Volume-II)								
		4	35.00			140.00			
						140.00	No	254.10	35574.00

23	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings, including fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and testing of joints complete as per direction of Engineer in Charge. Internal work - Exposed on wall 25 mm nominal dia Pipes SR 2023-24 Page No.122 I No 13.31.3 Base Rate 318 Add 5% 15.90=333.90 (Volume-II)								
		2	35.00			70.00			
						70.00	M	333.90	23373.00
24	Providing and fixing ball valve (brass) of approved quality, High or low pressure, with plastic floats complete 20 mm nominal bore : SR 2023-24 Page No.117 I No 13.5.2 Base Rate 314 Add 5% 15.75=329.75 (Volume-II)								
		4	2.00			8.00			
						8.00	No	329.75	2638.00

Total 15,99,908.96
GST 18% 2,87,983.61
Misc 62,107.42
Gross Total Rs 19,50,000.00

Junior Engineer
TMC, Ramdurg

Chief Officer
TMC Ramdurg

ಸಂಖ್ಯೆ: 146 ದಿನಾಂಕ: 6.4.2026
ರೂ. 1952000 (ರೂಪಾಯಿಗಳು) ಎರಡು ಸಾವಿರ
ಐವತ್ತೈದು ಸಾವಿರ ರೂಪಾಯಿಗಳು
ಮಾತ್ರ) ಮೊತ್ತದ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ಲೆಕ್ಕ
ಹೀರಿಕೆ 2025-26 ನೇ ಸಾಲಿನ ವ್ಯಕ್ತಿಗೂ ಸೇರಿಸಿ ಸಹ (2-ಎ)
ಅಡಿಯಲ್ಲಿ ಕೈಗೊಳ್ಳಲು ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿಯನ್ನು ನೀಡಲಾಗಿದೆ

ಸಹಾಯಕ ಕಾರ್ಯನಿರ್ವಾಹಕ ಅಭಿಯಂತರರು
ಜಿಲ್ಲಾ ಸುಗಮಾಭಿವೃದ್ಧಿ ಕೋಶ
ಜಿಲ್ಲಾಧಿಕಾರಿಗಳ ಕಾರ್ಯಾಲಯ, ಬೆಳಗಾವಿ.

424
16/3/2026



ಕರ್ನಾಟಕ ಸರ್ಕಾರ

ಶ್ರೀಮಾನ್ಮಹಾರಾಷ್ಟ್ರ ಸರ್ಕಾರದ ನಿರ್ದೇಶನ: 2025-26

ಜಿಲ್ಲಾ ಪಂಚಾಯತ್ ರಾಜ್ ಕಾರ್ಯಾಲಯ

ಜಿಲ್ಲಾ ಪಂಚಾಯತ್ ರಾಜ್ ಕೋಶ,

ಬೆಳಗಾವಿ, ದಿನಾಂಕ: 02-02-2026

1710/2026

ವಿಷಯ: ಪುರಸಭೆ ರಾಮದುರ್ಗ ಸರ್ 2025-26ನೇ ಸಾಲಿನ ಸ್ವಚ್ಛ ಭಾರತ ಮಿಷನ್ (ನಗರ) 2.0

ಅಡಿಯಲ್ಲಿ ಸಾರ್ವಜನಿಕ ಶೌಚಾಲಯ ನಿರ್ಮಾಣ ಮಾಡಲು ಕ್ರಿಯಾ ಯೋಜನೆಗೆ ಅನುಮೋದನೆ ನೀಡುವ ಸುರಿತು.

ಓದಿತ್ತು:-1) ಮಾನ್ಯ ನಿರ್ದೇಶಕರು ಪೌರಾಡಳಿತ ನಿರ್ದೇಶನಾಲಯ ಬೆಂಗಳೂರು ರವರ ಸಂಖ್ಯೆ: 1068745/ಡಿಎಂಎ/ಫವನಿ/ಎಸ್‌ಬಿಎಂ/6/2023, ದಿನಾಂಕ: 03.10.2023.

2) ಮಾನ್ಯ ಸರ್ಕಾರದ ಅಧೀನ ಕಾರ್ಯದರ್ಶಿ, ನಗರಾಭಿವೃದ್ಧಿ ಇಲಾಖೆ (ಯೋಜನೆ), ಬೆಂಗಳೂರು

ರವರ ಆದೇಶ ಸಂಖ್ಯೆ: ನಅಇ 229 ಸಿಎಸ್‌ಎಸ್ 2021 (ಭಾ-1)(1) ಬೆಂಗಳೂರು

ದಿನಾಂಕ: 23.01.2026

3) ಮುಖ್ಯಾಧಿಕಾರಿಗಳು ಪುರಸಭೆ ರಾಮದುರ್ಗ ಇವರ ಪತ್ರ ಸಂಖ್ಯೆ: ಮಸರಾ/ಕಾವಿ/ಸಿಆರ್/

ಎಸ್‌ಬಿಎಂ/2025-26 ದಿನಾಂಕ: 31.01.2026

ಪ್ರಸ್ತಾವನೆ:

ಓದಿತ್ತು (1) ರನ್ವಯ ಮಾನ್ಯ ನಿರ್ದೇಶಕರು ಪೌರಾಡಳಿತ ನಿರ್ದೇಶನಾಲಯ ಬೆಂಗಳೂರು ಸ್ವಚ್ಛ ಭಾರತ ಮಿಷನ್‌ನಡಿಯಲ್ಲಿ ವೈಯಕ್ತಿಕ ಶೌಚಾಲಯಗಳನ್ನು ನಿರ್ಮಾಣ ಮಾಡಲಾಗಿದ್ದು ಎಲ್ಲ ನಗರ ಸ್ಥಳೀಯ ಸಂಸ್ಥೆಗಳನ್ನು ಬಯಲು ಶೌಚ ಮುಕ್ತ ಪ್ರದೇಶಗಳನ್ನಾಗಿ ಮಾಡಲಾಗಿರುತ್ತದೆ. ಇತ್ತೀಚೆಗೆ ಅನೇಕ ಗ್ರಾಮ ಪಂಚಾಯತಿಗಳು ನಗರಪ್ರದೇಶಗಳಾಗಿ ಪರಿವರ್ತನೆಯಾಗುತ್ತಿದ್ದು, ದಿನೇ ದಿನೇ ನಗರ ವ್ಯಾಪ್ತಿಯಲ್ಲಿ ಹೆಚ್ಚಾಗುತ್ತಿರುವುದರಿಂದ ಕೇಂದ್ರ ಸರ್ಕಾರವು ನಗರ ಪ್ರದೇಶಗಳಲ್ಲಿ ನೈರ್ಮಲ್ಯೀಕರಣ, ಸ್ವಚ್ಛತೆ ಮತ್ತು ಶುಚಿತ್ವದ ಮೇಲೆ ಹೆಚ್ಚು ಗಮನಹರಿಸಿ, ಸ್ವಚ್ಛ ಭಾರತ ಮಿಷನ್ (ನ) 2.0 ಯೋಜನೆಯಡಿ ವೈಯಕ್ತಿಕ ಶೌಚಾಲಯ ನಿರ್ಮಾಣ, ಸಮುದಾಯ ಹಾಗೂ ಸಾರ್ವಜನಿಕ ಶೌಚಾಲಯಗಳನ್ನು ನಿರ್ಮಾಣ ಮಾಡಲು ಅವಕಾಶ ಕಲ್ಪಿಸಿದ್ದು, ನಗರ ಸ್ಥಳೀಯ ಸಂಸ್ಥೆಗಳಿಗೆ ಅಗತ್ಯವಿರುವ ನೈರ್ಮಲ್ಯ ವ್ಯವಸ್ಥೆಯನ್ನು ರಾಜ್ಯಮಟ್ಟದಲ್ಲಿ ವಿಶ್ಲೇಷಿಸಿ, ಕ್ರಿಯಾ ಯೋಜನೆಯನ್ನು ರೂಪಿಸಿ, ರಾಜ್ಯ ಹಾಗೂ ಕೇಂದ್ರ ಸರ್ಕಾರದ ಅನುಮೋದನೆಯನ್ನು ಪಡೆಯಲಾಗಿರುತ್ತದೆ.

ಕೇಂದ್ರ ಸರ್ಕಾರ ಹಾಗೂ ರಾಜ್ಯ ಸರ್ಕಾರ ಬಿಡುಗಡೆ ಮಾಡುವ ಅನುದಾನದ ಜೊತೆಗೆ ನಗರ ಸ್ಥಳೀಯ ಸಂಸ್ಥೆಗಳ ಪಾಲಿನ ಅನುದಾನವನ್ನು ಭರಿಸಬೇಕಿದ್ದು, ರಾಜ್ಯ ಹಣಕಾಸು ಅಯೋಗದ ಎಸ್.ಎಫ್.ಸಿ. ಮುಕ್ತ ನಿಧಿ ಯೋಜನೆಯ ಶೇ. 24.10 (ಪರಿಶಿಷ್ಟ ಜಾತಿ/ಪರಿಶಿಷ್ಟ ಪಂಗಡ ವರ್ಗಗಳಿಗೆ) ಶೇ.7.25 (ಇತರೆ ನಗರ ಬಡಜನರಿಗೆ) ಹಾಗೂ ಶೇ.5 (ವಿಕಲಚೇತನರಿಗೆ) ರಂತೆ ಹಾಗೂ ಸ್ಥಳೀಯ ಸಂಸ್ಥೆಗಳ ಸ್ವಂತ ನಿಧಿಯಿಂದ ನಿಯಮಾನುಸಾರ ಭರಿಸಲು ಕ್ರಮ ಕೈಗೊಳ್ಳುವಂತೆ ಸೂಚಿಸಿರುತ್ತಾರೆ.

ಅದರಂತೆ ಓದಿತ್ತು (2) ರಲ್ಲಿ ಸ್ವಚ್ಛ ಭಾರತ ಮಿಷನ್ (ನ)-2.0ರ ನಗರ ನೈರ್ಮಲ್ಯ ಘಟಕದಡಿಯಲ್ಲಿ ರಾಜ್ಯಕ್ಕೆ ಹಂಚಿಕೆಯಾಗಿರುವ ಕೇಂದ್ರದ ಹಂಚಿಕೆಯಾಗಿರುವ ಕೇಂದ್ರದ ಪಾಲಿನ ಅನುದಾನ ರೂ.76.10 ಕೋಟಿಗಳ ಅನುದಾನದ ವೈಕಿ, ಬಾಕಿ ಉಳಿದ ಕೇಂದ್ರದ ಪಾಲಿನ ಅನುದಾನದಲ್ಲಿ ರೂ.11.66 ಕೋಟಿಗಳ ಮೊತ್ತಕ್ಕೆ (ಒಟ್ಟು ಅಂದಾಜುಮೊತ್ತ ರೂ.31.19 ಕೋಟಿಗಳು) ರಾಜ್ಯದ ನಗರ ಸ್ಥಳೀಯ ಸಂಸ್ಥೆಗಳ ವ್ಯಾಪ್ತಿಯಲ್ಲಿ ಕ್ರಮವಾಗಿ ಸಾರ್ವಜನಿಕ ಶೌಚಾಲಯಗಳು, ಸಮುದಾಯ ಶೌಚಾಲಯಗಳು ಹಾಗೂ ಮಹತ್ವಾಕಾಂಕ್ಷಿ ಸಾರ್ವಜನಿಕ ಶೌಚಾಲಯಗಳ ನಿರ್ಮಾಣಕ್ಕಾಗಿ ಸರ್ಕಾರವು ಆಡಳಿತಾತ್ಮಕ ಅನುಮೋದನೆ ನೀಡಿ ಆದೇಶಿಸಿದ್ದು ಇರುತ್ತದೆ.

ಓದಿತ್ತು (3) ರಲ್ಲಿ ಮುಖ್ಯಾಧಿಕಾರಿಗಳು ಪುರಸಭೆ ರಾಮದುರ್ಗ ರವರು ಸ್ವಚ್ಛ ಭಾರತ ಮಿಷನ್ (ನಗರ) 2.0 ಲ್ಲಿ ಸಾರ್ವಜನಿಕ ಶೌಚಾಲಯ ನಿರ್ಮಾಣ ಮಾಡಲು ಕ್ರಿಯಾ ಯೋಜನೆಗೆ ಆಡಳಿತಾಧಿಕಾರಿ ರವರ ಸಂಖ್ಯೆ: 377 ದಿನಾಂಕ: 29.01.2026 ರ ವೃತ್ತಾಂತ ಅನುಮೋದನೆ ನೀಡಲು ಕ್ರಿಯಾ ಯೋಜನೆ ಸಲ್ಲಿಸಿರುತ್ತಾರೆ. ಸದರಿ ಕ್ರಿಯಾ ಯೋಜನೆಯನ್ನು ಪರಿಶೀಲಿಸಿ ಈ ಕೆಳಗಿನಂತೆ ಆದೇಶಿಸಿದೆ.

ಆದೇಶ

ಮೇಲಿನ ಪ್ರಸ್ತಾವನೆಯಂತೆ, ರಾಮದುರ್ಗ ಪುರಸಭೆಗೆ ₹ 39.00 ಲಕ್ಷ ಅನುದಾನ ಹಂಚಿಕೆಯಾಗಿರುತ್ತದೆ. ಅದರಲ್ಲಿ ಕೇಂದ್ರ ಸರ್ಕಾರ ಹಾಗೂ ರಾಜ್ಯ ಸರ್ಕಾರ ಬಿಡುಗಡೆ ಮಾಡುವ ಅನುದಾನದ ಜೊತೆಗೆ ರಾಮದುರ್ಗ ಪುರಸಭೆಯ ಸ್ಥಳೀಯ ಮಂತ್ರಿ ಬಾಕಿ ₹ 6.63 (ಶೇ. 17) ಲಕ್ಷ ಮೊತ್ತವನ್ನು ಭರಿಸುವ ಅಂದಾಜು ಮೊತ್ತಕ್ಕೆ ಕ್ರಿಯಾ ಯೋಜನೆಗೆ ಅನುಮೋದನೆ ನೀಡಿ ಅಲ್ಪಾವಧಿ ಟೆಂಡರ್ ಕರೆಯಲು ಆದೇಶಿಸಿದೆ.

ಮರಸಭೆ ರಾಮದುರ್ಗ ಭವನದ ಮೊತ್ತ : ₹ 6.63 ಲಕ್ಷಗಳು
 ಕೇಂದ್ರ ಸರ್ಕಾರದ ಅನುದಾನ : ₹ 19.50 ಲಕ್ಷಗಳು
 ರಾಜ್ಯ ಸರ್ಕಾರದ ಅನುದಾನ : ₹ 12.87 ಲಕ್ಷಗಳು
 ಸಲ್ಲಿಸಿರುವ ಕ್ರಿಯಾ ಯೋಜನೆಯ ಮೊತ್ತ : ₹ 39.00 ಲಕ್ಷಗಳು

ಅ.ನಂ	ಕಾಮಗಾರಿ ವಿವರ	ಅಂದಾಜು ಮೊತ್ತ (ಲಕ್ಷಗಳಲ್ಲಿ)	ಕೇಂದ್ರ ಸರ್ಕಾರದ ಪಂಚಿಕೆ (ಶೇ. 50)	ರಾಜ್ಯ ಸರ್ಕಾರದ ಪಂಚಿಕೆ (ಶೇ. 33)	ಸ್ಥಳೀಯ ಸಂಸ್ಥೆ ಪಂಚಿಕೆ (ಶೇ. 17)
1	ಮರಸಭೆ ವ್ಯಾಪ್ತಿಯ ಮಿನಿ ವಿಧಾನಸೌಧದ ಹತ್ತಿರ ಸಾರ್ವಜನಿಕ ಬೆಂಚುಗಳು ನಿರ್ಮಾಣ ಮಾಡುವುದು. (13 SEAT)	19.50	9.75	6.435	3.315
2	ಮರಸಭೆ ಕಾರ್ಯಾಲಯದ ಹತ್ತಿರ ಸಾರ್ವಜನಿಕ ಬೆಂಚುಗಳು ನಿರ್ಮಾಣ ಮಾಡುವುದು (13 SEAT)	19.50	9.75	6.435	3.315
	ಒಟ್ಟು	39.00	19.50	12.87	6.63

ಈ ಮೇಲಿನ ಕೊಷ್ಟದಲ್ಲಿ ತಿಳಿಸಿದಂತೆ ಕೇಂದ್ರ ಸರ್ಕಾರ ಹಾಗೂ ರಾಜ್ಯ ಸರ್ಕಾರ ಬಿಡುಗಡೆ ಮಾಡುವ ಅನುದಾನದ ಜೊತೆಗೆ ರಾಮದುರ್ಗ ಮರಸಭೆಯ ₹ 6.63 (ಶೇ.17) ಲಕ್ಷ ಮೊತ್ತ ಒಟ್ಟು ₹ 39.00 ಲಕ್ಷಗಳ ಕ್ರಿಯಾ ಯೋಜನೆಗೆ ಅನುಮೋದನೆ ನೀಡಲಾಗಿದೆ. ಷರತ್ತುಗಳು:

- 1) ಸ್ವಚ್ಛ ಭಾರತ ಅಭಿಯಾನ ಯೋಜನೆಯ ಮಾರ್ಗಸೂಚಿಗಳನ್ನು ಮತ್ತು ಸುತ್ತೋಲೆಗಳನ್ನು ಕಟ್ಟುನಿಟ್ಟಾಗಿ ಪಾಲಿಸತಕ್ಕದ್ದು. ಎಲ್ಲಾ ಪಾವತಿಗಳನ್ನು PFMS ನಡಿ ಪಾವತಿಸುವುದು.
- 2) ಈ ಯೋಜನೆಯ ಅನುಷ್ಠಾನಕ್ಕೆ ಸಂಬಂಧಿಸಿದಂತೆ, ಕಾಲ ಕಾಲಕ್ಕೆ ಸರ್ಕಾರದಿಂದ ಹೊರಡಿಸಲಾದ ಆದೇಶಗಳನ್ನು, ನಿರ್ದೇಶನಾಲಯದಿಂದ ನೀಡಲಾದ ಸುತ್ತೋಲೆಗಳನ್ನು ಎಸ್.ಬಿ.ಎಮ್ ಮಾರ್ಗಸೂಚಿಗಳನ್ನು ಪಾಲಿಸುವುದು.
- 3) ಕೇಂದ್ರ ಸರ್ಕಾರ ಹಾಗೂ ರಾಜ್ಯ ಸರ್ಕಾರ ಬಿಡುಗಡೆ ಮಾಡುವ ಅನುದಾನದ ಜೊತೆಗೆ ನಗರ ಸ್ಥಳೀಯ ಸಂಸ್ಥೆಗಳ ಪಾಲಿಸ ಅನುದಾನವನ್ನು ರಾಜ್ಯ ಹಣಕಾಸು ಅಯೋಗದ SFC ಮುಕ್ತ ನೀಡಿ ಯೋಜನೆಯ ಶೇ.24.10, ಶೇ.7.25 ಹಾಗೂ ಶೇ.5.00 ಹಾಗೂ ಸ್ಥಳೀಯ ಸಂಸ್ಥೆಗಳ ಸ್ವಂತ ನಿಧಿಯಿಂದ ನಿಯಮಾನುಸಾರ ಭರಿಸಲು ಕ್ರಮ ಕೈಗೊಳ್ಳತಕ್ಕದ್ದು.
- 4) ಹೊಸ ಬಡಾವಣೆ/ ಅನಧಿಕೃತ/ ಖಾಸಗಿ ಸ್ಥಳಗಳಲ್ಲಿ ಯಾವುದೇ ಕಾಮಗಾರಿಗಳನ್ನು ಅನುಷ್ಠಾನ ಗೊಳಿಸತಕ್ಕದ್ದಲ್ಲ. ಅಂತಹ ಪ್ರಕರಣಗಳು ಕಂಡುಬಂದಲ್ಲಿ ಕೂಡಲೇ ಬದಲಿ ಕಾಮಗಾರಿಗೆ ಪ್ರಸ್ತಾವನೆ ಸಲ್ಲಿಸಿ, ಅನುಮೋದನೆ ಪಡೆದುಕೊಳ್ಳತಕ್ಕದ್ದು. ತಪ್ಪಿದ್ದಲ್ಲಿ ಮುಖ್ಯಾಧಿಕಾರಿಯೇ ಸೇರ ಹೊಣೆಗಾರರಾಗುತ್ತಾರೆ.
- 5) ಕಾಮಗಾರಿಗಳ ಅಂದಾಜುಗಳಿಗೆ ಸಕ್ಷಮ ಪ್ರಾಧಿಕಾರದಿಂದ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿಯನ್ನು ಪಡೆಯತಕ್ಕದ್ದು.
- 6) ಈ ಕಾಮಗಾರಿಗಳನ್ನು ಬೇರೆ ಯಾವುದೇ ಯೋಜನೆ / ಅನುದಾನದಡಿ ತೆಗೆದುಕೊಂಡಿರಬಾರದು.
- 7) ಕಾಮಗಾರಿಗಳನ್ನು ಅನುಷ್ಠಾನಗೊಳಿಸುವಲ್ಲಿ ಕೆಟಿಪಿಪಿ ಅಧಿನಿಯಮ 1999 ಮತ್ತು ನಿಯಮಗಳು 2000ನ್ನು ಕಟ್ಟು ನಿಟ್ಟಾಗಿ ಪಾಲಿಸತಕ್ಕದ್ದು.
- 8) ಕಾಮಗಾರಿಗಳ ಗುಣಮಟ್ಟದ ಬಗ್ಗೆ 3ನೇ ವ್ಯಕ್ತಿ ತಪಾಸಣಾ ಏಜೆನ್ಸಿಯಿಂದ ಪರಿಶೀಲನೆ ಮಾಡಿಸಿ ಉತ್ತಮ ಕಾರ್ಯನಿರ್ವಹಣೆಯ ಬಗ್ಗೆ ಪ್ರಮಾಣ ಪತ್ರ ಪಡೆದ ನಂತರ ಮಾತ್ರ ಬಿಲ್ಲುಗಳ ಪಾವತಿಗೆ ಕ್ರಮ ಕೈಗೊಳ್ಳತಕ್ಕದ್ದು.
- 9) ಹಂಚಿಕೆಯಾದ ಅನುದಾನವನ್ನು ಆಯಾ ಉದ್ದೇಶಗಳಿಗೆ ನಿಯಮಾನುಸಾರ ಬಳಕೆ ಮಾಡಲು ಕ್ರಮ ಕೈಗೊಂಡು ನಿಗದಿತ ನಮೂನೆಯಲ್ಲಿ (ಕೆಎಫ್‌ಸಿ-187) ಬಳಕೆ ಪ್ರಮಾಣಪತ್ರವನ್ನು ಪೌರಾಡಳಿತ ನಿರ್ದೇಶನಾಲಯಕ್ಕೆ ಸಲ್ಲಿಸುವುದು.

(ಮೊಹಮ್ಮದ್ ರೋಷನ್)
 ಜಿಲ್ಲಾಧಿಕಾರಿಗಳು, ಬೆಳಗಾವಿ

ಪ್ರತಿಯನ್ನು:

- 1) ಗೌರವಗಳೊಂದಿಗೆ, ಮಾನ್ಯ ನಿರ್ದೇಶಕರು, ಪೌರಾಡಳಿತ ನಿರ್ದೇಶನಾಲಯ, ಬೆಂಗಳೂರು ಇವರಿಗೆ ಮಾಹಿತಿಗಾಗಿ ಸಲ್ಲಿಸಿದೆ.
- 2) ಮುಖ್ಯಾಧಿಕಾರಿಗಳು ಮರಸಭೆ ರಾಮದುರ್ಗ ಇವರಿಗೆ ಸೂಕ್ತ ಕ್ರಮಕ್ಕಾಗಿ.

ಯೋಜನಾ ನಿರ್ದೇಶಕರು,
 ಜಿಲ್ಲಾ ನಗರಾಭಿವೃದ್ಧಿ ಕೋಶ, ಬೆಳಗಾವಿ