

**Bill of Quantity For Construction of (A)RCC Drain Cover From Pappu Mukhiya House to Guddan House (B) PCC Road From Md. Tahid House to Md. Rahim House in ward No.- 04 in Nagar Panchayat Tarapur ,Munger**

Sr. No.	SOR	Description	Unit	Quantity	Rate Rs	Amount
1	BCD/5.1.2	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement-All work upto plinth level 1:1.5:3(1 cement: 1.5 coarse sand:3 graded stone	M3	112.50	4688.30	527434.00
2	BCD/5.22.7(A)	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. Thermo-Mechanically Treated bars TMTC-500-8mm dia.	kg	2962.50	94.50	279956.00
3	BCD/5.22.7(B)	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. Thermo-Mechanically Treated bars TMTC-500-10mm dia.	kg	8546.85	90.80	776054.00
4	BCD/5.9.1	Centring and shuttering including strutting, propping etc. and removal of form for. Foundations, footings, bases of columns etc. for mass concrete	M2	697.10	211.60	147506.00
5	BCD/4.1.2	Providing and laying in position cement concrete of specified grade excluding the cost of centring and shuttering-all work upto plinth level. 1:1½ :3(1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size).	M3	41.58	4420.80	183795.00
<b>Carrage of Material</b>						
6	(i)	Coarse sand	M3	65.48	1207.93	79098.00
	(ii)	Stone Chips	M3	130.96	2345.91	307229.00
<b>Total</b>						2301072.00
7		Cost of Signboard & Photography	Nos	1.00	3500	3500.00
<b>Total</b>						2304572.00
8		Add Additional GST @ 5.36 %				123525.00
<b>Seigniorage Fee</b>						
9	(i)	Coarse sand	M3	65.48	17.58	1151.00
	(ii)	Stone Chips	M3	130.96	59.54	7798.00
<b>Total Rs.</b>						2437045.00

12/01/26

Gaurav Kumar

B & B Approval for Sl No- (1) to (09) for Rs. 2437045.00

(Rupees Twenty four lakh thirty seven thousand forty five and 00/100)

14/01/26  
E.E.

कार्यपालक अभियंता  
नगर विकास प्रमंडल  
मुंगेर-जमुई, जमुई