

BILL OF QUANTITY

स्टेट बैंक के उत्तर तरफ से पटेल कंप्यूटर से पीरो गाँव शिव मंदिर के सामने तक एवं मिशन स्कूल के पीछे से होते हुए राजबाहा तक नाला सफाई का कार्य।

Sr.	S.O.R	Item of Work	Unit	Qty	Rate	Amount
1	5.1.16 W.R.D	Earth work excavation of water courses in ordinary soil with all lead and lift including clod breaking rough dressing all complete and as per specification and direction of E/I				
				382.80		
				1708.80		
				1576.80		
				4410.00		
			cum	8078.40	151.34	1222585
2	5.1.11 W.R.D	Extra for earth work in marshy,slushy and daldal soil (vide classification of soil item F) all complete as per specification and direction of E/I.				
				382.80		
				1708.80		
				1576.80		
				4410.00		
			cum	8078.40	49.95	403516
3		Carriage for disposal of Mud/Slush from work site				
			cum	1615.68	274.46	443440
TOTAL=						2069541
4		Add 1% Lwc				20695
5		Add 18% GST				372517
						2462753

[Signature]
02.05.2026
J.E. *[Signature]*

BOQ is approved from file no. 01 to 05 for Rs 24,62,753/- (Twenty four lakh sixty two thousand seven hundred and fifty three) only.

[Signature]
02/05/26
A.E.

[Signature]
27/05/26
E.E.