

BILL OF QUANTITY

मुसहर टोली से राजा बाबु के घर होते हुए हीरो एजेंसी के पीछे तक नाला सफाई का कार्य ।

Sr.	S.O.R	Item of Work	Unit	Qty	Rate	Amount
1	5.1.16 W.R.D	Earth work excavation of water courses in ordinary soil with all lead and lift including clod breaking rough dressing all complete and as per specification and direction of E/I				
			cum	170.10	151.34	25743
2	5.1.11 W.R.D	Extra for earth work in marshy,slushy and daldal soil (vide classification of soil item F) all complete as per specification and direction of E/I.				
			cum	170.10	49.95	8496
3	Carriage for disposal of Mud/Slush from work site					
			cum	119.07	274.46	27235
TOTAL=						61474
4	Add 1% Lwc					615
5	Add 18% GST					11065
	(A)					73154
Sr.	S.O.R	Item of Work	Unit	Qty	Rate	Amount
6	15.3 B.C.D	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material withing 50 metres lead:				
			cum	5.57	1411.2	7859
7	5.1.2 B.C.D	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering,finishing and reinforcement-All work upto plinth level 1:1:5:3(1 cement: 1.5 coarse sand:3 graded stone aggregate 20 mm nominal size)				
			cum	5.57	4688.3	26108
8	5.22.7B	Reinforcement for R.C.C. work including straightening,cutting,bending, placing in position and binding all complete.Thermo-Mechanically Treated bars TMTC-500-10mm dia.5.57cum @80kg/m3 (as per design)	kg	445.50	92.60	41253

9	5.9.1 B.C.D	Centring and shuttering including				
			sqm	24.75	211.6	5237
10	Carriage of Material					
a	Coarse Sand		cum		1364.56	3220
b.	Stone chips		cum		3198.00	15127
					Total=	98804
						5296
11	Add @ 5.36% GST					
12	Signiorage Fee					
a	Coarse Sand		cum		17.58	41
b.	Stone chips		cum		59.54	282
					(B)	104423
	Add Total Amount (A+B)= (73154.00+104423.00)					177577

Arx
04/05/26
J.E

Chandan
A.E 04/05/26

E.E

B.O.R is approved from Sr. No- 01 to 12 for Rs 1,77,577/-
(Rupees One Lacs Seventy seven thousand five hundred
and seventy seven) only.

P/W
27/05/26
B.G