



BILL OF QUANTITY

बिहिया लाईन नहर से मिल्की पकड़ी पेड़ होते हुए भागलपुर मदरसा से वार्ड नं0-23/16 वार्ड का वार्डर क्रॉस होते हुए नगर परिषद् के पीछे तक एवं पुरानी पानी टंकी से पड़ाव मैदान के चारदिवारी के सटे सासाराम मेन रोड विशाल मेगा मार्ट तक नाला सफाई का कार्य।

Sr.	S.O.R	Item of Work	Unit	Qty	Rate	Amount
1	5.1.16 W.R.D	Earth work excavation of water courses in ordinary soil with all lead and lift including clod breaking rough dressing all complete and as per specification and direction of E/I				
			cum	1199.40	151.34	181517
2	5.1.11 W.R.D	Extra for earth work in marshy,slushy and daldal soil (vide classification of soil item F) all complete as per specification and direction of E/I.				
			cum	1199.40	49.95	59910
3		Carriage for disposal of Mud/Slush from work site				
			cum	599.70	274.46	164594
		TOTAL=				406021
4		Add 1% Lwc				4060
5		Add 18% GST				73084
					(A)	483165
Sr.	S.O.R	Item of Work	Unit	Qty	Rate	Amount
6	15.3 B.C.D	Demolishing R.C.C. work including stacking of steel bars and disposal of unserviceable material withing 50 metres lead:				
			cum	23.37	1411.2	32982


7	5.1.2 B.C.D	Providing and laying in position specified grade of reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement- All work upto plinth level 1:1:5:3 (1 cement: 1.5 coarse sand: 3 graded stone aggregate 20 mm nominal size)				
			cum	23.37	4688.30	109574
8	5.22.7B	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. Thermo-Mechanically Treated bars TMTC-500-10mm dia. 23.37cum @ 80kg/m3 (as per design)	kg	1869.75	92.60	173139
9	5.9.1 B.C.D	Centring and shuttering including strutting, propping etc. and removal of form for Foundations, footings, bases of columns etc. for mass concrete.				
			sqm	113.81	211.60	24083
10	Carriage of Material					
a	Coarse Sand			cum	1364.56	13554
b.	Stone chips			cum	3198.00	63532
	Total=					416864
11	Add @ 5.36% GST					22344
12	Signiorage Fee					
a	Coarse Sand			cum	17.58	175
b.	Stone chips			cum	59.54	1183
	(B)					440566
	Add Total Amount (A+B)= (483165.00+440566.00)					923731


 02.05.26
 J.E.
 27/05/26


 A.E. 02/05/2026

E.E

BOQ is approved from item no. 01 to 12 for B 9,23,731/-
 (Rupees Nine Lacs twenty three thousand seven hundred and
 thirty one) only.


 27/05/26