


**Bill of Quantity For Construction of (A)RCC Drain & PCC Road From Raji Akthar House to Naushad House (B) RCC Drain Masdak House to Moln Dilar House
©PCC Road From Md. KallimodIn House to Challi House in ward No.- 16 in
Nagar Panchayat Tarapur ,Munger**

Sr. No.	SOR	Description	Unit	Quantity	Rate Rs	Amount
1	1 BCD/15.2.1	Demoishing cement concrete including disposal of material within 50 metre lead: Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	M3	16.65	970.90	16165.00
2	2 BCD/2.8.1	Earth work in excavation in foundation trenches or drains (not exceeding 1.5 m in width or 10 sqm on plan) including dressing of sides and ramming of bottoms, lift upto 1.5 m. Including getting out the excavated soil and disposal of surplus excavated soil as directed, within a lead of 50 m. All kinds of soil	M3	204.30	360.70	73691.00
3	3 BCD/2.25(A)	Excavating, supplying and filling of local earth (including royalty but excluding carriage cost) by mechanical transport upto a lead of 3km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete. If local earth is available at more than 3 km lead the actual lead must be approved by competent authority. Carriage of material will be paid separately and calculated after deducting initial lead..	M3	52.50	411.70	21614.00
4	4 RCD/3.11	Removal of unserviceable soil including excavation, loading and disposal upto 1000 metres lead but excluding replacement by suitable soil which shall be paid separately as per clause 305.	M3	220.95	125.55	27740.00
5	5 BCD/2.28	Supplying and Filling in plinth with local sand and under floors including, watering, ramming consolidating and dressing complete	M3	24.60	287.30	7068.00
6	6 BCD/11.72	Providing designation 100 A one brick flat soling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specification and direction of E/I,	M2	328.00	283.30	92922.00
7	7 BCD/5.1.2	Providing and laying in position specified grade or reinforced cement concrete excluding the cost of centring, shuttering, finishing and reinforcement-All work upto plinth level 1:1.5:3 (1 cement: 1.5 coarse sand: 3 graded stone aggregate 20 mm nominal size)	M3	84.15	4688.30	394520.00
8	8 BCD/5.22.7(A)	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. Thermo-Mechanically Treated bars TMTC-500-8mm dia.	kg	1712.33	94.50	161815.00
9	9 BCD/5.22.7(B)	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. Thermo-Mechanically Treated bars TMTC-500-10mm dia.	kg	2959.35	92.60	274036.00
10	10 BCD/5.9.1	Centring and shuttering including strutting, propping etc. and removal of form for. Foundations, footings, bases of columns etc. for mass concrete.	M2	892.50	211.60	188853.00
11	11 BCD/4.1.2	Providing and laying in position cement concrete of specified grade exluding the cost of centring and shuttering-all work upto plinth level. 1:1½ :3 (1 cement : 1½ coarse sand : 3 graded stone aggregate 20 mm nominal size).	M3	124.55	4420.80	550611.00
Carrage of Material						
10	(i)	Coarse sand(60 km p + 01 km k)	M3	88.70	1207.93	107140.00
	(ii)	Stone Chips(184 km p + 01 km k)	M3	177.40	2345.91	416153.00
	(iii)	Bricks (07 km + 01 km k)	Nos	10582	867.15	9176.00
	(iv)	Local Sand (02 km + 01 km k)	M3	29.55	268.35	7929.00
Total						2349433.00
11		Cost of Signboard & Photography	Nos	1.00	3500	3500.00
Total						2352933.00
12		Add Additional GST @ 5.36 %				126117.00
Seigniorage Fee						
	(i)	Coarse sand	M3	88.70	17.58	1559.00

13	(ii)	Stone Chips	M3	177.40	59.54	10562.00
	(iii)	Bricks (07 km + 01 km k)	Nos	10582	512.8	5427.00
	(iv)	Local Sand (02 km + 01 km k)	M3	29.55	14.19	419.00
				Total Rs.		2497017.00

18/1/24

Gaurav Kumar

BoB Approval for sl no (7) to (13) for Rs. 2497017.00

(Rupees Twenty four lakh ninety seven thousand seven hundred and seventeen only)

18/01/24

कार्यपालक अभियंता
नगर विकास प्रमंडल
मुंगेर-जमुई, जमुई