



G 204 P-05

योजना का नाम :- नगर परिषद सुलतानगंज के जर्मन हैंगर के पास ईट सोलिंग का पहुँच पथ का निर्माण।


- (i) Estimated Cost Rs:- 283349.00
(ii) Cost of B.O.Q Rs:- 500
(iii) Earnest Mony Rs: 5700.00
(iv) Last date of Sale of B.O.Q :-
(v) Time of Completion :-
(vi) Date and Time of receiving Tender :-
(vii) Date and time of Opening the Tender :-
(viii) Place of sale of B.O.Q & Reciving of Tender :- Nagar Parisad Sultanganj
(ix) Issue to Name of Agency) :-
(x) Mode of payment :- D D / Case M R NO Date

S.N.	Item of Work	Qty	Unit	Rate	Amount
1	Supplying and Filling in plinth with local sand and under floors including, watering, ramming consolidating and dressing complete.(BCD SOR ITEM NO 2.28)	93.31	M ³	287.30	26808.00
2	Providing designation 100 A one brick flat soling joints filled with local sand including cost of watering, taxes, royalty all complete as per building specification and direction of E/I(BCD SOR ITEM NO 11.72)	612.45	M ²	283.30	173507.00
3	Carriage of material				
i	Bricks (7P + 1 k.) =8 km.	19752	Nos	940.97	18586.00
ii	Local Sand (2 S. + 1 k.) =3 km.	102.50	M ³	310.42	31817.00
4	Difference Cost of Materials				
i	Bricks	19752	Nos	365.61	7222.00
					257940.00
5	Add GST 5.36 % (Difference GST Rate)				13826.00
					271766.00
6	Seigniorage Fee				11583.00
					Rs 283349.00


12/06/26


12/06/26

BOB, approved for ₹ 2,83,349/- (Rupees two lakh eighty three thousand three hundred forty - nine rupees) only.


12.6.26