

Name of Wotk :- Construction of Anganvadi - Nandghar (Frame structure) at Various Village of
Ranpur Taluka Dist. Botad (Package BTB/Anganvadi/Pac-19) (Jalila-4, Chandarva-3)

Quantity sheet

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
1	Excavation for foundation upto 1.50 M.depth including sorting out & stacking of useful materials i.e. disposing the excavated stuff up to all lead (a) Dense or Hard soil.	SE-1/1	40.60	157.160	6380.69	SE-2/1	9.00	157.160	1414.44	SE-1/1	40.60	157.160	6380.69
2	Excavation for foundation upto 1.5 m depth including sorting out and stacking of useful materials and disposing off the excavated stuff upto all lead.(C) Hard Murrum.	SE-1/2	24.40	268.92	6561.64	SE-2/2	2.90	268.92	779.86	SE-1/2	24.40	268.920	6561.64
3	Providing and laying cement concrete 1:4:8 (1 cement, 4sand, 8 Crushed stone aggregates 40 mm.Nominal size) and curing complete, excluding cost of formwork in(a) Foundation and Plinth.	SE-1/3	14.40	2927.46	42155.42	SE-2/3	2.00	2927.46	5854.92	SE-1/3	14.40	2927.460	42155.42
4	Brickwork using common burnt clay building brick shaving crushing strength not less than 35 Kg/Sqcm. in foundation and plinth in cement mortar 1:6(1 Cement ; 6 Fine sand) Conventional bricks.	SE-1/6	29.50	4214.33	124322.73	SE-2/7	3.00	4214.33	12642.99	SE-1/6	29.50	4214.330	124322.73

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
1	Excavation for foundation upto 1.50 M.depth including sorting out & stacking of useful materials i.e. disposing the excavated stuff up to all lead (a)Dense or Hard soil.	SE-2/1	9.00	157.160	1414.44	99.20	157.16	One Cubic metre	15590.26
2	Excavation for foundation upto 1.5 m depth including sorting out and stacking of useful materials and disposing off the excavated stuff upto all lead.(C) Hard Murrum.	SE-2/2	2.90	268.920	779.86	54.60	268.92	One Cubic metre	14683.00
3	Providing and laying cement concrete 1:4:8 (1 cement, 4sand,8 Crushed stone aggregates 40 mm.Nominal size)and curing complete, excluding cost of formwork in(a) Foundation and Plinth.	SE-2/3	2.00	2927.460	5854.92	32.80	2927.46	One Cubic metre	96020.68
4	Brickwork using common burnt clay building brick shaving crushing strength not less than 35 Kg/Sqcm. in foundation and plinth in cement mortar 1:6(1 Cement ; 6 Fine sand) Conventional bricks.	SE-2/7	3.00	4214.330	12642.99	65.00	4214.33	One Cubic metre	273931.44

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
5	Providing and laying ordinary cement concrete 1:1:2 (1 cement, 1 sand, 2 graded stone aggregates 20 mm. Nominal size) and finishing smooth with curing etc. complete excluding cost of form work and reinforcement for reinforced cement concrete work in in A) Foundations, footings, base of columns and mass concrete	SE-1/4	6.70	6789.22	45487.77	SE-2/4	1.20	6789.22	8147.06	SE-1/4	6.70	6789.22	45487.77
6	Filling in foundation and plinth with murrum or selected soil in layers of 20cm. thickness including watering, ramming and consolidating etc. complete.	SE-1/7	58.20	301.78	17563.59		0.00	301.78	0.00	SE-1/7	58.20	301.78	17563.59
7	Filling in plinth with sand under floors including watering ramming, consolidating and dressing complete.	SE-1/8	7.40	481.80	3565.32		0.00	481.80	0.00	SE-1/8	7.40	481.80	3565.32
8	Brickwork using common burnt clay building brick shaving crushing strength not less than 35 Kg/Sqcm. in super structure for all floors. in cement mortar 1:6 (1 Cement ; 6 Fine sand)	SE-1/9	9.90	4496.05	44510.89	SE-2/9	7.40	4496.05	33270.77	SE-1/9	9.90	4496.05	44510.89

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
5	Providing and laying ordinary cement concrete 1:1:2 (1 cement, 1 sand, 2 graded stone aggregates 20 mm. Nominal size) and finishing smooth with curing etc. complete excluding cost of form work and reinforcement for reinforced cement concrete work in in A) Foundations, footings, base of columns and mass concrete	SE-2/4	1.20	6789.220	8147.06	15.80	6789.22	One Cubic metre	107269.66
6	Filling in foundation and plinth with murrum or selected soil in layers of 20cm. thickness including watering, ramming and consolidating etc. complete.		0.00	301.780	0.00	116.40	301.78	One Cubic metre	35127.18
7	Filling in plinth with sand under floors including watering ramming, consolidating and dressing complete.		0.00	481.800	0.00	14.80	481.80	One Cubic metre	7130.64
8	Brickwork using common burnt clay building brick shaving crushing strength not less than 35 Kg/Sqcm. in super structure for all floors. in cement mortar 1:6 (1 Cement ; 6 Fine sand)	SE-2/9	7.40	4496.050	33270.77	34.60	4496.05	One Cubic metre	155563.32

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
9	Half brick masonry in comon burnt clay building bricks having crushing strength not less than 35Kg./Sq.Cm. in cement mortar 1:3 (1 Cement : 3 coarse sand) with 2 nos of 6mm mild steel round bars after every three course embedded in cement mortar in foundation and plinth.Conventional	SE-1/10	23.00	746.03	17158.69		0.00	746.03	0.00	SE-1/10	23.00	746.030	17158.69
10	Providing and laying ordinary cement concrete1:1.5:3 (1cement, 1.5sand, 3 graded stone aggregates 20 mm .Nominal size) and finishing smooth with curing etc. complete including the cost of formwork but excluding the cost of reinforcement of R.C.C. work in Column (iii) Having cross-sectional area more than 0.085 Sq.M. and up to 0.18Sq.M	SE-1/5	2.10	10839.25	22762.42	SE-2/5	1.50	10839.25	16258.87	SE-1/5	2.10	10839.250	22762.42

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
9	Half brick masonry in comon burnt clay building bricks having crushing strength not less than 35Kg./Sq.Cm. in cement mortar 1:3 (1 Cement : 3 coarse sand) with 2 nos of 6mm mild steel round bars after every three course embedded in cement mortar in foundation and plinth.Conventional		0.00	746.030	0.00	46.00	746.03	One Squire metre	34317.38
10	Providing and laying ordinary cement concrete1:1.5:3 (1cement, 1.5sand, 3 graded stone aggregates 20 mm .Nominal size) and finishing smooth with curing etc. complete including the cost of formwork but excluding the cost of reinforcement of R.C.C. work in Column (iii) Having cross-sectional area more than 0.085 Sq.M. and up to 0.18Sq.M	SE-2/5	1.50	10839.250	16258.87	7.20	10839.25	One Cubic metre	78042.58

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
11	Providing & laying ordinary C.C. 1:1 1/2:3 (1 cement ,1 1/2 course sand, 3 graded stone agg. of 20 mm nominal size)and for R.C.C. LINTELS incl. Finishing smooth with curring of formwork but excl. the cost of reinforcement.for above floor upto Floor ALL level.	SE-1/12	0.30	8888.19	2666.45		0.00	8888.19	0.00	SE-1/12	0.30	8888.190	2666.45
12	Providing and laying cement concrete1:1.5:3 (1cement, 1.5sand, 3 gradedstone aggregates20 mm.Nominal size) and curing complete, including cost of formwork in sill and sides (R.C.C. band) but excluding the cost of reinforcement upto floor all level	SE-1/11	0.20	7207.31	1441.46	SE-2/8	0.64	7207.31	4612.67	SE-1/11	0.20	7207.310	1441.46
13	Providing & laying cement concrete 1:11/2:3 (1 cement ,11/2 course sand,3graded stone agg.of 20 mm nominal size) for rein-forcement concrete CHHAJJAS not exceeding 10cm. thickness upto floor two level incl. finishing the exposed surface with C.M. 1:3 (1 cement ,3 fine sand) to give a smooth and ever surface, centering, formwork and curring comp.Excl. the cost of reinforcement. above plinth Upto floor all level.	SE-1/13	0.80	7063.33	5650.66		0.00	7063.33	0.00	SE-1/13	0.80	7063.330	5650.66

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
11	Providing & laying ordinary C.C. 1:1 1/2:3 (1 cement ,1 1/2 course sand, 3 graded stone agg. of 20 mm nominal size)and for R.C.C. LINTELS incl. Finishing smooth with curring of formwork but excl. the cost of reinforcement.for above floor upto Floor ALL level.		0.00	8888.190	0.00	0.60	8888.17	One Cubic metre	5332.90
12	Providing and laying cement concrete1:1.5:3 (1cement, 1.5sand, 3 gradedstone aggregates20 mm.Nominal size) and curing complete, including cost of formwork in sill and sides (R.C.C. band) but excluding the cost of reinforcement upto floor all level	SE-2/8	0.64	7207.310	4612.67	1.68	7207.30	One Cubic metre	12108.26
13	Providing & laying cement concrete 1:11/2:3 (1 cement ,11/2 course sand,3graded stone agg.of 20 mm nominal size) for rein-forcement concrete CHHAJJAS not exceeding 10cm. thickness upto floor two level incl. finishing the exposed surface with C.M. 1:3 (1 cement ,3 fine sand) to give a smooth and ever surface, centering, formwork and curring comp.Excl. the cost of reinforcement. above plinth Upto floor all level.		0.00	7063.330	0.00	1.60	7063.33	One Cubic metre	11301.32

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
14	Providing & laying C.C. 1:1/2:3 (1 cement ,1/2 course sand,3 graded stone agg.of 20 mm nominal size) and finishing smooth with curring etc. comp. incl. the cost of formwork but excl. the cost of reinforcement for R.C.C. work in. (A) Beam :- Having cross sectional Area 0.085 to 0.12 Sqm.upto floor all level	SE-1/14	7.50	8035.64	60267.30	SE-2/6	2.00	8035.64	16071.28	SE-1/14	7.50	8035.640	60267.30
15	Providing & laying ordinary cement concrete1:1/2:3 (1 cement ,1/2 course sand,3 graded stone agg.of 20 mm nominal size) exposed work with curring etc.comp. incl. the cost of formwork but excluding the cost of reinforcement for R.C.C. work in. SLAB :- having more then 10cm. and end upto 13cm. thickness.upto floor all level	SE-1/15	8.10	7258.19	58791.33		0.00	7258.19	0.00	SE-1/15	8.10	7258.190	58791.33
16	Providing TMT Bar FE 500/500D reinforcement for R.C.C. work including bending, binding and placing in position complete upto floor all level	SE-1/16	2445.00	77.29	188974.05	SE-2/10	479.00	77.29	37021.91	SE-1/16	2445.00	77.290	188974.05

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
14	Providing & laying C.C. 1:1/2:3 (1 cement ,1/2 course sand,3 graded stone agg.of 20 mm nominal size) and finishing smooth with curring etc. comp. incl. the cost of formwork but excl. the cost of reinforcement for R.C.C. work in. (A) Beam :- Having cross sectional Area 0.085 to 0.12 Sqm.upto floor all level	SE-2/6	2.00	8035.640	16071.28	19.00	8035.64	One Cubic metre	152677.16
15	Providing & laying ordinary cement concrete1:11/2:3 (1 cement ,11/2 course sand,3 graded stone agg.of 20 mm nominal size) exposed work with curring etc.comp. incl. the cost of formwork but excluding the cost of reinforcement for R.C.C. work in. SLAB :- having more then 10cm. and end upto 13cm. thickness.upto floor all level		0.00	7258.190	0.00	16.20	7258.19	One Cubic metre	117582.66
16	Providing TMT Bar FE 500/500D reinforcement for R.C.C. work including bending, binding and placing in position complete upto floor all level	SE-2/10	479.00	77.290	37021.91	5848.00	77.29	One Kilogram	451991.92

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
17	Providing fixing of Polished Marble Colour or Black frame for Doors & Windows, Platform including necessary holdfasts, holes for fixtures and fastenings incl. all labour & materials etc. comp	SE-1/17	19.30	3211.25	61977.12		0.00	3211.25	0.00	SE-1/17	19.30	3211.250	61977.12
18	Providing and fixing 35mm. Thick Panelled,glazed orPanelled and glazed shutters for doors, windows and clearstory windows including anodised alluminium butt hinges with necessary screws and Indian Teak Wood shutters with-(B) Partical board panells.12mm. thick including applying primer and two coats of oil painting etc. complete	SE-1/18	3.60	3933.51	14160.63		0.00	3933.51	0.00	SE-1/18	3.60	3933.510	14160.63

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
17	Providing fixing of Polished Marble Colour or Black frame for Doors & Windows, Platform including necessary holdfasts, holes for fixtures and fastenings incl. all labour & materials etc. comp		0.00	3211.250	0.00	38.60	3211.25	One Squire metre	123954.24
18	Providing and fixing 35mm. Thick Panelled,glazed orPanelled and glazed shutters for doors,windows andclearstory windows including anodised alluminiumbutt hinges with necessary screws and Indian TeakWood shutters with-(B) Partical board panells.12mm. thick including applying primer and two coats of oil painting etc. complete		0.00	3933.510	0.00	7.20	3933.51	One Squire metre	28321.26

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
19	Providing and fixing 30mm thick FACTORY MADE SOLID BOTH SIDE PRELAM PANEL PVC DOOR SHUTTER consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19mm x 19mm for stiles, top and bottom rails. M.S. frame shall have a coat of steel primer of approved makde and manufactures. M.S frame covered with 5mm thick heat moulded prelim PVC 'C' channel of siz 30mm thickness, 70 mm width of which 50mm shall be flat and 20mm shall be tapered in 45 degree Angle on either side forming stiles, and 5mm thick, 95mm wide pream PVC sheet out of which 75mm shall be flat and 20mm shall be tapered in 45 degree on the inner side ot form top and bottom rail and 115mm wide prelim PVC sheet out of which 75mm shall be flat and 20mm shall be tapered on both side to form lock rail, Top, bottom and lock rails shall be provided either side of the panel. 10mm (5mm x 2) thick 20mm wide cross PVC sheet shall be provided as gap insert for top rail and bottom rails. Panelling of 5mm thck both side prelim PVC sheet to be fitted in the M.S. frame welded,sealed to the stiles and rails with 7mm (5mm + 2 mm) thick x 15mm wide PVC sheet beading on inner side, and joined togeth with solvent cement adhesive. An additional 5mm thick PVC strip of 20mm width is to be stuck on the interior side of the 'C' chanel using PVC solvent adhesive etc. complete as per direction of Engineering in charge, manufacture's specification and rawing.	SE-1/45	1.30	2236.14	2906.98		0.00	2236.14	0.00	SE-1/45	1.30	2236.140	2906.98

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
19	Providing and fixing 30mm thick FACTORY MADE SOLID BOTH SIDE PRELAM PANEL PVC DOOR SHUTTER consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19mm x 19mm for stiles, top and bottom rails. M.S. frame shall have a coat of steel primer of approved makde and manufactures. M.S frame covered with 5mm thick heat moulded prelim PVC 'C' channel of siz 30mm thickness, 70 mm width of which 50mm shall be flat and 20mm shall be tapered in 45 degree Angle on either side forming stiles, and 5mm thick, 95mm wide pream PVC sheet out of which 75mm shall be flat and 20mm shall be tapered in 45 degree on the inner side of form top and bottom rail and 115mm wide prelim PVC sheet out of which 75mm shall be flat and 20mm shall be tapered on both side to form lock rail, Top, bottom and lock rails shall be provided either side of the panel. 10mm (5mm x 2) thick 20mm wide cross PVC sheet shall be provided as gap insert for top rail and bottom rails. Panelling of 5mm thck both side prelim PVC sheet to be fitted in the M.S. frame welded,sealed to the stiles and rails with 7mm (5mm + 2 mm) thick x 15mm wide PVC sheet beading on inner side, and joined togeth with solvent cement adhesive. An additional 5mm thick PVC strip of 20mm width is to be stuck on the interior side of the 'C' chanel using PVC solvent adhesive etc. complete as per direction of Engineering in charge, manufacture's specification and rawing.		0.00	2236.140	0.00	2.60	2236.14	One Squire metre	5813.96

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
20	20mm thick sand faced cement plaster on wall up to height 10meters above ground level consisting of 12mm thick backing coat of C.M. 1:3 (1 cement : 3 sand) and 8mm thick finishing coat of C.M. 1:1 (1 cement : 1 sand) etc. complete	SE-1/19	122.00	342.41	41774.02	SE-2/11	101.00	342.41	34583.41	SE-1/19	122.00	342.410	41774.02
21	Providing 10mm thick cement plaster in single coat on brick/concrete walls for interior plastering upto floor all level and finished even and smooth in (i)Cement mortar 1:3 (1-cement:3-sand)	SE-1/20	153.00	145.65	22284.45		0.00	145.65	0.00	SE-1/20	153.00	145.650	22284.45
22	Providing and laying 24" x 24" vitrified 8MM thick tile flooring over 20MM (average) base of cement mortar 1:6 (1- Cement : 6- Coarse Sand) on new surface or fixing on existing flooring by adhe-sive material including dismentalling of existing flooring and jointed with colour cement slurry including finished with flush pointing and cleaning the surface etc. complete. For Light shade	SE-1/21	44.00	1264.41	55634.04		0.00	1264.41	0.00	SE-1/21	44.00	1264.410	55634.04

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
20	20mm thick sand faced cement plaster on wall up to height 10meters above ground level consisting of 12mm thick backing coat of C.M. 1:3 (1 cement : 3 sand) and 8mm thick finishing coat of C.M. 1:1 (1 cement : 1 sand) etc. complete	SE-2/11	101.00	342.410	34583.41	446.00	342.41	One Squire metre	152714.86
21	Providing 10mm thick cement plaster in single coat on brick/concrete walls for interior plastering upto floor all level and finished even and smooth in (i)Cement mortar 1:3 (1-cement:3-sand)		0.00	145.650	0.00	306.00	145.65	One Squire metre	44568.90
22	Providing and laying 24" x 24" vitrified 8MM thick tile flooring over 20MM (average) base of cement mortar 1:6 (1- Cement : 6- Coarse Sand) on new surface or fixing on existing flooring by adhe-sive material including dismentalling of existing flooring and jointed with colour cement slurry including finished with flush pointing and cleaning the surface etc. complete. For Light shade		0.00	1264.410	0.00	88.00	1264.41	One Squire metre	111268.08

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
23	Providing and laying Ceramic tiles 6mm thick in flooring treads of steps and landing laid on a bed of 12mm thick cement mortar 1:3 (1cement : 3-coarse sand) finishing with flush pointing in white cement	SE-1/22	5.10	992.15	5059.96		0.00	992.15	0.00	SE-1/22	5.10	992.150	5059.96
24	Providing and laying Ceramic tiles 6mm thick in skirting risers of steps and dedo on 10mm thick cement plaster 1:3 (1-cement : 3coarse sand) and jointed with white cement slurry	SE-1/23	38.10	1023.89	39010.20		0.00	1023.89	0.00	SE-1/23	38.10	1023.890	39010.20
25	Providing and laying polished Kota stone slab flooring over 20mm (Average) thick base of cement mortar 1:6 (1cement : 6-coarse sand) or L.M. 1.1.5 (1-Lime putty :1.5 - coarse sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of slab including rubbing and polishing etc. complete. (A) 25mm thick	SE-1/44	13.80	1019.39	14067.58		0.00	1019.39	0.00	SE-1/44	13.80	1019.390	14067.58

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
23	Providing and laying Ceramic tiles 6mm thick in flooring treads of steps and landing laid on a bed of 12mm thick cement mortar 1:3 (1cement : 3-coarse sand) finishing with flush pointing in white cement		0.00	992.150	0.00	10.20	992.15	One Squire metre	10119.92
24	Providing and laying Ceramic tiles 6mm thick in skirting risers of steps and dedo on 10mm thick cement plaster 1:3 (1-cement : 3coarse sand) and jointed with white cement slurry		0.00	1023.890	0.00	76.20	1023.89	One Squire metre	78020.40
25	Providing and laying polished Kota stone slab flooring over 20mm (Average) thick base of cement mortar 1:6 (1cement : 6-coarse sand) or L.M. 1.1.5 (1-Lime putty :1.5 - coarse sand) laid over and jointed with grey cement slurry mixed with pigment to match the shade of slab including rubbing and polishing etc. complete. (A) 25mm thick		0.00	1019.390	0.00	27.60	1019.39	One Squire metre	28135.16

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
26	Applying two coats of Birla or Asian acrylic lapy (putty) & two coats of primer of approved brand and manufacture on new wall surface to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth	SE-1/24	136.90	40.59	5556.77		0.00	40.59	0.00	SE-1/24	136.90	40.590	5556.77
27	Finishing wall with weather proof exterior emulsion paint on wall surface(two coats) to give an required shape even shade after thoroughly brushing the surface to remove all dirt, and remains of loose powdered materials etc complete	SE-1/25	121.40	120.26	14599.56	SE-2/12	101.00	120.26	12146.26	SE-1/25	121.40	120.260	14599.56

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
26	Applying two coats of Birla or Asian acrylic lapy (putty) & two coats of primer of approved brand and manufacture on new wall surface to give an even shade including thoroughly brushing the surface free from mortar dropping and other foreign matter and sand papered smooth		0.00	40.590	0.00	273.80	40.59	One Squire metre	11113.54
27	Finishing wall with weather proof exterior emulsion paint on wall surface(two coats) to give an required shape even shade after thoroughly brushing the surface to remove all dirt, and remains of loose powdered materials etc complete	SE-2/12	101.00	120.260	12146.26	444.80	120.26	One Squire metre	53491.64

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
28	Distempering (Two coats) with oil bound distemper of approved brand and manufacture and of required shade on wall surface to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar dropping and other foreign matter and also including preparing the surface even and papered smooth	SE-1/26	137.00	75.68	10368.16		0.00	75.68	0.00	SE-1/26	137.00	75.680	10368.16
29	Providing and fixing C.I. Manhole cover 0.60 M. x 0.45M. Size having weight not less than 35Kg.	SE-1/27	1.00	958.17	958.17		0.00	958.17	0.00	SE-1/27	1.00	958.170	958.17
30	Providing and fixing water closet squatting pan (Indian type W.C.Pan) size 580 mm. incl. 100mm. Size P trap & Foot rest(Earthwork, bed concrete,foot rests and trap to be measured and paid for separately) (A) Vitreous china (I) Long pattern white colour.	SE-1/28	1.00	1436.33	1436.33		0.00	1436.33	0.00	SE-1/28	1.00	1436.330	1436.33

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
28	Distempering (Two coats) with oil bound distemper of approved brand and manufacture and of required shade on wall surface to give an even shade over and including a priming coat with distemper primer of approved brand and manufacture after thoroughly brushing the surface free from mortar dropping and other foreign matter and also including preparing the surface even and papered smooth		0.00	75.680	0.00	274.00	75.68	One Squire metre	20736.32
29	Providing and fixing C.I. Manhole cover 0.60 M. x 0.45M. Size having weight not less than 35Kg.		0.00	958.170	0.00	2.00	958.17	One Number	1916.34
30	Proving and fixing water closet squatting pan (Indian type W.C.Pan) size 580 mm. incl. 100mm. Size P trap & Foot rest(Earthwork, bed concrete,foot rests and trap to be measured and paid for separately) (A) Vitreous china (I) Long pattern white colour.		0.00	1436.330	0.00	2.00	1436.33	One Number	2872.66

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
31	Providing and fixing PVC SWR Nahni trap IS 14735 for drain - 100 mm diameter with jali of the following nominal diameter of self cleansing design with C.I scread down or hinged grating including the cost of cutting and making good the walls.	SE-1/29	1.00	586.27	586.27		0.00	586.27	0.00	SE-1/29	1.00	586.270	586.27
32	Providing and fixing cast iron spigot and socket soil, waste and ventilating pipes of the following nominal size.(C) 100 mm. Dia.	SE-1/30	3.00	892.39	2677.17		0.00	892.39	0.00	SE-1/30	3.00	892.390	2677.17
33	Providing and fixing in position cowl vent to pipes(C) 100 mm. Dia.	SE-1/31	1.00	505.17	505.17		0.00	505.17	0.00	SE-1/31	1.00	505.170	505.17
34	Providing and fixing S.W. gully trap with C.I. grating brick masonry chamber and water tight C.I. cover with frame of 300mm x 300mm size (inside) with standard weight.(i) Square mouth traps. (A) 100mm x 100mm size P type.	SE-1/32	2.00	1292.19	2584.38		0.00	1292.19	0.00	SE-1/32	2.00	1292.190	2584.38
35	Constructing brick masonry road gully chamber 450mm x 450mm x 775mm with vertical grating complete With C.I. Manhole Cover 450x600 mm size	SE-1/33	1.00	3504.02	3504.02		0.00	3504.02	0.00	SE-1/33	1.00	3504.020	3504.02

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
31	Providing and fixing PVC SWR Nahni trap IS 14735 for drain - 100 mm diameter with jali of the following nominal diameter of self cleansing design with C.I scread down or hinged grating including the cost of cutting and making good the walls.		0.00	586.270	0.00	2.00	586.27	One Number	1172.54
32	Proving and fixing cast iron spigot and socket soil, waste and ventilating pipes of the following nominal size.(C) 100 mm. Dia.		0.00	892.390	0.00	6.00	892.39	One Running metre	5354.34
33	Proving and fixing in position cowl vent to pipes(C) 100 mm. Dia.		0.00	505.170	0.00	2.00	505.17	One Number	1010.34
34	Providing and fixing S.W. gully trap with C.I. grating brick masonry chamber and water tight C.I. cover with frame of 300mm x 300mm size (inside) with standard weight.(i) Square mouth traps. (A) 100mm x 100mm size P type.		0.00	1292.190	0.00	4.00	1292.19	One Number	5168.76
35	Constructing brick masonry road gully chamber 450mm x 450mm x 775mm with vertical grating complete With C.I. Manhole Cover 450x600 mm size		0.00	3504.020	0.00	2.00	3504.02	One Number	7008.04

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
36	Providing and fixing washbasin with single hole for pillar tap with C.I. or M.S. brackets painted white including sutting holes and making good (A) Vitreous China:(ii) Flat Back washbasin 550 mm x 400mm size. (i) In white colour. with CP brass couplin, padastal matching the shade, waste pipe,rubber pipe etc complete	SE-1/34	1.00	2390.66	2390.66		0.00	2390.66	0.00	SE-1/34	1.00	2390.660	2390.66
37	Providing, laying and jointing in true line and level 110 diameter U.P.V.C (Type B) conforming to IS 13592-1992 with one end plain and other end socketed with rubber ring, & fittings conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant, pipe shall be fixed on wall using of PVC clamp of the size 110 mm diameter x 149 mm length x 145 mm heigh at every 2000 mm center to center or shall be concealed in walls as directed including necessary fittings such as bends, shoes etc. including testing of pipes and joints and jointed with adhesive solvent cement including cost of all materials.	SE-1/35	15.00	876.90	13153.50	SE-3/1	6.00	876.90	5261.40	SE-1/35	15.00	876.900	13153.50

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
36	Providing and fixing washbasin with single hole for pillar tap with C.I. or M.S. brackets painted white including sutting holes and making good (A) Vitreous China:(ii) Flat Back washbasin 550 mm x 400mm size. (i) In white colour. with CP brass couplin, padastal matching the shade, waste pipe,rubber pipe etc complete		0.00	2390.660	0.00	2.00	2390.66	One Number	4781.32
37	Providing, laying and jointing in true line and level 110 diametre U.P.V.C (Type B) conforming to IS 13592-1992 with one end plain and other end socketed with rubber ring, & fittings conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant, pipe shall be fixed on wall using of PVC clamp of the size 110 mm diametre x 149 mm length x 145 mm heigh at every 2000 mm center to center or shall be concealed in walls as directed including necessary fittings such as bends, shoes etc. including testing of pipes and joints and jointed with adhesive solvent cement including cost of all materials.	SE-3/1	6.00	876.900	5261.40	42.00	876.90	One Running metre	36829.80

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
38	Providing laying and jointing in true line and level 160 mm dia. U.P.V.C. SWR Type B pipe conforming to IS 13592-1992 with one end plain and other end socketed with rubbering & fitting conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant. Pipe shall be fixed on the wall using of PVC clamp of the size 110 mm dia X 149 mm length X 145 mm high at every 2000 mm center to center or shall be concealed in wall as directed including necessary fittings such as bends, shoes etc. including testing of pipe and joints and jointed with adhesive solvent cement, including cost of all materials.		0.00	834.38	0.00	SE-3/2	5.00	834.38	4171.90		0.00	834.380	0.00
39	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. [D] 32mm.	SE-1/36	10.00	338.24	3382.40		0.00	338.24	0.00	SE-1/36	10.00	338.240	3382.40

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
38	Providing laying and jointing in true line and level 160 mm dia. U.P.V.C. SWR Type B pipe conforming to IS 13592-1992 with one end plain and other end socketed with rubbering & fitting conforming to ISI 14735-1999 of approved make for drainage system pipe line, pipe shall be jointed with each other with rubber lubricant. Pipe shall be fixed on the wall using of PVC clamp of the size 110 mm dia X 149 mm length X 145 mm high at every 2000 mm center to center or shall be concealed in wall as directed including necessary fittings such as bends, shoes etc. including testing of pipe and joints and jointed with adhesive solvent cement, including cost of all materials.	SE-3/2	5.00	834.380	4171.90	10.00	834.38	One Running metre	8343.80
39	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. [D] 32mm.		0.00	338.240	0.00	20.00	338.24	One Running metre	6764.80

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
40	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. [B] 20mm.	SE-1/37	20.00	208.80	4176.00		0.00	208.80	0.00	SE-1/37	20.00	208.800	4176.00
41	Providing and fixing screw down bib taps of following size.(A) Brass screw down bib tap polished bright. (I) 15 mm. Dia.	SE-1/38	3.00	186.83	560.49		0.00	186.83	0.00	SE-1/38	3.00	186.830	560.49
42	Providing sock pit of 5.0 Cumt. Volume including excavating and filling brick bats with dry masonry work at top for 45 cm. Height including covering the top with stone including providing vatas in c.m. 1:3 with finishing, curing etc. complete as directed.	SE-1/39	1.00	3457.27	3457.27		0.00	3457.27	0.00	SE-1/39	1.00	3457.270	3457.27

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
40	Providing and fixing concealed center point to wall ceiling & floor CPVC (SDR 13.5) PIPE having National Sanitation Foundation (NSF) seal for potable water of following dia. nominal bore tube fittings and clamps including making good the wall, ceiling and floor etc. complete. [B] 20mm.		0.00	208.800	0.00	40.00	208.80	One Running metre	8352.00
41	Proving and fixing screw down bib taps of following size.(A) Brass screw downbib tap polished bright. (I) 15 mm. Dia.		0.00	186.830	0.00	6.00	186.83	One Number	1120.98
42	Proving sock pit of 5.0 Cumt. Volume including excavating and filling brick bats with dry masonry work at top for 45 cm. Height including covering the top with stone including providing vatas in c.m. 1;3 with finishing,curing etc. complete as directed.		0.00	3457.270	0.00	2.00	3457.27	One Number	6914.54

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
43	Providing and Fixing double coated Syntex or Equivalent PVC (ISI) mark water tank of required capacity each with all necessary fittings and connection etc. comp on terrace or as directed by Engineer - in- charge.	SE-1/40	1000.00	3.95	3950.00		0.00	3.95	0.00	SE-1/40	1000.00	3.950	3950.00
44	Providing & Constructing filter Chamber of size 1.76 x 1.21 x 1.20 mt. Including connecting rain water pipes as per detail drawing or as directed by engineer incharge.		0.00	10576.72	0.00	SE-2/3	1.00	10576.72	10576.72		0.00	10576.720	0.00
45	Providing and Constructing Percolation Sockwell of 1.54 mt internal clear diameter and 3.50 Mt depth including brick masonry in C.M 1:6.,R.C.C. Top slab of 10 cm thick.filling with gravel etc.complete as per detail drawing or as directed by engineer in charge.		0.00	20693.89	0.00	SE-2/4	1.00	20693.89	20693.89		0.00	20693.890	0.00

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
43	Providing and Fixing double coated Syntex or Equivalent PVC (ISI) mark water tank of required capacity each with all necessary fittings and connection etc. comp on terrace or as directed by Engineer - in- charge.		0.00	3.950	0.00	2000.00	3.95	One Litre	7900.00
44	Providing & Constructing filter Chamber of size 1.76 x 1.21 x 1.20 mt. Including connecting rain water pipes as per detail drawing or as directed by engineer incharge.	SE-2/3	1.00	10576.720	10576.72	2.00	10576.72	One Number	21153.44
45	Providing and Constructing Percolation Sockwell of 1.54 mt internal clear diameter and 3.50 Mt depth including brick masonry in C.M 1:6.,R.C.C. Top slab of 10 cm thick.filling with gravel etc.complete as per detail drawing or as directed by engineer in charge.	SE-2/4	1.00	20693.890	20693.89	2.00	20693.89	One Number	41387.78

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
46	Providing and laying water proofing tretment with chaina mosaic tiles flooring over avg 40 mm C.C.1:2:4 { 1 Cement : 2 sand : 4 Kapachi / Gritt 6 to 12 mm size } bedding for maintaining slope for plain and curve surface & 12 mm to 20 mm of broken piece of seramic / glazed tiles (one for more color as directed) to be laid over cement mortar bedding of C M 1:3 (1 cement : 3 sand) containg one Kg of water profing materials per bag of O P C at plain or / and slops and to be tempered to bring mortar ceramic up to surface with using white cement and colour pigment including rounding of junctions and extending them up to 15 cm along the wall and curing with bends any pattens or design as per drawing and cleaning by using oxalic acid etc complete.	SE-1/41	51.00	1070.33	54586.83		0.00	1070.33	0.00	SE-1/41	51.00	1070.330	54586.83
47	Pro. /Fix. with windows with 40x40x5mm. Iron angle & frame 30x30x4 mm size in Double Shutter with B.G. 20 Gauge Sheet plates with , Hold fasts ,Iron hinges handles,stopper ,and locking arrangement etc. comp. Steel welded is built up section cutting hoisiting , finishing in two coats of oil painting over coat of primer coat etc. comp.	SE-1/42	7.20	3930.67	28300.82		0.00	3930.67	0.00	SE-1/42	7.20	3930.670	28300.82

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
46	Providing and laying water proofing tretment with chaina mosaic tiles flooring over avg 40 mm C.C.1:2:4 { 1 Cement : 2 sand : 4 Kapachi / Gritt 6 to 12 mm size} bedding for maintaining slope for plain and curve surface & 12 mm to 20 mm of broken piece of seramic / glazed tiles (one for more color as directed) to be laid over cement mortar bedding of C M 1:3 (1 cement : 3 sand) containg one Kg of water profing materials per bag of O P C at plain or / and slops and to be tempered to bring mortar ceramic up to surface with using white cement and colour pigment including rounding of junctions and extending them up to 15 cm along the wall and curing with bends any pattens or design as per drawing and cleaning by using oxalic acid etc complete.		0.00	1070.330	0.00	102.00	1070.33	One Squere metre	109173.66
47	Pro. /Fix. with windows with 40x40x5mm. Iron angle & frame 30x30x4 mm size in Double Shutter with B.G. 20 Gauge Sheet plates with , Hold fasts ,Iron hinges handles,stopper ,and locking arrangement etc. comp. Steel welded is built up section cutting hoisiting , finishing in two coats of oil painting over coat of primer coat etc. comp.		0.00	3930.670	0.00	14.40	3930.67	One Squere metre	56601.64

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
48	Providing & Fixing Acrylic sheet name board size 2.00 mt x 0.60 sqm. With painting letters Indicating Gram panchayat office / Village/ Taluka/ Dist. Etc. as directed by Adm. Department etc. with all required material & Labour comp.	SE-1/46	1.20	1515.00	1818.00		0.00	1515.00	0.00	SE-1/46	1.20	1515.000	1818.00
49	Providing, Painting, Lettering " Nandghar" Logo board as per design specified and providing two Direction side of the Building photograph copies -4 of each in postcard size of the completed work as directed 23cm.x45cm.	SE-1/47	1.00	2020.00	2020.00		0.00	2020.00	0.00	SE-1/47	1.00	2020.000	2020.00
50	Providing, Painting, Lettering, of Soft-boards, blackboards, Storage areas as per drawing including all material & taxes etc. complete as per direction of Engineer in charge	SE-1/48	1.00	20200.00	20200.00		0.00	20200.00	0.00	SE-1/48	1.00	20200.000	20200.00

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
48	Providing & Fixing Acrylic sheet name board size 2.00 mt x 0.60 sqm. With painting letters Indicating Gram panchayat office / Village/ Taluka/ Dist. Etc. as directed by Adm. Department etc. with all required material & Labour comp.		0.00	1515.000	0.00	2.40	1515.00	One Squire metre	3636.00
49	Providing, Painting, Lettering " Nandghar" Logo board as per design specified and providing two Direction side of the Building photograph copies -4 of each in postcard size of the completed work as directed 23cm.x45cm.		0.00	2020.000	0.00	2.00	2020.00	One Number	4040.00
50	Providing, Painting, Lettering, of Soft-boards, blackboards, Storage areas as per drawing including all material & taxes etc. complete as per direction of Engineer in charge		0.00	20200.000	0.00	2.00	20200.00	One Number	40400.00

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
51	Providing, Painting, Lettering Mic. Play / Activities and out door installations & Notice Board as per drawing including all material & taxes etc. complete as per direction of Engineer in charge	SE-1/49	1.00	6060.00	6060.00		0.00	6060.00	0.00	SE-1/49	1.00	6060.000	6060.00
52	Providing and fixing M.S. Grills of required pattern to frames of Pipe / Angles etc.including Priming coat of approved primer and Two coats of Oil painting etc. complete (A) Plain Grill grill	SE-1/43	130.00	172.41	22413.30	SE-2/13	78.00	172.41	13447.98	SE-1/43	130.00	172.410	22413.30
53	Providing and fixing 0.60 Meter high fencing with 1.10 (Y shape) meter long M.S. angle posts 40mm x 40mm x 6mm and oil painting 3 coats fixed at 3.00 Mt. c/c with Three horizontal lines and two diagonals of galvanized steel barbed wire weighing 9.38 Kg per 100meter strained and fixed to posts with G.I. staples including fixing the posts in Compoundwall masonry & Coping etc. complete		0.00	298.66	0.00	SE-2/14	30.00	298.66	8959.80		0.00	298.660	0.00

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
51	Providing, Painting, Lettering Mic. Play / Activities and out door installations & Notice Board as per drawing including all material & taxes etc. complete as per direction of Engineer in charge		0.00	6060.000	0.00	2.00	6060.00	One Number	12120.00
52	Providing and fixing M.S. Grills of required pattern to frames of Pipe / Angles etc.including Priming coat of approved primer and Two coats of Oil painting etc. complete (A) Plain Grill grill	SE-2/13	78.00	172.410	13447.98	416.00	172.41	One Kilogram	71722.56
53	Providing and fixing 0.60 Meter high fencing with 1.10 (Y shape) meter long M.S. angle posts 40mm x 40mm x 6mm and oil painting 3 coats fixed at 3.00 Mt. c/c with Three horizontal lines and two diagonals of galvanized steel barbed wire weighing 9.38 Kg per 100meter strained and fixed to posts with G.I. staples including fixing the posts in Compoundwall masonry & Coping etc. complete	SE-2/14	30.00	298.660	8959.80	60.00	298.66	One Running metre	17919.60

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
54	Point wiring for Light / Bell with 2-1.5 sq.mm & earth wire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multi strand copper wires up to 10 mtr length , in below type of pipe erected with 6A Modular type switch / bell push & accessories and earth continuity of following type, erected on PVC / Metallic/Wooden box, single mounting base frame covered with textured/metallic/white front plate modules erected on / in wall / ceiling as per pipe erected, with necessary Lamp holder/ceiling rose / H.D.Connector as directed. (f) with medium class Rigid PVC pipe and accessories erected concealed in wall/ceiling complete Cat- II	SE-1/50	10.00	465.61	4656.10		0.00	465.61	0.00	SE-1/50	10.00	465.610	4656.10
55	Point wiring for FAN with 2-1.5 sq.mm & earth wire of 1.5 sq.mm (Green) both are of .ISI marked 1.1 KV Grade FRLS PVC insulated multi strand copper wires up to 10 mtr length, in below type of pipe erected with 6A Modular type switch and hum free EME step type electronic fan regulator mounted and accessories with earth continuity of following type erected on PVC / Metallic/Wooden box, single mounting base frame covered with textured/metallic/white front plate modules erected on / in wall / ceiling as per pipe erected. with necessary ceiling rose / H.D.Connector as directed. (f) with medium class Rigid PVC pipe and accessories erected concealed in wall/ceiling completeCat- II	SE-1/51	3.00	654.48	1963.44		0.00	654.48	0.00	SE-1/51	3.00	654.480	1963.44

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
54	Point wiring for Light / Bell with 2-1.5 sq.mm & earth wire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multi strand copper wires up to 10 mtr length , in below type of pipe erected with 6A Modular type switch / bell push & accessories and earth continuity of following type, erected on PVC / Metallic/Wooden box, single mounting base frame covered with textured/metallic/white front plate modules erected on / in wall / ceiling as per pipe erected, with necessary Lamp holder/ceiling rose / H.D.Connector as directed. (f) with medium class Rigid PVC pipe and accessories erected concealed in wall/ceiling complete Cat- II		0.00	465.610	0.00	20.00	465.61	One Point	9312.20
55	Point wiring for FAN with 2-1.5 sq.mm & earth wire of 1.5 sq.mm (Green) both are of .ISI marked 1.1 KV Grade FRLS PVC insulated multi strand copper wires up to 10 mtr length, in below type of pipe erected with 6A Modular type switch and hum free EME step type electronic fan regulator mounted and accessories with earth continuity of following type erected on PVC / Metallic/Wooden box, single mounting base frame covered with textured/metallic/white front plate modules erected on / in wall / ceiling as per pipe erected. with necessary ceiling rose / H.D.Connector as directed. (f) with medium class Rigid PVC pipe and accessories erected concealed in wall/ceiling completeCat- II		0.00	654.480	0.00	6.00	654.48	One Point	3926.88

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
56	Point wiring for on board Looped Plug with 6A Modular type switch & 5 pin socket erected on PVC / Metallic/Wooden box, single mounting base frame covered with textured / metallic/white front plate modules erected on / in wall / ceiling with following type accessories Cat- II	SE-1/52	2.00	236.34	472.68		0.00	236.34	0.00	SE-1/52	2.00	236.340	472.68
57	Point wiring for Individual Plug with & earth wire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multi strand copper wires up to 10 mtr length, in below type of pipe erected complete with Modular type switch & 5 pin Plug erected on PVC / Metallic/Wooden box covered with appropriate front plate modules erected on / in wall / ceiling as per pipe erected with following type of accessories. [I] For 6A Plug and 6 a switch with 2-1.5 sq.mm Cu. Wire from nearby switchboard/mcb db board (f) with medium class Rigid PVC pipe and accessories erected concealed in wall/ceiling complete - Cat_II	SE-1/53	2.00	493.89	987.78		0.00	493.89	0.00	SE-1/53	2.00	493.890	987.78

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
56	Point wiring for on board Looped Plug with 6A Modular type switch & 5 pin socket erected on PVC / Metallic/Wooden box, single mounting base frame covered with textured / metallic/white front plate modules erected on / in wall / ceiling with following type accessories Cat- II		0.00	236.340	0.00	4.00	236.34	One Point	945.36
57	Point wiring for Individual Plug with & earth wire of 1.5 sq.mm (Green) both are of ISI marked 1.1 KV grade FRLS PVC insulated multi strand copper wires up to 10 mtr length, in below type of pipe erected complete with Modular type switch & 5 pin Plug erected on PVC / Metallic/Wooden box covered with appropriate front plate modules erected on / in wall / ceiling as per pipe erected with following type of accessories. [I] For 6A Plug and 6 a switch with 2-1.5 sq.mm Cu. Wire from nearby switchboard/mcb db board (f) with medium class Rigid PVC pipe and accessories erected concealed in wall/ceiling complete - Cat_II		0.00	493.890	0.00	4.00	493.89	One Point	1975.56

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
58	supplying and erecting LED indoor fittings with LEDs of wattage 0.2 Watt to 0.5 Watt assembled on single MCPCB, with housing used as a heat sink shall be made of thick sheet Steel conforming to IS: 513/CRCA/ aluminium die cast powder coated and high U.V. & corrosion resistance with diffuser with company mark/name 160V to 270V, Power Factor more than 0.95, THD < 15%, CCT 3000 K to 6500K, Luminaire efficacy> 85 lumens/watt ,LED LED driver efficiency > 85 % (fitting required LM-79 & LM-80 Certificates)(NOTE: Below description have shown ranges of Wattage capacity of LED fittings.The Engineer incharge may select any wattage capacity between the ranges shown.) (A) Tube Light with integral driver (iii) 18-20 Watts, Surge - 2KV,IP-20, conventional 4 feet cat-II	SE-1/54	8.00	238.36	1906.88		0.00	238.36	0.00	SE-1/54	8.00	238.360	1906.88
59	providing and erecting Miniature circuit breaker single pole 6A to 25A suitable to operate on 240 V A.C. system and having breaking capacity 10 KA to be erected in existing box. confirming to IS 8828/1996 with ISI Mark Cat-II	SE-1/55	1.00	91.91	91.91		0.00	91.91	0.00	SE-1/55	1.00	91.910	91.91

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
58	supplying and erecting LED indoor fittings with LEDs of wattage 0.2 Watt to 0.5 Watt assembled on single MCPCB, with housing used as a heat sink shall be made of thick sheet Steel conforming to IS: 513/CRCA/ aluminium die cast powder coated and high U.V. & corrosion resistance with diffuser with company mark/name 160V to 270V, Power Factor more than 0.95, THD < 15%, CCT 3000 K to 6500K, Luminaire efficacy> 85 lumens/watt ,LED LED driver efficiency > 85 % (fitting required LM-79 & LM-80 Certificates)(NOTE: Below description have shown ranges of Wattage capacity of LED fittings.The Engineer incharge may select any wattage capacity between the ranges shown.) (A) Tube Light with integral driver (iii) 18-20 Watts, Surge - 2KV,IP-20, conventional 4 feet cat-II		0.00	238.360	0.00	16.00	238.36	One Number	3813.76
59	providing and erecting Miniature circuit breaker single pole 6A to 25A suitable to operate on 240 V A.C. system and having breaking capacity 10 KA to be erected in existing box. confirming to IS 8828/1996 with ISI Mark Cat-II		0.00	91.910	0.00	2.00	91.91	One Number	183.82

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
60	Providing & erecting 240 V MCB double pole switch for lighting Load (B Curve) having 10 KA breaking capacity & confirms to IS : 8828 in existing box having following capacity (A) 6 to 32 Amp. - Cat-III	SE-1/56	1.00	278.76	278.76		0.00	278.76	0.00	SE-1/56	1.00	278.760	278.76
61	Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with busbar, neutral link, earth bar and DIN rail, Conforms to IS 8623-1 & 3, IEC 61439-1 & 3 without MCB to house appropriate nos. of MCBs.(The DBs should be used of same company of MCB to be used) suitable for (A) single phase incoming and horizontal single phase outgoing (b) sheet steel double door (IP-43) (iv) 12 Way	SE-1/57	1.00	1492.78	1492.78		0.00	1492.78	0.00	SE-1/57	1.00	1492.780	1492.78
62	Providing and erecting Approved make Ceiling fan with double ball bearing ISI mark with condenser A.C. 230V.50 c/s.1200 mm. sweep complete, canopy erected on existing hook or clamp with earthing.	SE-1/58	2.00	1596.81	3193.62		0.00	1596.81	0.00	SE-1/58	2.00	1596.810	3193.62

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
60	Providing & erecting 240 V MCB double pole switch for lighting Load (B Curve) having 10 KA breaking capacity & confirms to IS : 8828 in existing box having following capacity (A) 6 to 32 Amp. - Cat-III		0.00	278.760	0.00	2.00	278.76	One Number	557.52
61	Providing and erecting Sheet Steel powder coated MCB distribution board - flush / surface mounted fitted with busbar, neutral link, earth bar and DIN rail, Conforms to IS 8623-1 & 3, IEC 61439-1 & 3 without MCB to house appropriate nos. of MCBs.(The DBs should be used of same company of MCB to be used) suitable for (A) single phase incoming and horizontal single phase outgoing (b) sheet steel double door (IP-43) (iv) 12 Way		0.00	1492.780	0.00	2.00	1492.78	One Number	2985.56
62	Providing and erecting Approved make Ceiling fan with double ball bearing ISI mark with condenser A.C. 230V.50 c/s.1200 mm. sweep complete, canopy erected on existing hook or clamp with earthing.		0.00	1596.810	0.00	4.00	1596.81	One Number	6387.24

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
63	Providing and Erecting following Shock Proof Tissino Type accessories erected on 3 mm thick PC (Polycarbonate) Sheet in PVC / Metal Box erected on Wall / Ceiling. (14) Electronic Hum Free EME Socket Type Step Fan Regulator.	SE-1/59	2.00	219.17	438.34		0.00	219.17	0.00	SE-1/59	2.00	219.170	438.34
64	Supplying Erecting Aproved make Bracket Fan of ISI Mark with 230 Volt A.C., 50 Cy/S 400/450 mm Sweep complete on Wall or With lead cores and connections complete. (Make shall be Approved by Engineer in Charge)Category II.	SE-1/60	1.00	2105.85	2105.85		0.00	2105.85	0.00	SE-1/60	1.00	2105.850	2105.85
65	Providing and erecting Pipe type earthing with 40 mm dia 2.5 mtr long 'B' grade G.I. pipe with necessary coupling buch buried in specially prepared earth pit & G.I. earth wire of 8 SWG erected & connected as directed. For using salt and charcoal / coke as required for pipe type earthing.	SE-1/61	1.00	994.85	994.85		0.00	994.85	0.00	SE-1/61	1.00	994.850	994.85

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
63	Providing and Erecting following Shock Proof Tissino Type accessories erected on 3 mm thick PC (Polycarbonate) Sheet in PVC / Metal Box erected on Wall / Ceiling. (14) Electronic Hum Free EME Socket Type Step Fan Regulator.		0.00	219.170	0.00	4.00	219.17	One Number	876.68
64	Supplying Erecting Aproved make Bracket Fan of ISI Mark with 230 Volt A.C., 50 Cy/S 400/450 mm Sweep complete on Wall or With lead cores and connections complete. (Make shall be Approved by Engineer in Charge)Category II.		0.00	2105.850	0.00	2.00	2105.85	One Number	4211.70
65	Providing and erecting Pipe type earthing with 40 mm dia 2.5 mtr long 'B' grade G.I. pipe with necessary coupling buch buried in specially prepared earth pit & G.I. earth wire of 8 SWG erected & connected as directed. For using salt and charcoal / coke as required for pipe type earthing.		0.00	994.850	0.00	2.00	994.85	One Number	1989.70

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
66	Mains with 1.1 KV FRLS PVC insulated ISI Marked Standard Copper Conductor wire in following Type of Pipe to be erected Concealed in / Flushed on Wall / Ceiling with 1.5 Sq.mm Copper Conductor FRLS PVC Insulated Standered wire of Green Colour for Earth continuity of following size. (A) With Medium Class Rigid PVC Pipe and Accessories. (a) 2 wire 1.5 Sq.mm.	SE-1/62	35.00	62.62	2191.70		0.00	62.62	0.00	SE-1/62	35.00	62.620	2191.70
67	Supplying & erecting approved make self-priming domestic monoblock water pump with 0.5 H.P. motor, suitable for operation on 230 volts 50 c/s. AC supply with metallic flange, delivery and discharge of 32 LPM at 10 mtrs.head. Cat. II	SE-1/63	1.00	4819.72	4819.72		0.00	4819.72	0.00	SE-1/63	1.00	4819.720	4819.72
68	Providing and fixing 600mm x 450mm bevelled edge mirror of superior glass mounted on 6mm thick A.C. sheet or plywood sheet and fixing to wooden pluge with C.P. brass screws and washers.	SE-1/64	1.00	859.41	859.41		0.00	859.41	0.00	SE-1/64	1.00	859.410	859.41

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
66	Mains with 1.1 KV FRLS PVC insulated ISI Marked Standard Copper Conductor wire in following Type of Pipe to be erected Concealed in / Flushed on Wall / Ceiling with 1.5 Sq.mm Copper Conductor FRLS PVC Insulated Standered wire of Green Colour for Earth continuity of following size. (A) With Medium Class Rigid PVC Pipe and Accessories. (a) 2 wire 1.5 Sq.mm.		0.00	62.620	0.00	70.00	62.62	One Running metre	4383.40
67	Supplying & erecting approved make self-priming domestic monoblock water pump with 0.5 H.P. motor, suitable for operation on 230 volts 50 c/s. AC supply with metallic flange, delivery and discharge of 32 LPM at 10 mtrs.head. Cat. II		0.00	4819.720	0.00	2.00	4819.72	One Number	9639.44
68	Providing and fixing 600mm x 450mm bevelled edge mirror of superior glass mounted on 6mm thick A.C. sheet or plywood sheet and fixing to wooden pluge with C.P. brass screws and washers.		0.00	859.410	0.00	2.00	859.41	One Number	1718.82

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
69	Providing and fixing pre-cast Rubber Dye / steel Dye inter locking concrete block 60mm thick with grade of concrete M300 pneumatic compressed / vibrated mechanically and as per approved design Confirming to IS 15658 : 2006 including 35 mm Sand layer for levelling and filling the joint with sand in proper line and level as per guidelines of IRC : SP 63-2018 etc. Complete	SE-1/65	30.00	706.93	21207.90		0.00	706.93	0.00	SE-1/65	30.00	706.930	21207.90
70	Supplying and Fixing 32 Inch & Display Resolution 1280 x 720 L.E.D. TV complete as per direction of Engineer in charge (Product Id. 5116877-42423941485)	SE-1/66	1.00	10100.00	10100.00		0.00	10100.00	0.00	SE-1/66	1.00	10100.000	10100.00
71	Supplying and Fixing Storage Type Water Cooler With Storage Capacity 15 Liter complete as per direction of Engineer in charge (Product Id. 5116877-67816859218)	SE-1/67	1.00	17675.00	17675.00		0.00	17675.00	0.00	SE-1/67	1.00	17675.000	17675.00
72	Providing and Fixing SS 304 Foldable Checking bed having size 1.50 X 0.60 X 0.75 mm including using of 25mm dia pipe, SS 2mm thick, matter of 25.4 (1") of 40 density, cover with regine cloth of approved quality etc completed as directed by Engineer Incharge.	SE-2/1	1.00	6060.00	6060.00		0.00	6060.00	0.00	SE-2/1	1.00	6060.000	6060.00

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
69	Providing and fixing pre-cast Rubber Dye / steel Dye inter locking concrete block 60mm thick with grade of concrete M300 pneumatic compressed / vibrated mechanically and as per approved design Confirming to IS 15658 : 2006 including 35 mm Sand layer for levelling and filling the joint with sand in proper line and level as per guidelines of IRC : SP 63-2018 etc. Complete		0.00	706.930	0.00	60.00	706.93	One Squire metre	42415.80
70	Supplying and Fixing 32 Inch & Display Resolution 1280 x 720 L.E.D. TV complete as per direction of Engineer in charge (Product Id. 5116877-42423941485)		0.00	10100.000	0.00	2.00	10100.00	One Number	20200.00
71	Supplying and Fixing Storage Type Water Cooler With Storage Capacity 15 Liter complete as per direction of Engineer in charge (Product Id. 5116877-67816859218)		0.00	17675.000	0.00	2.00	17675.00	One Number	35350.00
72	Providing and Fixing SS 304 Foldable Checking bed having size 1.50 X 0.60 X 0.75 mm including using of 25mm dia pipe, SS 2mm thick, matter of 25.4 (1") of 40 density, cover with regine cloth of approved quality etc completed as directed by Engineer Incharge.		0.00	6060.000	0.00	2.00	6060.00	One Number	12120.00

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
73	Providing and Placing IT wood writing table having size 1.50 X 0.75 X 0.75 mt with one side drawer with using of 19mm thick WP wood, top cover with 1 mm thick wood type Formica including using of all necessary material & labour etc completed as directed by Engineer Incharge.	SE-2/2	1.00	15150.00	15150.00		0.00	15150.00	0.00	SE-2/2	1.00	15150.000	15150.00
74	Providing and fixing Fabric cloth Curtain having length 1.8 mtr for covering of checking area including using of alluminum sliding channel etc complete as directed by Engineer Incharge.	SE-2/3	6.75	858.50	5794.87		0.00	858.50	0.00	SE-2/3	6.75	858.500	5794.87
75	Providing and Fixing of SS 304 Hanger for bag including using all necessary materials like SS rail, screw etc completed as directed by Engineer Incharge.	SE-2/4	20.00	252.50	5050.00		0.00	252.50	0.00	SE-2/4	20.00	252.500	5050.00
76	Providing and Fixing pin cushion display board having size 1.20 X 0.75 mt including using of alluminum section frame, 18mm thick WB plywood, nevy blue Cushion cloth pin etc completed as directed by Engineer Incharge.	SE-2/5	1.00	606.00	606.00		0.00	606.00	0.00	SE-2/5	1.00	606.000	606.00

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
73	Providing and Placing IT wood writing table having size 1.50 X 0.75 X 0.75 mt with one side drawer with using of 19mm thick WP wood, top cover with 1 mm thick wood type Formica including using of all necessary material & labour etc completed as directed by Engineer Incharge.		0.00	15150.000	0.00	2.00	15150.00	One Number	30300.00
74	Providing and fixing Fabric cloth Curtain having length 1.8 mtr for covering of checking area including using of alluminum sliding channel etc complete as directed by Engineer Incharge.		0.00	858.500	0.00	13.50	858.50	One Running metre	11589.74
75	Providing and Fixing of SS 304 Hanger for bag including using all necessary materials like SS rail, screw etc completed as directed by Engineer Incharge.		0.00	252.500	0.00	40.00	252.50	One Number	10100.00
76	Providing and Fixing pin cushion display board having size 1.20 X 0.75 mt including using of alluminum section frame, 18mm thick WB plywood, nevy blue Cushion cloth pin etc completed as directed by Engineer Incharge.		0.00	606.000	0.00	2.00	606.00	One Number	1212.00

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
77	Providing and fixing PVC modular kitchen cabinet consisting of base and wall units, made from high quality rigid PVC boards (minimum 15-18 mm thick), including shutters, shelves, drawers, SS hinges, telescopic channels, handles, magnetic locks, necessary fittings, cutting, fixing, complete as per design and direction of Engineer Incharge.	SE-2/6	2.32	7575.00	17574.00		0.00	7575.00	0.00	SE-2/6	2.32	7575.000	17574.00
78	Providing and fixing foldable MS ladder having 0.90mt wide & 3.60mt long including rod hinge arrangement at middle with ladder including one coat of red oxide & two coats of oil paint etc completed as directed by Engineer Incharge.	SE-2/7	48.60	110.77	5383.42		0.00	110.77	0.00	SE-2/7	48.60	110.770	5383.42
79	Providing and fixing of hook of 10mm or 12mm dia including drilling hole, fixing of male- female thrade fastner sealing the same with appoxy compound, finishing the same etc complete as directed by Engineer Incharge.	SE-2/8	1.00	303.00	303.00		0.00	303.00	0.00	SE-2/8	1.00	303.000	303.00

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
77	Providing and fixing PVC modular kitchen cabinet consisting of base and wall units, made from high quality rigid PVC boards (minimum 15-18 mm thick), including shutters, shelves, drawers, SS hinges, telescopic channels, handles, magnetic locks, necessary fittings, cutting, fixing, complete as per design and direction of Engineer Incharge.		0.00	7575.000	0.00	4.64	7575.00	One Squire metre	35148.00
78	Providing and fixing foldable MS ladder having 0.90mt wide & 3.60mt long including rod hinge arrangement at middle with ladder including one coat of red oxide & two coats of oil paint etc completed as directed by Engineer Incharge.		0.00	110.770	0.00	97.20	110.77	One Kilogram	10766.84
79	Providing and fixing of hook of 10mm or 12mm dia including drilling hole, fixing of male- female thrade fastner sealing the same with appoxy compound, finishing the same etc complete as directed by Engineer Incharge.		0.00	303.000	0.00	2.00	303.00	One Number	606.00

Sr No.	Item	Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Jalila-4 Tal. Ranpur Dist. Botad				Sub Estimate 03 & 04				Construction of Anganvadi - Nand Ghar (Frame structure) at Village- Chandarva-3 Tal. Ranpur Dist. Botad			
		Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount	Nos	Qty	Rate	Amount
80	Providing and fixing medical device & equipment standio meter height measuring scale 2.10mt long including fixing in wall with using of all heavy SS screw, rail etc complete as directed by Engineer Incharge.	SE-2/9	1.00	1414.00	1414.00		0.00	1414.00	0.00	SE-2/9	1.00	1414.000	1414.00
81	Providing and supplying standard PVC (Polyvinyl chloride) Chair with handle of approved design and make as directed by Engineer Incharge.	SE-2/10	2.00	1010.00	2020.00		0.00	1010.00	0.00	SE-2/10	2.00	1010.000	2020.00
82	Providing and supplying standard PVC (Polyvinyl chloride) Chair with handle of approved design and make as directed by Engineer Incharge.	SE-2/11	2.00	606.00	1212.00		0.00	606.00	0.00	SE-2/11	2.00	606.000	1212.00
83	Providing & fixing ABC type fire extinguisher 4 kg ISI marked complete	SE-2/12	1.00	1515.00	1515.00		0.00	1515.00	0.00	SE-2/12	1.00	1515.000	1515.00
	Dismntled Material Credit Rs. 0 will be deducted from 1 St R.A. Bill												
	Total				1251899.67				245916.13				1251899.67

1497815.89

-0.09

1497815.89

-0.09

Sr No.	Item	Sub Estimate 03 & 04				Total Qty	Rate	Unit.	Amount
		Nos	Qty	Rate	Amount				
80	Providing and fixing medical device & equipment standio meter height measuring scale 2.10mt long including fixing in wall with using of all heavy SS screw, rail etc complete as directed by Engineer Incharge.		0.00	1414.000	0.00	2.00	1414.00	One Number	2828.00
81	Providing and supplying standard PVC (Polyvinyl chloride) Chair with handle of approved design and make as directed by Engineer Incharge.		0.00	1010.000	0.00	4.00	1010.00	One Number	4040.00
82	Providing and supplying standard PVC (Polyvinyl chloride) Chair with handle of approved design and make as directed by Engineer Incharge.		0.00	606.000	0.00	4.00	606.00	One Number	2424.00
83	Providing & fixing ABC type fire extinguisher 4 kg ISI marked complete		0.00	1515.000	0.00	2.00	1515.00	One Number	3030.00
	Dismantled Material Credit Rs. 0 will be deducted from 1 St R.A. Bill								
	Total				245916.13				2995631.60