

BILL OF QUANTITY

Providing And Installing Bituminous Geomebrane Liner At Ch.0' To 120 mt Of Main Canal Of D.R.P.

It. No.	Description of Item (with brief specification and reference to book of specifications)	Quantity	Unit	Rate in Rs.	Amount in Rs.
1	Bituminous Geomembrane liner for canal: Supply, laying and joining Bituminous Geomembrane as hydraulic liner over canal with side slope not steeper than 1(V):1(H) including up to 200 mm overlap, having average thickness of 4mm (minimum thickness 3.6mm), minimum width of 5m, minimum tensile strength of 15kN/m and minimum permissible elongation of 50% which shall be laid on the properly prepared subgrade including import duties & custom clearance charges, transportation, loading/unloading, labour charges, excavation for trench, anchorage and testing which shall confirm to ASTM/IS standards and excluding dismantling of concrete, earthwork, dewatering, and overlap beyond 200 mm and all other ancillary operations including all lead and lifts etc., complete.	2142.00	Sq.Mt	1782.00	3817044.00
			Total Amount Rs.		3817044.00

Executive Engineer
Deesa Irrigation Division
Deesa