

## **SCHEDULE - B**

**Name of work :-**

**PROPOSED CONSTRUCTION OF A INTERIAR C C ROAD WORK IN  
R.S.No. 27 paiky AT MAIN MARKET YARD - SALIYAVADI ( KADANA )**

Item No.	Quantities estimated but may be more Or less	Item of Work	Tender rates		Unit	Total Amount according to estimated quantities
			In figures	In words		
1	2	3	4	5	6	7
1	687.40	01.Box cutting the road surface to proper slope and camber for making a base for road work including removing the excavated stuff and depositing on the road side slope as directed upto 50Mt.lead.	109.41	Rupees One Hundred Nine And Paise Forty One Only	Cu m	75208.43
2	171.85	02.Providing laying and spreading granular machine crushed BT aggregate materials in required proportion so as to have mix materials gradation equivalent to GSB grade II mixing grader with rotavator and grading with mortar grader at OMC and compacted with vibratory roller 80 to 100 KN static wight to achive desired density etc.complete	1232.85	Rupees One Thousand Two Hundred Thirty Two And Paise Eighty Five Only	Cu m	211865.27
3	303.70	03.Providing and laying compacted WBM grading-II MCBT metal of size 45 to 63mm in required layers including using 13% stone dust as filler including spreading watering and consolidation by vibratory roller etc.complete	1710.29	Rupees One Thousand Seven Hundred Ten And Paise Twenty Nine Only	Cu m	519415.07
4	263.70	04. Providing and laying controlled cement concrete M.200 and curing complete excluding the cost of formwork and reinforcement for reinforced concrete work in (A)Foundations, footings, Base of columns and Mass concrete	4113.41	Rupees Four Thousand One Hundred Thirteen And Paise Forty One Only	Cu m	1084706.22

5	142.50	<b>05.</b> Providing and fixing pre-cast Rubber Dye / steel Dye inter locking concrete block 60mm thick with grade of concrete M300 pneumatic compressed/vibrated mechanically and as per approved design Confirming to IS 15658:2006 including 35 mm Sand layer for levelling and filling the joint with sand in proper line and level as per guidelines of IRC:SP 63-2018 etc. Complete	706.76	Rupees Seven Hundred Six And Paise Seventy Six Only	Cu m	100713.30
6	17.10	<b>06.</b> Providing and casting in situ ordinary cement concrete M-200 for Kerbs/Kerb blocks including formwork, curing and finishing complete.	4360.05	Rupees Four Thousand Three Hundred Sixty And Paise Five Only	Cu m	74556.86
7	2637.00	<b>07.</b> Providing TMT Bar FE 415 reinforcement for R.C.C. work including bending, binding and placing in position complete upto floor two level	68.32	Rupees Sixty Eight And Paise Thirty Two Only	Cu m	180159.84
8	36.45	<b>08.</b> Earthwork for embankment including breaking clods, dressing with all lead and lift and including watering rolling and consolidation of subgrade in layers at O.M.C to required dry density including filling the depression which occur during the process using power roller 8T to 10T.(E) From Borrow area within 3.0KM. lead .	177.91	Rupees One Hundred Seventy Seven And Paise Ninety One Only	Cu m	6484.82
				<b>Total Rs.</b>		<b>2253116.81</b>
					<b>Say Rs.</b>	<b>2253117.00</b>
			<b>TOTAL</b>	<b>Rs.</b>	<b>=</b>	<b>2253117.00</b>