

SCHEDULE - B

Name of work :-

**PROPOSED CONSTRUCTION OF A WEIGH BRIDGE WORK IN R.S.No. 27
paiky AT MAIN MARKET YARD - SALIYAVADI (KADANA)**

Item No.	Quantities estimated but may be more Or less	Item of Work	Tender rates		Unit	Total Amount according to estimated quantities
			In figures	In words		
1	2	3	4	5	6	7
1	45.09	01. Excavation for foundation up to 1:5mt depth l/c Sorting out and Stracking of useful material & Disposing of excavated stuff up to 50mt.dense or hard soil	157.15	Rupees One Hundred Fifty Seven And Paise Fifteen Only	Cu m	7085.89
2	9.84	02. Providing & Laying cement concrete 1 :4:8 (1Cement,4 Corse Sand, 8 Hands Broken Stone aggregate 40mm nominal size) & curring Complate excluding the cost of formwork in foundation and plinth.	2717.19	Rupees Two Thousand Seven Hundred Seventeen And Paise Nineteen Only	Cu m	26737.15
3	14.14	03. Brickwork using Common Burnt clay building Bricks crusing St rength not less then 35Kg/cm2 in Foundation& Plinth inCement Mortar1:5(1Cement, 5 findSand) Conventional up to floor two level.	4245.09	Rupees Four Thousand Two Hundred Forty Five And Paise Nine Only	Cu m	60025.57
4	8.82	04. Providing & Fixing 35 mm thick Sutter for Doors & Windows including Indian Teak Wood Frame 10X 7cm.Sizeincluding anodized allumi -nium fixture & Fastenings including Prime coat of Approved quality &Two coats of oil pents.(B) Fully Pannalled	5533.67	Rupees Five Thousand Five Hundred Thirty Three And Paise Sixty Seven Only	Sq m	48806.97

5	1.29	05. Providing &lay.Ordinary Cement Concrate1:2:4 (1Cement, 2 CoarseSand,4aggregate 20mm nominal size) of reinforcement Concrate LINTEL not Exceeting 10 cm thickness upto floor two level including finishing the exposed surface with cement mortar1: 3 (1cement, 3 fineSand) to grove smooth surface centaring & formwork and curring etc.comp Excluding the costof Reinforcement.	10219.39	Rupees Ten Thousand Two Hundred Nineteen And Paise Thirty Nine Only	Cu m	13183.01
6	2.70	06. Providing and Casting in setu ordinary cement concreate M100 mix and providing nessessary pin headera including shuttering, scaffolding laying vibreting curing and finishing complate without v, grove A. HIGH from 0 to 5/M (more then 10 ton)	3547.14	Rupees Three Thousand Five Hundred Forty Seven And Paise Fourteen Only	Cu m	9577.28
7	20.42	07. Providing and laying controlled cement concrete M.250 exposed work with curing etc. complete including the cost of formwork but excluding the cost of reinforcement for R.C.C. work in (A) BEAMS :(i) Having cross-sectional area 0.05 to 0.08 Sq.MSqm)	10824.26	Rupees Ten Thousand Eight Hundred Twenty Four And Paise Twenty Six Only	Cu m	221031.39
8	15.10	08. Providing and laying Controlled concreate M200 exposed work with curing etc. complate Including the cost of formwork but excluding the cost of Rein- forcement for R.C.C work in (B) COLUMN having Cross Sectional area more thane (0.08 and upto 0.1)	12577.32	Rupees Twelve Thousand Five Hundred Seventy Seven And Paise Thirty Two Only	Cu m	189917.53

9	4.02	09. Providing and laying controlled M150 and finishing smooth with curing etc. comp. including cost of formwork but excluding the cost of Reinfor -cement forwork in (ii) SLAB having cross sectional area more than (10 cm & up to13 cm thickness)	6888.14	Rupees Six Thousand Eight Hundred Eighty Eight And Paise Fourteen Only	Cu m	27690.32
10	3835.00	10. Providing H.Y.S.D.Bar reinforcement for R.CC work including bending, binding and placing in position complete upto floor two levell.	63.87	Rupees Sixty Three And Paise Eighty Seven Only	Kg	244941.45
11	1643.00	11. Providing Mild Steel reinforcement for R.C.C. work including bending binding, and placing in position complete upto floor two level	61.65	Rupees Sixty One And Paise Sixty Five Only	Kg	101290.95
12	135.00	12. Providing 20 mm.Th.Cement Plaster in Singale coat on fair side of brick concrate wall for interior finished even smooth incement mortar1:4(1ement :4Sand) including finising with a floting coat of ce. slurry.	274.43	Rupees Two Hundred Seventy Four And Paise Forty Three Only	Sq m	37048.05
13	69.75	13. Providing and laying cement concrete flooring 1:2:4(1-cement : 2-coarse sand : 4-graded stone aggregate20mm nominal size)laid in one layer and finished with a floating coat of neat cement.	347.41	Rupees Three Hundred Forty Seven And Paise Forty One Only	Sq m	24231.85
14	1.00	14. Shifting and RE instollation for electronic weighting machine approved bythe legal metrology department Government of india i/c cost of exice vat, service tax i/c stamping charges instollation commissioning callebration, transportation charges etc. comp. as per instruction of EIC the weight Bridge having 50.00 MTcapacity	550000.00	Rupees Five Lakh(s) Fifty Thousand Only	Unit	550000.00
				Total Rs.		1561574.42
				Say Rs.		1561574.00
			TOTAL	Rs.	=	1561574.00