

SCHEDULE -B

Sub : Work of Providing FRP fencing around distribution transformer at various locations within jurisdiction of Vandsa SDN UNDER Waghai Division.

Sr. No.	Description	QTY	Unit	Rate	Amount in RS.
1	Providing and fixing of FRP fencing of 1500mm height at Distribution Transformer Centers with necessary excavation, concreting for grout in vertical posts up to 450 mm in ground, Hardware, accessories, fitting, lock, etc. complete as shown in specifications and drawing enclosed. The fencing shall comprise of one gate 2000 mm wide having two flaps and payment for the same shall be measured on Rmt basis.		RMT	3000	
2	Inside fencing area to be levelled property first by compaction above road level and then finished with 6" thick 1:2:4 cement concrete & cement plaster supported with 6" brick wall on surrounding (Material to be utilised : Cement bags, Bricks, Sand & Aggregates) is to be bought by the contractor at his own cost.(Payment will be given in sq.foot for which concrete is done inside FRP Fencing including wall)(size 3 x 3 mtr)		SQ FT.	81	
TOTAL AMOUNT					25,00,000

IN WORDS: TWENTY FIVE LAKHS ONLY

Executive Engineer (O & M)
DGVCL,Waghai Division