

Mandatory Instructions for Collection & supply of Ballast

The following instructions shall be strictly adhered to during the collection and supply of ballast works:

Height of the stack measurement:

- i) The height of the ballast stack should be measured accurately using a levelling instrument.

Unloading of ballast in railway track:

- ii) Minimum 15 labourers should be deployed for unloading at least 30 BOBYN ballast wagons. In case of any deficiency in labour deployment noticed during execution of the work, suitable penalty as decided by the Engineer-in-Charge shall be imposed and recovered from the contractor.