

SPECIAL CONDITIONS for NON-SCHEDULE ITEMS

- 1) **NS/1:-** Fabricating, Supplying & installing Stainless steel Water booth made up of Stainless Steel pipe of 150 mm dia & 3.15 mm thick & stainless steel sheet for basin. Minimum thickness of 3.00 mm confirming to grade SS 304 or superior including cost of taps & GI pipe above the PF surface but excluding grating and other items below PF surface as per drg no. Misc -507/07, ANVR including steel base plate of 300 x 300 x 12 mm, the approx weight of stainless steel sheet (covered with protective coating) to be used in water booth should be of 116 kg. The finish surface shall be free from any dent/undulation, the item include all accessories, equipments, tool & plants, preparation of fabrication drawing, all labour & material as a complete job. The hand railing & other horizontal members shall be bent to correct radius, profiles, shapes required by the engineer-in-charge using the appropriate means without losing the profile of pipe. Nothing extra shall be paid whatsoever the case may be.
- 2) **NS/2:-** Fabricating, supplying and installing stainless steel 4/ 10 seater benches with or without back rest and seat partition of size and shape as per design and drawing approved by Engineer Incharge. Bench shall be manufactured from stainless steel 304 Grade Confirming IS :6911-1933 with latest Amendments as a complete job. Tolerance in the weight will be 2 % of Specified weight from Nominated weight on either side. Tolerance in Over all dimensions +/- 5% from drawing and +/- 2 % from proto type. The fixing of benches will be done after drilling 300mm in existing surface, providing sleeve pipes with arrangement, filling drilled hole with chemical/concrete GP2 or equivalent non-shrink grout and providing and fixing bolts. For the purpose of fixing of benches, the HD bolts must be SS304 grade with 8mm dia. The logo of 'Indian Railways' may be of vinyl sticker with adhesive of 3M or equivalent quality.
- 3) **NS/3:-** Painting Murals, Pictures, Carving of different size & shapes duly coloured on Smooth Wall Surface / Ply Wood surface with paint & oil Paint / Acrylic paint with different shape on wall to give Ethnic-etho local art / architecture to Station building as a Complete Job as directed by Engineer in charge or his Representative including all labour & materials nothing shall be paid extra on any account. **(A) Scope:-** To improve the architectural view of station buildings & premises scenario and to give Ethnic -ethos local art/architecture to station buildings for attracting tourists, the painting of murals & picture has to be done duly coloured on plastered wall. **(B) Description:-** Painting of murals, picture, carving of different size & shape duly coloured on smooth wall surface/plywood surface with paint & oil painting with different shape on the wall to give Ethnic-etho local art/architecture to station building as a complete job as directed by Engineer-in-charge or his representative including all labour & material such as paints, brushes, tool & plants, etc. nothing shall be paid extra on any account. **(C) Safety Precaution:-** This work is to be carried out on running Passenger platform. So, at the time of arrival/departure of train, work shall not be carried out in view of safety of the passengers/staff and to avoid inconvenience to the passengers/staff. All safety measures are to be adopted by the contractor on his own expenses. **(D) Payment:-** This item includes all labour & material such as paints, brushes, tool & plants, etc. Nothing extra shall be paid on any account. The payment of this item shall be done in square metre of area.
- 4) **NS/4:-** Supply & fixing of display name sign, place made out of 3mm ACP sheet 0.25mm thickness with digital print on Avery's dennison vinyl LD 1710 G, with lamination LD 171212G with 10 years warranty of colour fading and fix on wall with help of steel screw. The item to be provided as per consultant and Railway engineer-in-charge/supervisor's entire satisfaction. All specifications/guarantee card/warranty card duly stamped and authorized by authorized dealer/competent authority shall be provided to Railway.

- 5) **NS/5:-** Providing & fixing of C.P hand spray (Health faucet) of Jaguar ALD573 / CERA CG106/ParrywareT9941A1 button control and flexible hose connection with CP holder for hand spray complete including CPT extension for connection from angle valve for filling of WC tank complete in all respects and making good. The item to be provided as per consultant and Railway engineer-in-charge/supervisor's entire satisfaction. All specifications/guarantee card/warrantee cardduly stamped and authorized by authorized dealer/competent authority shall be provided to Railway.
- 6) **NS/6:-** Providing & fixing First Quality White vitreos china Oval Shaped over/ under counter Wash basin 505 x 410 mm with 32 mm dia cp brass bottle trap with CI brackets of Required Length and Size and other ancillary fittings as per Specifications. The item to be provided as per consultant and Railway engineer-in-charge/supervisor's entire satisfaction. All specifications/guarantee card/warrantee cardduly stamped and authorized by authorized dealer/competent authority shall be provided to Railway.
- 7) **NS/7:-** Supplying , Fixing ,Jointing and testing of 15 mm dia CP brass Angle Valve of JAQUAR florentine FLR-5053N/CERA Ocean CQ608/Parry ware Coral G1453 A1 with CP brass wall flange with any other item complete including cutting and Making good the wall Wherever required as per direction of Engineer-In charge. The item to be provided as per consultant and Railway engineer-in-charge/supervisor's entire satisfaction. All specifications/guarantee card/warrantee cardduly stamped and authorized by authorized dealer/competent authority shall be provided to Railway.
- 8) **NS/8:-** Providing & fixing JAQUAR Continental CAN-1161-N/ CERA Vermont CA408/Parry ware T6506A1 robe hook, fixed to pvcrawl plug with cp brass screw as per direction of Engineer-In charge complete with all labour and Materials. The item to be provided as per consultant and Railway engineer-in-charge/supervisor's entire satisfaction. All specifications/guarantee card/warrantee cardduly stamped and authorized by authorized dealer/competent authority shall be provided to Railway.
- 9) **NS/9:-** Providing & fixing CP brass single hole Wash basin mixer without popup waste system with 450 mm long braided hoses complete including cutting and Making good the wall Wherever required of JAQUAR florentine FLR-5167/NB/CERA Ocean CQ 615 A/ Parry ware Coral G1414A1 make or Equivalent as Approved. The item to be provided as per consultant and Railway engineer-in-charge/supervisor's entire satisfaction. All specifications/guarantee card/warrantee cardduly stamped and authorized by authorized dealer/competent authority shall be provided to Railway.
- 10) **NS/10:-** Providing and fixing Hindware Cat No F 190027/ Jaquar/ Cera or equivalent make concealed stop cock with internal body on hindware cat No. F- 850096 /Jaquar/ Cera or equivalent & all fittings and fixtures complete including cutting & making good the walls wherever required complete as per direction of engineer incharge. The rate is for complete job & nothing shall be paid extra for labour, material taxes, royalty, fixing & transportation etc. The item to be provided as per consultant and Railway engineer-in-charge/supervisor's entire satisfaction. All specifications/guarantee card/warrantee cardduly stamped and authorized by authorized dealer/competent authority shall be provided to Railway.
- 11) **NS/11:-** Providing and fixing Jayna LSF 140/ Jaquar/ Cera or equivalent make heavy duty C.P. Grating matt finish of size 140 X 140 mm with openable lid and with all fittings and fixtures complete including cutting & making good the walls/floors wherever required complete as per direction of engineer incharge. The rate is for complete job & nothing shall be paid extra for labour, material taxes, royalty, fixing & transportation etc. The item to be provided as per consultant and Railway engineer-in-charge/supervisor's entire satisfaction. All specifications/guarantee card/warrantee cardduly stamped and authorized by authorized dealer/competent authority shall be provided to Railway.

- 12)**NS/12:-** Providing and fixing of CP brass over head shower with arm, round shape multiflow of Jaquar OHS 1989/ Cera CG401/Parryware T9934A1 or similar complete including cutting & making good the walls wherever required complete as per direction of Engineer in charge with contractor's labour, tool & plant including all taxes, royalties and fastener etc complete. The item to be provided as per consultant and Railway engineer-in-charge/supervisor's entire satisfaction. All specifications/guarantee card/warrantee card duly stamped and authorized by authorized dealer/competent authority shall be provided to Railway.
- 13)**NS/13:-** Providing and fixing of rimless wall hung wc with PP soft hinge make of FLS-WHT-5953PPSM and concealed cistern make JCS-WHT-2400S or equivalent including cp bolts and nuts, floor fixing arrangements, soft close seat cover with CP hinges and rubber Buffers, Cp Brass screws, washer with all accessories. The item to be provided as per consultant and Railway engineer-in-charge/supervisor's entire satisfaction. All specifications/guarantee card/warrantee card duly stamped and authorized by authorized dealer/competent authority shall be provided to Railway.
- 14)**NS/14:-** Providing & fixing of Roller Blinds make ORINO or Equivalent with black out fabric shade as Approved with aluminium top & bottom including manual chain operating system . Rates inclusive of all the materials ,Labour, machinery, tools and plants, taxes etc complete in all respect. The item to be provided as per consultant and Railway engineer-in-charge/supervisor's entire satisfaction. All specifications/guarantee card/warrantee card duly stamped and authorized by authorized dealer/competent authority shall be provided to Railway.
- 15)**NS/15:-** Providing 200mm stainless steel handle with necessary SS screw, etc, complete as per direction of Engineer-in-charge. The item to be provided as per consultant and Railway engineer-in-charge/supervisor's entire satisfaction.
- 16)**NS/16:-** Providing and fixing Diverter of make of approved brand like Jaquar ALD-CHR-065 or 639 or equivalent. The item to be provided as per consultant and Railway engineer-in-charge/supervisor's entire satisfaction. All specifications/guarantee card/warrantee card duly stamped and authorized by authorized dealer/competent authority shall be provided to Railway.
- 17)**NS/17:-** Precast Chequered factory made terrazzo tiles 30mm thick with graded marble chips of sizes up to 12mm in stairs treads jointed with neat cement slurry mixed with pigment to match the shade of the tiles including rubbing and polishing, rounding of nosing etc. complete on 20mm thick bed of cement mortar 1:4 (1cement:Coarse sand)- With ordinary cement without any pigment. (Cost of cement for mortar will be paid separately). The work is to be executed as per the direction/satisfaction of engineer in-charge.
- 18)**NS/18:-** Providing & fixing floor mounted e Toilet Cubical with door of Merino make or equivalent, Pilaster and divider of 12 mm thick board both side decorative compact laminated of required colour, shade. As required including stainless steel accessories (SS304 grade) like top rail, door-knob, thumb turn and occupancy indicator twin coat hook, door stopper, adjustable legs,. spring loaded butt hinges with cover, foot sliding latch with indicator PVC wall plugs and locking arrangement, SS Channels etc. as desired. all complete as per drawing and direction of EIC. (Cubical size= Width(W)=1300 to 1500mm, Depth(D)=1500mm, Height(H)= 2100 mm (Including bottom Gap of 100mm), Door size = 1925mm(H) X 600mm (W)). The item to be provided as per consultant and Railway engineer-in-charge/supervisor's entire satisfaction. All specifications/guarantee card/warrantee card duly stamped and authorized by authorized dealer/competent authority shall be provided to Railway.

- 19)**NS/19:-** Providing and fixing Grab bar CERA 2509 /Jaquar/Hindware or equivalent make with all fittings and fixtures complete including cutting & making good the walls wherever required complete as per direction of engineer incharge. The rate is for complete job & nothing shall be paid extra for labour, material taxes, fixing & transportation etc. The item to be provided as per consultant and Railway engineer-in-charge/supervisor's entire satisfaction. All specifications/guarantee card/warrantee cardduly stamped and authorized by authorized dealer/competent authority shall be provided to Railway.
- 20)**NS/20:-**Providing and fixing white vitreous sensor operated Gents Urinal having pre & post flushing with water having water inlet from back side, including fixing of control Plate (Made of stainless steel sensor) to wall with suitable brackets all as per manufacturers specification and direction of Engineer-in- charge.
- 21)**NS/21:-**Providing and applying marbel texture based paint of average thickness 1mm,of approved brand and manufacturer over the plastered wall surface upto all height above ground level in panels with groove all around as per approved pattern complete as per direction of Engineer-in-charge (Payment for providing grooves shall not be made separately.)
- 22)**NS/22:-**Dismantling and credit to railway for released material of existing service/residential buildings such as office rooms, verandah, service room, lavatory block etc. with contractor's own labour and equipments etc. at the site released materials such as rails, pipe line, electrical & telecommunication fixtures shall be the property of railway and the same will be stacked at SSE/Works store godown from dismantling of walls, roofing, floors all types of foundations to the required depth, trusses and ceiling at any height the other released materials will be the contractor's property and all the dismantled materials including rubbing etc. shall be removed simultaneously to keep the site clear for execution of other works as directed by the Engineer-In-Charge and as per special conditions of contract and standard specifications including all lead, lift, ascents, descents, crossing of railway tracks, level crossing, nallahs, and any other obstructions whatsoever including all handling, re-handling of materials etc. and all other charges to complete the work.
- NS/23 and NS/24 are self explanatory.**