

Zone 24 50.00 % WO's for year 2026-27			
S. No.	Work Order Name	Amount	
1 ✓	Roof repair by aluminium alloy sheeting of SPN Running room.	497190.00	
2 ✓	Service buildings tile and granite repair works at BFPA, BSUR, NOH, BNSA and SZN.	499450.16	
3 ✓	Misc. repair work of RWP, Water hydrants, flooring, doors, RCC benches, roof parapets and water cooler stand of stations between Pilibhit-Shahjahanpur.	499047.51	
4 ✓	Improvement of sunken CC brackets of Low cost PP Shelter of Halts between PBE-SPN.	440668.54	
5 ✓	One time jungle cleaning of Halts between PBE-SPN.	174000.00	
6 ✓	Painting of bridges and parapets between PBE-SPN.	497375.00	
7 ✓	Lettering of bridges tablet, HFL, DL, Span etc between PBE-SPN.	336887.85	
8 ✓	Periodical painting works of NOH and SZN qtrs. (12 Nos. type-II)	499991.94	
9 ✓	Periodical painting works of BFPA qtrs. (08 Nos. type-II)	333327.96	
10 ✓	Periodical painting works of BSUR TSS, BFPA & NOH SSP, PBE & SZN SP and Tower Wagon Shed.	302199.56	
11 ✓	Repair of plaster, septic tank, flooring, etc of SPN colony quarters.	472369.84	
12 ✓	Roof repair by aluminium alloy sheeting of BSUR Type-I Block.	497190.00	
13 ✓	Repair of doors, windows of SPN railway colony.	341926.73	
14 ✓	Repair of doors, windows of BFPA, BSUR, NOH and SZN colony.	302082.73	
15 ✓	Providing back verandah grill mesh for protection from monkeys in quarters at LC's.	139454.00	
16 ✓	Roof repair by aluminium alloy sheeting of SPN Type-II Block.	497190.00	
17 ✓	Repair of flooring, drain, tiles and plaster of SZN+NOH colony (08 type-II).	418801.44	
18 ✓	Repair of flooring, drain, tiles and plaster of BFPA+BSUR colony.	499907.48	
	Grand Total=	7249060.72	

*(Signature)*  
(8888888888)

क्षेत्र-संविदा के अन्तर्गत निर्माणदेश

निर्माणदेश संख्या - 01/PS/26-27/

दिनांक-.....

क्षेत्र संविदा करार सं०--IZN/DIV/ENG/NER-IZN-2026-ZONE 23/..... दिनांक-.....के


अन्तर्गत निर्माण का काम- Painting of bridges and parapets between PBE-SPN.

प्राधिकार..... विनिधान.....  
इसके पहले संदर्भित क्षेत्र-संविदा करार के अन्तर्गत ठेकेदार ..... को एतद्वारा निम्नलिखित निर्माण कार्य करने का आदेश दिया जाता है-

क्रम संख्या	क्षेत्र-संविदा करार के साथ नत्थी अनुसूची की मद सं० DSR- 2021	अनुमानित परिमाण	निर्माण मद विवरण	इकाई	क्षेत्र-संविदा करार के साथ नत्थी अनुसूची की दर रु० पै०	रकम रु० पै०
1	2	3	4	5	6	7
1	13.111.2	2000.00	Finishing walls with Acrylic Smooth exterior paint of required shade : Old,work (One or more coat applied @ 0.90 ltr/10 sqm).	Sqm.	74.75	149500.00
2	13.109.2	5500.00	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats @ 2.20 kg/10 sqm) complete.	Sqm.	63.25	347875.00
Total=						497375.00
Gr. Total=						497375.00

इसमें उल्लिखित निर्माण कार्य (दिनांक)--30.06.2027--को अथवा उसके पहले पूरे होने चाहिए। इसमें अनुमानित है और संविदा की सामान्य शर्तों की धारा 42 के अन्तर्गत इसमें घट और बढ़ सकती है।

दिनांक-----

  
सी.से.इंजी.(कार्य)  
पीलीभीत

सहायक मण्डल इंजी०  
पीलीभीत

वरिष्ठ मण्डल इंजीनियर(I) इज्जतनगर  
कृते भारत के राष्ट्रपति

यहाँ नत्थी रेखणों के अनुरूप पूर्वोक्तित क्षेत्र-संविदा सम्बन्धी सामान्य व विशेष शर्तों (यदि कोई हो ) यथा विनिर्देशों के अनुसार  
यहां उल्लिखित निर्माण कार्या के उपर्युक्त तिथि को अथवा उसके पूर्व करने का करार करता हूँ ।

गवाह हस्ताक्षर .....  
दिनांक .....

(ठेकेदार/ ठेकेदारों का हस्ताक्षर) .....  
दिनांक.....

पूर्वोत्तर रेलवे  
क्षेत्र -सविदा के अन्तर्गत निर्माणादेश

निर्माणादेश संख्या - 01/PS/26-27/

दिनांक-.....

क्षेत्र सविदा करार सं०--IZN/DIV/ENG/NER-IZN-2026-ZONE 23/..... दिनांक-.....के

अन्तर्गत निर्माण का काम- Repair of plaster, septic tank, flooring, etc of SPN colony quarters.

प्राधिकार-..... विनिर्धान-.....  
इसके पहले संदर्भित क्षेत्र-सविदा करार के अन्तर्गत ठेकेदार ..... को एतद्वारा निम्नलिखित निर्माण कार्य करने का आदेश दिया जाता है-

क्रम संख्या	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की मद सं० DSR- 2021	अनुमानित परिमाण	निर्माण मद विवरण	इकाई	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की दर रु० पै०	रकम रु० पै०
1	2	3	4	5	6	7
1	12.50	16.20	Providing and fixing precoated galvanised iron profile sheets (size, shape and pitch of corrugation as approved by Engineer-in-charge)	Sqm.	671.55	10879.11
2	11.3.1	150.00	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) 40 mm thick with 20 mm nominal size stone aggregate.	Sqm.	545.00	81750.00
3	6.1.2	6.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:6 (1 cement : 6 coarse sand).	Cum.	6658.25	39949.50
4	6.4.2	4.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand).	Cum.	8288.35	33153.40
5	6.13.2	37.50	Half brick masonry with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level. Cement mortar 1:4 (1 cement :4 coarse sand)	Sqm.	1018.05	38176.88
6	13.4.2	325.00	12 mm cement plaster of mix 1:6 (1 cement: 6 coarse sand).	Sqm.	294.35	95663.75
7	15.56	250.00	Dismantling old plaster or skirting raking out joints and cleaning the surface for plaster including disposal of rubbish to the dumping ground within 50 metres lead.	Sqm.	45.05	11262.50
8	5.12	0.50	Providing, hoisting and fixing above plinth level up to floor five level precast reinforced cement concrete work in string courses, bands, copings, bed plates, anchor blocks, plain window sills.	Cum.	9673.50	4836.75
9	5.22.6	80.00	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level. Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg.	89.65	7172.00
10	15.7.4	0.50	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge in cement mortar.	Cum.	* 1698.45	849.23



11	13.80	325.00	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqm.	123.85	40251.25
12	15.2.1	7.50	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix).	Cum.	2007.10	15053.25
13	10.16.1	140.00	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position Hot finished welded type tubes.	Kg.	154.90	21686.00
14	14.80.1	2.00	Providing & fixing White vitreous china water closet squatting pan (Indian type) Long pattern W.C Pan of size 580x440 mm.	Each	2962.80	5925.60
15	4.1.3	7.50	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources).	Cum.	7365.15	55238.63
16	2.31	300.00	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	Sqm.	14.50	4350.00
17	12.41.2	16.00	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming 110 mm diameter.	Mtr.	319.75	5116.00
18	12.42.5.2	8.00	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes Bend 87.5° 110 mm bend.	Each	132.00	1056.00
Total=						472369.84
Gr. Total=						472369.84

इसमें उल्लिखित निर्माण कार्य (दिनांक) — 30.06.2027 — को अथवा उसके पहले पूरे होने चाहिए। इसमें अनुमानित है और संविदा की सामान्य शर्तों की धारा 42 के अन्तर्गत इसमें घट और बढ़ सकती है।

दिनांक \_\_\_\_\_

  
 सी. सी. ई.जी. (कार्य)  
 पीलीभीत

सहायक मण्डल इंजीनियर  
 पीलीभीत

वरिष्ठ मण्डल इंजीनियर (I) इज्जतनगर  
 कृते भारत के राष्ट्रपति

यहाँ नत्थी रेखाओं के अनुरूप पूर्वावल्लिखित क्षेत्र-संविदा सम्बन्धी सामान्य व विशेष शर्तों (यदि कोई हो) यथा विनिर्देशों के अनुसार यहाँ उल्लिखित निर्माण कार्यों के उपर्युक्त तिथि को अथवा उसके पूर्व करने का करार करता हूँ।

गवाह हस्ताक्षर \_\_\_\_\_  
 दिनांक \_\_\_\_\_

(ठेकेदार/ ठेकेदारों का हस्ताक्षर) \_\_\_\_\_  
 दिनांक \_\_\_\_\_

पूर्वोत्तर रेलवे  
क्षेत्र-संविदा के अन्तर्गत निर्माणादेश

निर्माणादेश संख्या - 01/PS/26-27/

दिनांक-----

क्षेत्र संविदा करार सं०--IZN/DIV/ENG/NER-IZN-2026-ZONE 23/..... दिनांक-----के

अन्तर्गत निर्माण का काम- Periodical painting works of BSUR TSS, BFPA & NOH SSP, PBE & SZN SP and Tower Wagon Shed.

प्राधिकार-----


विनिधान-----

इसके पहले संदर्भित क्षेत्र-संविदा करार के अन्तर्गत ठेकेदार ..... को एतद्वारा निम्नलिखित निर्माण कार्य करने का आदेश दिया जाता है-

क्रम संख्या	क्षेत्र-संविदा करार के साथ नत्थी अनुसूची की मद सं०	अनुमानित परिमाण	निर्माण मद विवरण	इकाई	क्षेत्र-संविदा करार के साथ नत्थी अनुसूची की दर	रकम
1	2	3	4	5	6	7
1	13.90.1	1500.00	Distemping with 1st quality acrylic distemper (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade : Old work (one or more coats)	Sqm.	56.80	85200.00
2	13.80	161.25	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqm.	123.85	19970.81
3	13.99.1	400.00	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	Sqm.	86.55	34620.00
4	13.109.1	1725.00	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 litres/10 sqm complete including cost of Priming coat.	Sqm.	94.15	162408.75
Total=						302199.56
Gr. Total=						302199.56

इसमें उल्लिखित निर्माण कार्य (दिनांक)---30.06.2027---को अथवा उसके पहले पूरे होने चाहिए। इसमें अनुमानित है और संविदा की सामान्य शर्तों की धारा 42 के अन्तर्गत इसमें घट और बढ़ सकती है।

दिनांक-----

  
पी.सी.इंजी. (कार्य)  
पीलीभीत

सहायक मण्डल इंजी०  
पीलीभीत

वरि० मण्डल इंजीनियर(1) इज्जतनगर  
क्षेत्र भारत के राष्ट्रपति

यहाँ नत्थी रेखणों के अनुरूप पूर्वोत्तर रेलवे क्षेत्र-संविदा सम्बन्धी सामान्य व विशेष शर्तों (यदि कोई हो) यथा विनिर्देशों के अनुसार यहाँ उल्लिखित निर्माण कार्य के उपर्युक्त तिथि को अथवा उसके पूर्व करने का करार करता हूँ।

गवाह हस्ताक्षर -----

(ठेकेदार/ ठेकेदारों का हस्ताक्षर) -----

दिनांक -----

दिनांक-----

**पूर्वोत्तर रेलवे**  
**क्षेत्र -संविदा के अन्तर्गत निर्माणदेश**

निर्माणदेश संख्या - 01/PS/26-27/

दिनांक-.....

क्षेत्र संविदा करार सं०--IZN/DIV/ENG/NER-IZN-2026-ZONE 23/..... के दिनांक-.....के

अन्तर्गत निर्माण का काम- Periodical painting works of BFPA qtrs. (08 Nos. type-II)

प्राधिकार.....


विनिधान.....

इसके पहले संदर्भित क्षेत्र-संविदा करार के अन्तर्गत ठेकेदार ..... को एतद्वारा निम्नलिखित निर्माण कार्य करने का आदेश दिया जाता है-

क्रम संख्या	क्षेत्र-संविदा करार के साथ नत्थी अनुसूची की मद सं० DSR- 2021	अनुमानित परिमाण	निर्माण मद विवरण	इकाई	क्षेत्र-संविदा करार के साथ नत्थी अनुसूची की दर रु० पै०	रकम रु० पै०
1	2	3	4	5	6	7
1	13.90.1	1760.00	Distempering with 1st quality acrylic distemper (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade : Old work (one or more coats)	Sqm.	56.80	99968.00
2	13.80	181.60	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqm.	123.85	22491.16
3	13.99.1	400.00	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	Sqm.	86.55	34620.00
4	13.109.1	1872.00	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 litres/10 sqm complete including cost of Priming coat.	Sqm.	94.15	176248.80
<b>Total=</b>						<b>333327.96</b>
<b>Gr. Total=</b>						<b>333327.96</b>

इसमें उल्लिखित निर्माण कार्य (दिनांक)---30.06.2027---को अथवा उसके पहले पूरे होने चाहिए। इसमें अनुमानित है और संविदा की सामान्य शर्तों की धारा 42 के अन्तर्गत इसमें घट और बढ़ सकती है।

दिनांक.....

  
सी. सी. इंजी. (कार्य)  
पीलीभीत

सहायक मण्डल इन्जी०  
पीलीभीत

वरि० मण्डल इंजीनियर (I) इज्जतनगर  
कृते भारत के राष्ट्रपति

यहाँ नत्थी रेखणों के अनुरूप पूर्वोक्तिलिखित क्षेत्र-संविदा सम्बन्धी सामान्य व विशेष शर्तों (यदि कोई हो) यथा विनिर्देशों के अनुसार यहाँ उल्लिखित निर्माण कार्यों के उपर्युक्त तिथि को अथवा उसके पूर्व करने का करार करता हूँ।

गवाह हस्ताक्षर .....

(ठेकेदार/ ठेकेदारों का हस्ताक्षर) .....

दिनांक .....

दिनांक.....



पूर्वोत्तर रेलवे  
क्षेत्र-संविदा के अन्तर्गत निर्माणआदेश

निर्माणआदेश संख्या - 01/PS/26-27/

दिनांक-.....


क्षेत्र संविदा करार सं०-IZN/DIV/ENG/NER-IZN-2026-ZONE 23/..... दिनांक-.....के

अन्तर्गत निर्माण का काम- Periodical painting works of NOH and SZN qtrs. (12 Nos. type-II)

प्राधिकार..... विनिर्धान.....  
इसके पहले संदर्भित क्षेत्र-संविदा करार के अन्तर्गत ठेकेदार ..... को एतद्वारा निम्नलिखित निर्माण कार्य करने का आदेश दिया जाता है-

क्रम संख्या	क्षेत्र-संविदा करार के साथ नत्थी अनुसूची की मद सं० DSR- 2021	अनुमानित परिमाण	निर्माण मद विवरण	इकाई	क्षेत्र-संविदा करार के साथ नत्थी अनुसूची की दर रु० पै०	रकम रु० पै०
1	2	3	4	5	6	7
1	13.90.1	2640.00	Distempering with 1st quality acrylic distemper (Ready mix) having VOC content less than 50 grams/ litre of approved brand and manufacture to give an even shade : Old work (one or more coats)	Sqm.	56.80	149952.00
2	13.80	272.40	Providing and applying white cement based putty of average thickness 1 mm, of approved brand and manufacturer, over the plastered wall surface to prepare the surface even and smooth complete.	Sqm.	123.85	33736.74
3	13.99.1	600.00	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	Sqm.	86.55	51930.00
4	13.109.1	2808.00	Finishing walls with water proofing cement paint of required shade : Old work (one or more coats applied @ 2.20 kg/10 sqm) over priming coat of primer applied @ 0.80 litres/10 sqm complete including cost of Priming coat.	Sqm.	94.15	264373.20
Total=						499991.94
Gr. Total=						499991.94

इसमें उल्लिखित निर्माण कार्य (दिनांक)-30.06.2027-को अथवा उसके पहले पूरे होने चाहिए। इसमें अनुमानित है और संविदा की सामान्य शर्तों की धारा 42 के अन्तर्गत इसमें घट और बढ सकती है।  
दिनांक.....

  
सी.से.ई.जी.(काय)  
पीलीभीत

सहायक मण्डल इंजीनियर  
पीलीभीत

वरिष्ठ मण्डल इंजीनियर (I) इज्जतनगर  
कृते भारत के राष्ट्रपति

यहाँ नत्थी रेखणों के अनुरूप पूर्वोक्तलिखित क्षेत्र-संविदा सम्बन्धी सामान्य व विशेष शर्तों (यदि कोई हो ) यथा विनिर्देशों के अनुसार यहाँ उल्लिखित निर्माण कार्यों के उपर्युक्त तिथि को अथवा उसके पूर्व करने का करार करता हूँ ।

गवाह हस्ताक्षर .....  
दिनांक .....

(ठेकेदार/ ठेकेदारों का हस्ताक्षर) .....  
दिनांक.....

**क्षेत्र-सविदा के अन्तर्गत निर्माणादेश**

निर्माणादेश संख्या - 01/PS/26-27/

दिनांक-.....

क्षेत्र सविदा करार सं०--IZN/DIV/ENG/NER-IZN-2026-ZONE 23/..... दिनांक-.....के

अन्तर्गत निर्माण का काम- Lettering of bridges tablet, HFL, DL, Span etc between PBE-SPN.

प्राधिकार-.....


विनिधान-.....

इसके पहले संदर्भित क्षेत्र-सविदा करार के अन्तर्गत ठेकेदार ..... को एतद्वारा निम्नलिखित निर्माण कार्य करने का आदेश दिया जाता है-

क्रम संख्या	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की मद सं० DSR- 2021	अनुमानित परिमाण	निर्माण मद विवरण	इकाई	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की दर रु० पै०	रकम रु० पै०
1	2	3	4	5	6	7
1	13.71	65400.00	Lettering with black Japan paint of approved brand and manufacture.	Sqm.	5.05	330270.00
2	13.99.1	104.63	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade : One or more coats on old work	Sqm.	63.25	6617.85
<b>Total=</b>						<b>336887.85</b>
<b>Gr. Total=</b>						<b>336887.85</b>

इसमें उल्लिखित निर्माण कार्य (दिनांक)--30.06.2027--को अथवा उसके पहले पूरे होने चाहिए। इसमें अनुमानित है और सविदा की सामान्य शर्तों की धारा 42 के अन्तर्गत इसमें घट और बढ़ सकती है।

दिनांक-.....

  
**म.स.इ.जी. (कार्य)**  
 पीलीभीत

सहायक मण्डल इंजीनी०  
 पीलीभीत

वरि० मण्डल इंजीनियर(१) इज्जतनगर  
 कृते भारत के राष्ट्रपति

यहाँ नत्थी रेखणों के अनुरूप पूर्वोक्त क्षेत्र-सविदा सम्बन्धी सामान्य व विशेष शर्तों (यदि कोई हो) यथा विनिर्देशों के अनुसार यहाँ उल्लिखित निर्माण कार्यों के उपर्युक्त तिथि को अथवा उसके पूर्व करने का करार करता हूँ।

गवाह हस्ताक्षर .....

दिनांक .....

(ठेकेदार/ठेकेदारों का हस्ताक्षर) .....

दिनांक.....



पूर्वोत्तर रेलवे  
क्षेत्र-सविदा के अन्तर्गत निर्माणादेश

निर्माणादेश संख्या - 01/PS/26-27/

दिनांक-.....

क्षेत्र सविदा करार सं०--IZN/DIV/ENG/NER-IZN-2026-ZONE 23/..... दिनांक-.....के


अन्तर्गत निर्माण का काम- One time jungle cleaning of Halts between PBE-SPN.

प्राधिकार----- विनिधान-----  
इसके पहले संदर्भित क्षेत्र-सविदा करार के अन्तर्गत ठेकेदार ..... को एतद्वारा निम्नलिखित निर्माण कार्य करने का आदेश दिया जाता है-

क्रम संख्या	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की मद सं० DSR- 2021	अनुमानित परिमाण	निर्माण मद विवरण	इकाई	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की दर रु० पै०	रकम रु० पै०
1	2	3	4	5	6	7
2	2.31	12000.00	Clearing jungle including uprooting of rank vegetation, grass, brush wood, trees and saplings of girth up to 30 cm measured at a height of 1 m above ground level and removal of rubbish up to a distance of 50 m outside the periphery of the area cleared.	Sqm.	14.50	174000.00
Total=						174000.00
Gr. Total=						174000.00

इसमें उल्लिखित निर्माण कार्य (दिनांक)---30.06.2027---को अथवा उसके पहले पूरे होने चाहिए। इसमें अनुमानित है और सविदा की सामान्य शर्तों की धारा 42 के अन्तर्गत इसमें घट और वढ सकती है।

दिनांक-----

  
सी.स.इंजी.(कार्य)  
पीलीभीत

सहायक मण्डल इंजी०  
पीलीभीत

वरि० मण्डल इंजीनियर(1) इज्जतनगर  
कृते भारत के राष्ट्रपति

यहाँ नत्थी रेखणों के अनुरूप पूर्वोल्लिखित क्षेत्र-सविदा सम्बन्धी सामान्य व विशेष शर्तों (यदि कोई हो ) यथा विनिर्देशों के अनुसार यहाँ उल्लिखित निर्माण कार्यों के उपर्युक्त तिथि को अथवा उसके पूर्व करने का करार करता हूँ ।

गवाह हस्ताक्षर -----

(ठेकेदार/ ठेकेदारों का हस्ताक्षर) -----

दिनांक -----

दिनांक-----

पूर्वोत्तर रेलवे  
क्षेत्र-सर्विदा के अन्तर्गत निर्माणदेश

निर्माणदेश संख्या - 01/PS/26-27/

दिनांक-.....


क्षेत्र-सर्विदा करार सं०--IZN/DIV/ENG/NER-IZN-2026-ZONE 23/..... दिनांक-.....के

अन्तर्गत निर्माण का काम- Improvement of sunken CC brackets of Low cost PP Shelter of Halts between PBE-SPN.

प्राधिकार-..... विनिर्धान-.....  
इसके पहले संदर्भित क्षेत्र-सर्विदा करार के अन्तर्गत ठेकेदार ..... को एतद्वारा निम्नलिखित निर्माण कार्य करने का आदेश दिया जाता है-

क्रम संख्या	क्षेत्र-सर्विदा करार के साथ नत्थी अनुसूची की मद सं० DSR- 2021	अनुमानित परिमाण	निर्माण मद विवरण	इकाई	क्षेत्र-सर्विदा करार के साथ नत्थी अनुसूची की दर रु० पै०	रकम रु० पै०
1	2	3	4	5	6	7
2	11.3.1	160.00	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) 40 mm thick with 20 mm nominal size stone aggregate.	Sqm.	545.00	87200.00
	2.25A	400.00	Excavating, supplying and filling of local earth (including royalty) by mechanical transport upto a lead of 5km also including ramming and watering of the earth in layers not exceeding 20 cm in trenches, plinth, sides of foundation etc. complete.	Cum.	368.65	147460.00
8	6.1.1	5.52	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum.	6882.00	37988.64
7	4.1.3	16.00	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources).	Cum.	7365.15	117842.40
13	15.2.1	25.00	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	Cum.	2007.10	50177.50
Total=						440668.54
Gr. Total=						440668.54

इसमें उल्लिखित निर्माण कार्य (दिनांक)---30.06.2027---को अथवा उसके पहले पूरे होने चाहिए। इसमें अनुमानित है और सर्विदा की सामान्य शर्तों की धारा 42 के अन्तर्गत इसमें घट और बढ़ सकती है।  
दिनांक-----

  
सी.से.ई.जी.(कार्य)  
पीलीभीत

सहायक मण्डल इंजी०  
पीलीभीत

वरि० मण्डल इंजीनियर(1) इज्जतनगर  
कृते भारत के राष्ट्रपति

यहाँ नत्थी रेखणों के अनुरूप पूर्वोत्तिखित क्षेत्र-सर्विदा सम्बन्धी सामान्य व विशेष शर्तों (यदि कोई हो) यथा विनिर्देशों के अनुसार

यहाँ उल्लिखित निर्माण कार्यों के उपर्युक्त तिथि को अथवा उसके पूर्व करने का करार करता हूँ।

(ठेकेदार/ ठेकेदारों का हस्ताक्षर)

दिनांक-----

गवाह हस्ताक्षर

दिनांक-----

पूर्वोत्तर रेलवे  
क्षेत्र -सविदा के अन्तर्गत निर्माणादेश

दिनांक-.....

निर्माणादेश संख्या - 01/PS/26-27/

क्षेत्र सविदा करार सं०--IZN/DIV/ENG/NER-IZN-2026-ZONE 23/..... दिनांक-.....के

अन्तर्गत निर्माण का काम- Repair of flooring, drain, tiles and plaster of BFPA+BSUR colony.

प्राधिकार..... विनिधान.....  
इसके पहले संदर्भित क्षेत्र-सविदा करार के अन्तर्गत ठेकेदार ..... को एतद्वारा निम्नलिखित निर्माण कार्य करने का आदेश दिया जाता है-


क्रम संख्या	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की मद सं० DSR- 2021	अनुमानित परिमाण	निर्माण मद विवरण	इकाई	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की दर रु० पै०	रकम रु० पै०
1	2	3	4	5	6	7
1	11.41.2	36.00	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm.	Sqm.	1416.65	50999.40
2	11.3.1	150.00	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) 40 mm thick with 20 mm nominal size stone aggregate.	Sqm.	545.00	81750.00
3	11.37	32.40	Providing and laying Ceramic glazed floor tiles of size 300x300 mm.	Sqm.	935.60	30313.44
4	11.46.2	7.20	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 600x600 mm	Sqm.	1466.50	10558.80



5	11.20.4	7.20	Chequerred precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand). Ordinary cement without any pigment.	Sqm.	928.50	6685.20
6	8.31	45.36	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	Sqm.	1063.45	48238.09
7	4.1.3	10.92	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources).	Cum.	7365.15	80427.44
8	6.1.1	5.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum.	6882.00	34410.00
9	6.4.2	2.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum.	8288.35	16576.70
10	13.4.2	290.00	12 mm cement plaster of mix 1:6 (1 cement: 6 coarse sand).	Sqm.	294.35	85361.50
11	14.80.1	4.00	Providing and fixing WC pan long pattern 580*440 mm.	Each	2962.80	11851.20
12	15.57	290.00	Dismantling old plaster.	Sqm.	45.05	13064.50

13	15.2.1	10.92	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	Cum.	2007.10	21917.53
14	15.23.1	128.16	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	Sqm.	60.50	7753.68
Total=						499907.48
Gr. Total=						499907.48

इसमें उल्लिखित निर्माण कार्य (दिनांक) 30.06.2027 को अथवा उसके पहले पूरे होने चाहिए। इसमें अनुमानित है और संविदा की सामान्य शर्तों की धारा 42 के अन्तर्गत इसमें घट और बढ़ सकती है।  
दिनांक \_\_\_\_\_

  
सी. से. इ. जी. (कार्य)  
पीलीभीत

सहायक मण्डल इंजीनियर  
पीलीभीत

वरिष्ठ मण्डल इंजीनियर (I) इज्जतनगर  
कृते भारत के राष्ट्रपति

यहाँ नत्थी रेखणों के अनुरूप पूर्वोक्तिलिखित क्षेत्र-संविदा सम्बन्धी सामान्य व विशेष शर्तों (यदि कोई हो) तथा विनिर्देशों के अनुसार

यहां उल्लिखित निर्माण कार्या के उपर्युक्त तिथि को अथवा उसके पूर्व करने का करार करता हूँ।

(ठेकेदार/ ठेकेदारों का हस्ताक्षर)

दिनांक \_\_\_\_\_

गवाह हस्ताक्षर

दिनांक \_\_\_\_\_

पूर्वोत्तर रेलवे  
क्षेत्र -सविदा के अन्तर्गत निर्माणादेश

निर्माणादेश संख्या - 01/PS/26-27/

दिनांक-.....

क्षेत्र सविदा करार सं०-IZN/DIV/ENG/NER-IZN-2026-ZONE 23/..... दिनांक-.....के

अन्तर्गत निर्माण का काम- Repair of flooring, drain, tiles and plaster of SZN+NOH colony (08 type-II).

प्राधिकार-.....

विनिधान-.....

इसके पहले संदर्भित क्षेत्र-सविदा करार के अन्तर्गत ठेकेदार ..... को एतद्वारा निम्नलिखित निर्माण कार्य करने का आदेश दिया जाता है-


क्रम संख्या	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की मद सं० DSR- 2021	अनुमानित परिमाण	निर्माण मद विवरण	इकाई	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की दर रु० पै०	रकम रु० पै०
1	2	3	4	5	6	7
1	11.41.2	24.00	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm.	Sqm.	1416.65	33999.60
2	11.3.1	128.00	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) 40 mm thick with 20 mm nominal size stone aggregate.	Sqm.	545.00	69760.00
3	11.37	21.60	Providing and laying Ceramic glazed floor tiles of size 300x300 mm.	Sqm.	935.60	20208.96
4	11.46.2	4.80	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 600x600 mm	Sqm.	1466.50	7039.20



5	11.20.4	4.80	Chequerred precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand). Ordinary cement without any pigment.	Sqm.	928.50	4456.80
6	8.31	30.24	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	Sqm.	1063.45	32158.73
7	4.1.3	8.68	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources).	Cum.	7365.15	63929.50
8	6.1.1	5.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in foundation and plinth in: Cement mortar 1:4 (1 cement : 4 coarse sand)	Cum.	6882.00	34410.00
9	6.4.2	2.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum.	8288.35	16576.70
10	13.4.2	300.00	12 mm cement plaster of mix 1:6 (1 cement: 6 coarse sand).	Sqm.	294.35	88305.00
11	14.80.1	4.00	Providing and fixing WC pan long pattern 580*440 mm.	Each	2962.80	11851.20
12	15.57	300.00	Dismantling old plaster.	Sqm.	45.05	13515.00

13	15.2.1	8.68	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	Cum.	2007.10	17421.63
14	15.23.1	85.44	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	Sqm.	60.50	5169.12
Total=						418801.44
Gr. Total=						418801.44

इसमें उल्लिखित निर्माण कार्य (दिनांक)—30.06.2027—को अथवा उसके पहले पूरे होने चाहिए। इसमें अनुमानित है और संविदा की सामान्य शर्तों की धारा 42 के अन्तर्गत इसमें घट और बढ़ सकती है।  
दिनांक \_\_\_\_\_

  
सी.से.इंजी.(कार्य)  
पीलीभीत

सहायक मण्डल इंजी०  
पीलीभीत

वरिष्ठ मण्डल इंजीनियर(1) इज्जतनगर  
कृते भारत के राष्ट्रपति

यहाँ नत्थी रेखणों के अनुरूप पूर्वोल्लिखित क्षेत्र-संविदा सम्वन्धी सामान्य व विशेष शर्तों (यदि कोई हो) यथा विनिर्देशों के अनुसार

यहां उल्लिखित निर्माण कार्या के उपर्युक्त तिथि को अथवा उसके पूर्व करने का करार करता हूँ ।

गवाह हस्ताक्षर \_\_\_\_\_  
दिनांक \_\_\_\_\_

(टेकेंदार/टेकेंदारों का हस्ताक्षर) \_\_\_\_\_  
दिनांक \_\_\_\_\_

पूर्वोत्तर रेलवे  
क्षेत्र -सविदा के अन्तर्गत निर्माणदेश

निर्माणदेश संख्या - 01/PS/26-27/

क्षेत्र सविदा करार सं०--IZN/DIV/ENG/NER-IZN-2026-ZONE 23/..... दिनांक-----के

अन्तर्गत निर्माण का काम- Roof repair by aluminium alloy sheeting of SPN Type-II Block.


प्राधिकार----- विनिधान-----  
इसके पहले संदर्भित क्षेत्र-सविदा करार के अन्तर्गत ठेकेदार ..... को एतद्वारा निम्नलिखित निर्माण कार्य करने का आदेश दिया जाता है-

क्रम संख्या	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की मद सं० DSR- 2021	अनुमानित परिमाण	निर्माण मद विवरण	इकाई	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की दर		रकम	
					रु०	पै०	रु०	पै०
1	2	3	4	5	6		7	
1	6.4.2	8.42	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum.	8288.35		69746.47	
2	4.3.1	54.72	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns	Sqm.	307.95		16851.02	
3	4.2.2	6.29	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:1½:3 (1 cement : 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	Cum.	9793.75		61602.69	
4	13.4.2	36.60	12 mm cement plaster of mix 1:6 (1 cement: 6 coarse sand).	Sqm.	294.35		10773.21	
5	15.7.4	1.00	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar.	Cum.	1698.45		1698.45	



6	13.44.1	36.60	Finishing walls with water proofing cement paint of required shade New work (Two or more coats applied @ 3.84 kg/10 sqm)	Sqm.	97.60	3572.16
7	12.65.1	120.00	Providing & fixing at all heights, levels and locations colour finish Aluminium alloy roofing sheets 0.56 mm, Aluminium Color coated troughed profile with center to center pitch of 200 mm, depth of 32 mm, overall profile width 1092 mm, cover width 1000mm.	Sqm.	1006.30	120756.00
8	12.66.1	30.00	Providing and fixing of Pre-coated colour or mill finish Aluminium Roofing Accessories in 0.71 mm thickness Precoated/mill finish aluminium Ridges plain (500- 600mm).	Metre	969.50	29085.00
9	10.16.3	1300.00	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Electric resistance or induction butt welded tubes.	Kg.	140.85	183105.00
Total=						497190.00
Gr. Total=						497190.00

इसमें उल्लिखित निर्माण कार्य (दिनांक) —30.06.2027—को अथवा उसके पहले पूरे होने चाहिए। इसमें अनुमानित है और संविदा की सामान्य शर्तों की धारा 42 के अन्तर्गत इसमें घट और बढ़ सकती है।  
दिनांक—

  
सी.से.इंजी. (कार्य)  
पीलीभीत

सहायक मण्डल इंजी०  
पीलीभीत

वरिष्ठ मण्डल इंजीनियर(1) इज्जतनगर  
कृते भारत के राष्ट्रपति

यहाँ नक्की रेखणों के अनुरूप पूर्वोक्तलिखित क्षेत्र—संविदा सम्बन्धी सामान्य व विशेष शर्तों (यदि कोई हो) यथा विनिर्देशों के अनुसार

यहां उल्लिखित निर्माण कार्यों के उपर्युक्त तिथि को अथवा उसके पूर्व करने का करार करता हूँ।

(देकेदार/देकेदारों का हस्ताक्षर)

दिनांक.....

गवाह हस्ताक्षर \_\_\_\_\_  
दिनांक \_\_\_\_\_

पूर्वोत्तर रेलवे  
क्षेत्र -सविदा के अन्तर्गत निर्माणदेश

निर्माणदेश संख्या - 01/PS/26-27/

क्षेत्र सविदा करार सं-IZN/DIV/ENG/NER-IZN-2026-ZONE 23/..... दिनांक-.....के


अन्तर्गत निर्माण का काम- Roof repair by aluminium alloy sheeting of BSUR Type-I Block.

प्राधिकार-..... विनिर्धान-.....  
इसके पहले संदर्भित क्षेत्र-सविदा करार के अन्तर्गत ठेकेदार ..... को एतद्वारा निम्नलिखित निर्माण कार्य करने का आदेश दिया जाता है-

क्रम संख्या	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की मद सं० DSR- 2021	अनुमानित परिमाण	निर्माण मद विवरण	इकाई	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की दर रु० पै०	रकम रु० पै०
1	2	3	4	5	6	7
1	6.4.2	8.42	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum.	8288.35	69746.47
2	4.3.1	54.72	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns	Sqm.	307.95	16851.02
3	4.2.2	6.29	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:1½:3 (1 cement : 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	Cum.	9793.75	61602.69
4	13.4.2	36.60	12 mm cement plaster of mix 1:6 (1 cement: 6 coarse sand).	Sqm.	294.35	10773.21
5	15.7.4	1.00	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar.	Cum.	1698.45	1698.45

6	13.44.1	36.60	Finishing walls with water proofing cement paint of required shade New work (Two or more coats applied @ 3.84 kg/10 sqm)	Sqm.	97.60	3572.16
7	12.65.1	120.00	Providing & fixing at all heights, levels and locations colour finish Aluminium alloy roofing sheets 0.56 mm, Aluminium Color coated troughed profile with center to center pitch of 200 mm, depth of 32 mm, overall profile width 1092 mm, cover width 1000mm.	Sqm.	1006.30	120756.00
8	12.66.1	30.00	Providing and fixing of Pre-coated colour or mill finish Aluminium Roofing Accessories in 0.71 mm thickness Precoated/mill finish aluminium Ridges plain (500- 600mm).	Metre	969.50	29085.00
9	10.16.3	1300.00	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Electric resistance or induction butt welded tubes.	Kg.	140.85	183105.00
Total=						497190.00
Gr. Total=						497190.00

इसमें उल्लिखित निर्माण कार्य (दिनांक) — 30.06.2027 — को अथवा उसके पहले पूरे होने चाहिए। इसमें अनुमानित है और संविदा की सामान्य शर्तों की धारा 42 के अन्तर्गत इसमें घट और बढ सकती है।  
दिनांक \_\_\_\_\_

  
सी. से. इंजी. (कार्य)  
पीलीभीत

सहायक मण्डल इंजी०  
पीलीभीत

वरिष्ठ मण्डल इंजीनियर (I) इज्जतनगर  
कृते भारत के राष्ट्रपति

यहाँ नक्शे रेखणों के अनुरूप पूर्वोक्तलिखित क्षेत्र—संविदा सम्बन्धी सामान्य व विशेष शर्तों (यदि कोई हो) यथा विनिर्देशों के अनुसार

यहां उल्लिखित निर्माण कार्या के उपर्युक्त तिथि को अथवा उसके पूर्व करने का करार करता हूँ।

गवाह हस्ताक्षर \_\_\_\_\_  
दिनांक \_\_\_\_\_

(टेकेदार/टेकेदारों का हस्ताक्षर) \_\_\_\_\_  
दिनांक \_\_\_\_\_



पूर्वोत्तर रेलवे  
क्षेत्र-सविदा के अन्तर्गत निर्माणादेश

दिनांक-.....

निर्माणादेश संख्या - 01/PS/26-27/

क्षेत्र सविदा करार सं०--IZN/DIV/ENG/NER-IZN-2026-ZONE 23/..... दिनांक-.....के


अन्तर्गत निर्माण का काम- Roof repair by aluminium alloy sheeting of SPN Running room.

प्राधिकार-..... विनिर्धान-.....  
इसके पहले संदर्भित क्षेत्र-सविदा करार के अन्तर्गत ठेकेदार ..... को एतद्वारा निम्नलिखित निर्माण कार्य करने का आदेश दिया जाता है-

क्रम संख्या	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की मद सं० DSR- 2021	अनुमानित परिमाण	निर्माण मद विवरण	इकाई	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की दर रु० पै०	रकम रु० पै०
1	2	3	4	5	6	7
1	6.4.2	8.42	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum.	8288.35	69746.47
2	4.3.1	54.72	Centering and shuttering including strutting, propping etc. and removal of form work for : Foundations, footings, bases for columns	Sqm.	307.95	16851.02
3	4.2.2	6.29	Providing and laying cement concrete in retaining walls, return walls, walls (any thickness) including attached pilasters, columns, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window sills, fillets, sunken floor etc., up to floor five level, excluding the cost of centering, shuttering and finishing: 1:1½:3 (1 cement : 1½ coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	Cum.	9793.75	61602.69
4	13.4.2	36.60	12 mm cement plaster of mix 1:6 (1 cement: 6 coarse sand).	Sqm.	294.35	10773.21
5	15.7.4	1.00	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar.	Cum.	1698.45	1698.45

6	13.44.1	36.60	Finishing walls with water proofing cement paint of required shade New work (Two or more coats applied @ 3.84 kg/10 sqm)	Sqm.	97.60	3572.16
7	12.65.1	120.00	Providing & fixing at all heights, levels and locations colour finish Aluminium alloy roofing sheets 0.56 mm, Aluminium Color coated troughed profile with center to center pitch of 200 mm, depth of 32 mm, overall profile width 1092 mm, cover width 1000mm.	Sqm.	1006.30	120756.00
8	12.66.1	30.00	Providing and fixing of Pre-coated colour or mill finish Aluminium Roofing Accessories in 0.71 mm thickness Precoated/mill finish aluminium Ridges plain (500- 600mm).	Metre	969.50	29085.00
9	10.16.3	1300.00	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. Electric resistance or induction butt welded tubes.	Kg.	140.85	183105.00
Total=						497190.00
Gr. Total=						497190.00

इसमें उल्लिखित निर्माण कार्य (दिनांक) — 30.06.2027 — को अथवा उसके पहले पूरे होने चाहिए। इसमें अनुमानित है और संविदा की सामान्य शर्तों की धारा 42 के अन्तर्गत इसमें घट और बढ़ सकती है।  
दिनांक —

  
सी.से.इंजी. (कार्य)  
पीलीभीत

सहायक मण्डल इंजीनियर  
पीलीभीत

वरिष्ठ मण्डल इंजीनियर (I) इज्जतनगर  
कृते भारत के राष्ट्रपति

यहाँ नथी रेखणों के अनुरूप पूर्वोक्तलिखित क्षेत्र—संविदा सम्बन्धी सामान्य व विशेष शर्तों (यदि कोई हो) यथा दिनिदर्शों के अनुसार

यहां उल्लिखित निर्माण कार्यों के उपर्युक्त तिथि को अथवा उसके पूर्व करने का करार करता हूँ।

गवाह हस्ताक्षर

(टेकदार/टेकदारों का हस्ताक्षर)

दिनांक

दिनांक

पूर्वोत्तर रेलवे  
क्षेत्र -सविदा के अन्तर्गत निर्माणादेश

दिनांक-.....

दिनांक-.....के

निर्माणादेश संख्या - 01/PS/26-27/

क्षेत्र सविदा करार सं०--IZN/DIV/ENG/NER-IZN-2026-ZONE 23/.....

अन्तर्गत निर्माण का काम- Misc. repair work of RWP, Water hydrants, flooring, doors, RCC benches, roof parapets and water cooler stand of stations between Pilibhit-Shahjahanpur.

प्राधिकार..... विनिर्धान.....  
इसके पहले संदर्भित क्षेत्र-सविदा करार के अन्तर्गत ठेकेदार ..... को एतद्वारा निम्नलिखित निर्माण कार्य करने का आदेश दिया जाता है-


क्रम संख्या	क्षेत्र-सविदा करार के साथ नक्शे अनुसूची की मद सं० DSR- 2021	अनुमानित परिमाण	निर्माण मद विवरण	इकाई	क्षेत्र-सविदा करार के साथ नक्शे अनुसूची की दर रु० पै०	रकम रु० पै०
1	2	3	4	5	6	7
1	11.3.1	50.00	Cement concrete flooring 1:2:4 (1 cement : 2 coarse sand : 4 graded stone aggregate) 40 mm thick with 20 mm nominal size stone aggregate.	Sqm.	545.00	27250.00
2	9.21.1	10.00	Providing and fixing ISI marked flush door shutters 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws.	Sqm	2015.75	20157.50
3	9.63.1	5.00	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete : (copper oxidized as per IS: 1378) 250x10 mm.	Each	74.65	373.25
4	9.62.1	10.00	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete : (copper oxidized as per IS: 1378) 300x16 mm	Each	180.55	1805.50
5	6.4.2	5.00	Brick work with common burnt clay F.P.S. (non modular) bricks of class designation 7.5 in superstructure above plinth level up to floor V level in all shapes and sizes in : Cement mortar 1:6 (1 cement : 6 coarse sand)	Cum.	8288.35	41441.75
6	13.4.2	210.00	12 mm cement plaster of mix 1:6 (1 cement: 6 coarse sand).	Sqm.	294.35	61813.50
7	15.2.1	3.20	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	Cum.	2007.10	6422.72
8	15.7.4	1.00	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge. In cement mortar.	Cum.	1698.45	1698.45



9	15.3	1.00	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in-charge.	Cum.	2928.10	2928.10
10	4.1.3	4.60	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level : 1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources).	Cum.	7365.15	33879.69
11	8.31	120.00	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	Sqm.	1063.45	127614.00
12	9.128	5.50	Providing and fixing factory made Fiberglass Reinforced plastics (F.R.P.) chajja 4 mm thick of required colour.	Sqm.	4901.50	26958.25
13	10.25.2	340.00	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required. In gratings, frames, guard bar, ladder, railings, brackets, gates and similar works	Kg.	142.30	48382.00
14	12.41.2	40.00	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming 110 mm diameter.	Mtr.	319.75	12790.00
15	12.42.5.2	20.00	Providing and fixing on wall face unplasticised - PVC moulded fittings/ accessories for unplasticised Rigid PVC rain water pipes Bend 87.5° 110 mm bend.	Each	132.00	2640.00

16	NS Item	10.00	Supplying, erecting and fixing precast concrete reinforced bench with back rest. Bench shall consist of 2 nos. L shaped base support in natural cement colour of thickness 100 mm, back height 1000 mm, front height 450 mm, base width 620 mm and 5 nos. reinforced concrete planks in red colour and size of 1500 x 100 x 50mm and 1 no. reinforced concrete plank of 150 x 200 x 50mm; manufactured by using M-30 grade concrete & reinforced suitably; all parts to be joined with galvanised nuts and bolts of suitable size. All bolts to be sealed after assembly. Complete job to be done as per directions of Engineer Incharge	Each	8289.28	82892.80
Total=						499047.51
Gr. Total=						499047.51

इसमें उल्लिखित निर्माण कार्य (दिनांक) — 30.06.2027 — को अथवा उसके पहले पूरे होने चाहिए। इसमें अनुमानित है और संविदा की सामान्य शर्तों की धारा 42 के अन्तर्गत इसमें घट और बढ़ सकती है।  
दिनांक \_\_\_\_\_

  
सी.से.इंजी.(कार्य)  
पीलीभीत

सहायक मण्डल इंजी०  
पीलीभीत

वरि० मण्डल इंजीनियर(१) इज्जतनगर  
कृते भारत के राष्ट्रपति

यहाँ नक्की रेखणों के अनुरूप पूर्वोत्लिखित क्षेत्र—संविदा सम्बन्धी सामान्य व विशेष शर्तों (यदि कोई हो ) यथा विनिर्देशों के अनुसार यहाँ उल्लिखित निर्माण कार्यों के उपर्युक्त तिथि को अथवा उसके पूर्व करने का करार करता हूँ ।

गयाह हस्ताक्षर \_\_\_\_\_  
दिनांक \_\_\_\_\_

(टेकेदार/ टेकेदारों का हस्ताक्षर) \_\_\_\_\_  
दिनांक.....

पूर्वोत्तर रेलवे  
क्षेत्र -सविदा के अन्तर्गत निर्माणदेश

निर्माणदेश संख्या - 01/PS/26-27/

दिनांक-----

क्षेत्र सविदा करार सं०--IZN/DIV/ENG/NER-IZN-2026-ZONE 23/..... दिनांक-----के

अन्तर्गत निर्माण का काम- Service buildings tile and granite repair works at BFPA, BSUR, NOH, BNSA and SZN.

प्राधिकार----- विनिधान-----  
इसके पहले संदर्भित क्षेत्र-सविदा करार के अन्तर्गत ठेकेदार ..... को एतद्वारा निम्नलिखित निर्माण कार्य करने का आदेश दिया जाता है-

क्रम संख्या	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की मद सं० DSR- 2021	अनुमानित परिमाण	निर्माण मद विवरण	इकाई	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की दर रु० पै०	रकम रु० पै०
1	2	3	4	5	6	7
1	11.41.2	83.00	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete. Size of Tile 600x600 mm.	Sqm.	1416.65	117581.95
2	11.37	42.00	Providing and laying Ceramic glazed floor tiles of size 300x300 mm.	Sqm.	935.60	39295.20
3	11.46.2	85.00	Providing and laying Vitrified tiles in different sizes (thickness to be specified by manufacturer), with water absorption less than 0.08 % and conforming to I.S. 15622, of approved make, in all colours & shade, in skirting, riser of steps, over 12 mm thick bed of cement mortar 1:3 (1 cement: 3 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joint with white cement & matching pigments etc. complete. Size of Tile 600x600 mm	Sqm.	1466.50	124652.50




4	11.20.4	20.00	Chequered precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand). Ordinary cement without any pigment.	Sqm.	928.50	18570.00
5	11.56.1	10.00	Providing and laying Polished Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge. Polished Granite stone slab colour of Black, Cherry/Ruby Red or equivalent	Sqm.	3908.80	39088.00
6	8.31	90.00	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	Sqm.	1063.45	95710.50

7	8.2.2.2	10.00	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing of edges to give high gloss finish etc. complete at all levels. Granite stone slab of colour black, Cherry/Ruby red. Area of slab over 0.50 sqm.	Sqm.	4425.35	44253.50
8	15.25	20.00	Dismantling stone slab flooring laid in cement mortar including stacking of serviceable material and disposal of unserviceable material within 50 metres lead.	Sqm.	219.75	4395.00
9	15.2.1	2.10	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge. Nominal concrete 1:3:6 or richer mix (i/c equivalent design mix)	Cum.	2007.10	4214.91
10	15.23.1	193.20	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead. For thickness of tiles 10 mm to 25 mm	Sqm.	60.50	11688.60
Total=						499450.16
Gr. Total=						499450.16

इसमें उल्लिखित निर्माण कार्य (दिनांक)—30.06.2027—को अथवा उसके पहले पूरे होने चाहिए। इसमें अनुमानित है और सविदा की सामान्य शर्तों की धारा 42 के अन्तर्गत इसमें घट और बढ़ सकती है।

दिनांक—

  
सी.से.इजी.(कार्य)  
पीलीभीत

सहायक मण्डल इंजीनियर  
पीलीभीत

वरिष्ठ मण्डल इंजीनियर(I) इज्जतनगर  
कृते भारत के राष्ट्रपति

यहाँ नत्थी रेखणों के अनुरूप पूर्वोल्लिखित क्षेत्र-सविदा सम्बन्धी सामान्य व विशेष शर्तों (यदि कोई हो) यथा विनिर्देशों के अनुसार यहाँ उल्लिखित निर्माण कार्यों के उपर्युक्त तिथि को अथवा उसके पूर्व करने का करार करता हूँ।

गवाह हस्ताक्षर \_\_\_\_\_

(टेकदार/टेकदारों का हस्ताक्षर) \_\_\_\_\_

दिनांक \_\_\_\_\_

दिनांक \_\_\_\_\_

पूर्वोत्तर रेलवे

क्षेत्र -संविदा के अन्तर्गत निर्माणदेश

निर्माणदश संख्या - 01/PS/26-27/

दिनांक-.....


क्षेत्र संविदा करार सं०--IZN/DIV/ENG/NER-IZN-2026-ZONE 23/..... दिनांक-.....के

अन्तर्गत निर्माण का काम- Providing back verandah grill mesh for protection from monkeys in quarters at LC's.

प्राधिकार..... विनिधान.....  
इसके पहले संदर्भित क्षेत्र-संविदा करार के अन्तर्गत ठेकेदार ..... को एतद्वारा निम्नलिखित निर्माण कार्य करने का आदेश दिया जाता है-

क्रम संख्या	क्षेत्र-संविदा करार के साथ नत्थी अनुसूची की मद सं० DSR-2021	अनुमानित परिमाण	निर्माण मद विवरण	इकाई	क्षेत्र-संविदा करार के साथ नत्थी अनुसूची की दर रु० पै०	रकम रु० पै०
1	2	3	4	5	6	7
1	10.25.2	980.00	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar work.	Kg	142.30	139454.00
Total=						139454.00
Gr. Total=						139454.00

इसमें उल्लिखित निर्माण कार्य (दिनांक)--30.06.2027--को अथवा उसके पहले पूरे होने चाहिए। इसमें अनुमानित है और संविदा की सामान्य शर्तों की धारा 42 के अन्तर्गत इसमें घट और बढ़ सकती है।  
दिनांक-----

  
सा.से.इ.जी. (कार्य)  
पीलीभीत

सहायक मण्डल इंजीनियर  
पीलीभीत

वरिष्ठ मण्डल इंजीनियर(I) इज्जतनगर  
कूते भारत के राष्ट्रपति

यहां नत्थी रेखणों के अनुरूप पूर्वोत्तर रेलवे क्षेत्र-संविदा सम्बन्धी सामान्य व विशेष शर्तों (यदि कोई हो) यथा विनिर्देशों के अनुसार यहां उल्लिखित निर्माण कार्यों के उपर्युक्त तिथि को अथवा उसके पूर्ण करने का करार करता हूँ।

गवाह हस्ताक्षर .....  
दिनांक .....

(ठेकेदार/ठेकेदारों का हस्ताक्षर) .....  
दिनांक.....



पूर्वोत्तर रेलवे

क्षेत्र-सविदा के अन्तर्गत निर्माणादेश

दिनांक-.....

निर्माणादेश संख्या - 01/PS/26-27/

क्षेत्र सविदा करार सं०--IZN/DIV/ENG/NER-IZN-2026-ZONE 23/..... दिनांक-.....के

अन्तर्गत निर्माण का काम- Repair of doors, windows of BFPA, BSUR, NOH and SZN colony.


प्राधिकार..... विनिर्धान.....  
इसके पहले संदर्भित क्षेत्र-सविदा करार के अन्तर्गत ठेकेदार ..... को एतद्वारा निम्नलिखित निर्माण कार्य करने का आदेश दिया जाता है-

क्रम संख्या	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की मद सं० DSR-2021	अनुमानित परिमाण	निर्माण मद विवरण	इकाई	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की दर रु० पै०	रकम रु० पै०
1	2	3	4	5	6	7
1	9.120.1	7.00	Providing and fixing factory made panel PVC door shutter consisting of frame made of 30 mm thick plain PVC door shutters.	Sqm	2455.10	17185.70
2	9.119	23.50	Providing and fixing factory made P.V.C. door frame of size 50x47 mm with awall thickness of 5 mm, made out of extruded 5mm rigid PVC foam sheet, mitred at corners and joined with 2 Nos of 150 mm long brackets of 15x15 mm M.S. square tube, the vertical door frame profiles to be reinforced with 19x19 mm M.S. square tube of 19 gauge, EPDM rubber gasket weather seal to be provided through out the frame. The door frame to be fixed to the wall using M.S. screws of 65/100 mm size, complete as per manufacturer's specification and direction of Engineer in-Charge.	Sqm	408.25	9593.88
3	9.55.3	15.00	Providing and fixing ISI marked IS : 1341 M.S. pressed butt hinges bright finished with necessary screws etc. complete 75x47x1.70mm.	Each	32.75	491.25
4	9.51.1	21.60	Providing and fixing fly proof galvanized M.S. wire gauge to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm all complete. With second class teak wood beading 62X19 mm.	Sqm	1164.90	25161.84
5	10.25.2	280.00	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar work.	Kg	142.30	39844.00

6	10.15.1	200.00	Providing and fixing M.S. Tubular frames for doors, windows, ventilators and cupboard with rectangular/ L-Type sections, made of 1.60 mm thick M.S. Sheet, joints mitred, welded and grinded finish, with profiles of required size, including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer. Fixing with 15x3 mm lugs 10 cm long embedded in cement concrete block 15x10x10 cm of C.C. 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	Kg	146.55	29310.00
7	9.27.1.1.1	10.80	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws : 35 mm thick shutters with ISI marked M.S. pressed butt hinges bright finished of required size Second class teak wood.	Sqm	4342.30	46896.84
8	9.48.1	150.00	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to steel windows by welding.	Kg	181.00	27150.00
9	14.85	10.00	Taking out existing wooden door shutter, repair by cutting, painting etc. and refixing of repaired door shutters to existing door frames, including replacement of hinges with screws, etc. as required, all complete as per the direction of the Engineer-in-charge.	Each	325.95	3259.50
10	15.13.1	20.00	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead Of area 3 sq. metres and below.	Each	118.30	2366.00
11	9.21.1	20.00	Providing and fixing ISI marked flush door shutters 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws.	Sqm	2015.75	40315.00
12	9.9.1.1	10.80	Providing and fixing glazed shutters for doors, windows and clerestory windows using 4 mm thick float glass panes, (weight not less than 10 kg per sqm) fixing with ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws. Second class teak wood, 35 mm thick.	Sqm	4458.40	48150.72
13	9.66.1	60.00	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete : (copper oxidized as per IS: 1378) 125 mm	Each	35.20	2112.00

14	9.100.1	10.00	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 125 mm	Each	60.05	600.50
15	9.97.2	10.00	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 250x10 mm	Each	104.40	1044.00
16	9.63.3	80.00	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete : (copper oxidized as per IS: 1378) 150x10 mm	Each	53.05	4244.00
17	9.63.1	10.00	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete : (copper oxidized as per IS: 1378) 250x10 mm.	Each	74.65	746.50
18	9.62.1	20.00	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete : (copper oxidized as per IS: 1378) 300x16 mm	Each	180.55	3611.00
Total=						302082.73
Gr. Total=						302082.73

इसमें उल्लिखित निर्माण कार्य (दिनांक)---30.06.2027---को अथवा उसके पहले पूरे होने चाहिए। इसमें अनुमानित है और संविदा की सामान्य शर्तों की धारा 42 के अन्तर्गत इसमें घट और बढ़ सकती है।  
दिनांक-----

  
सी.से.इंजी.(कार्य)  
पीलीभीत

सहायक मण्डल इंजी०  
पीलीभीत

वरि० मण्डल इंजीनियर(1) इज्जतनगर  
कृते भारत के राष्ट्रपति

यहाँ नत्थी रेखणों के अनुरूप पूर्वोल्लिखित क्षेत्र-संविदा सम्बन्धी सामान्य व विशेष शर्तों (यदि कोई हो) यथा विनिर्देशों के अनुसार यहां उल्लिखित निर्माण कार्या के उपर्युक्त तिथि को अथवा उसके पूर्व करने का करार करता हूँ।

गवाह हस्ताक्षर -----  
दिनांक -----

(टेकंदार/टेकंदारों का हस्ताक्षर) -----  
दिनांक-----



पूर्वोत्तर रेलवे

क्षेत्र -सविदा के अन्तर्गत निर्माणादेश

निर्माणादेश संख्या - 01/PS/26-27/

दिनांक-.....

क्षेत्र सविदा करार सं०--IZN/DIV/ENG/NER-IZN-2026-ZONE 23/..... दिनांक-.....के

अन्तर्गत निर्माण का काम- Repair of doors, windows of SPN railway colony.

प्राधिकार-----

विनिधान-----


इसके पहले संदर्भित क्षेत्र-सविदा करार के अन्तर्गत ठेकेदार ..... को एतद्वारा निम्नलिखित निर्माण कार्य करने का आदेश दिया जाता है--

क्रम संख्या	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की मद सं० DSR-2021	अनुमानित परिमाण	निर्माण मद विवरण	इकाई	क्षेत्र-सविदा करार के साथ नत्थी अनुसूची की दर रु० पै०	रकम रु० पै०
1	2	3	4	5	6	7
1	9.120.1	7.00	Providing and fixing factory made panel PVC door shutter consisting of frame made of 30 mm thick plain PVC door shutters.	Sqm	2455.10	17185.70
2	9.119	23.50	Providing and fixing factory made P.V.C. door frame of size 50x47 mm with awall thickness of 5 mm, made out of extruded 5mm rigid PVC foam sheet, mitred at corners and joined with 2 Nos of 150 mm long brackets of 15x15 mm M.S. square tube, the vertical door frame profiles to be reinforced with 19x19 mm M.S. square tube of 19 gauge, EPDM rubber gasket weather seal to be provided through out the frame. The door frame to be fixed to the wall using M.S. screws of 65/100 mm size, complete as per manufacturer's specification and direction of Engineer in-Charge.	Sqm	408.25	9593.88
3	9.55.3	15.00	Providing and fixing ISI marked IS : 1341 M.S. pressed butt hinges bright finished with necessary screws etc. complete 75x47x1.70mm.	Each	32.75	491.25
4	9.51.1	21.60	Providing and fixing fly proof galvanized M.S. wire gauge to windows and clerestory windows using wire gauge with average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm all complete. With second class teak wood beading 62X19 mm.	Sqm	1164.90	25161.84
5	10.25.2	560.00	Steel work welded in built up sections/ framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer using structural steel etc. as required In gratings, frames, guard bar, ladder, railings, brackets, gates and similar work.	Kg	142.30	79688.00

6	10.15.1	200.00	Providing and fixing M.S. Tubular frames for doors, windows, ventilators and cupboard with rectangular/ L-Type sections, made of 1.60 mm thick M.S. Sheet, joints mitred, welded and grinded finish, with profiles of required size, including fixing of necessary butt hinges and screws and applying a priming coat of approved steel primer. Fixing with 15x3 mm lugs 10 cm long embedded in cement concrete block 15x10x10 cm of C.C. 1:3:6 (1 Cement : 3 coarse sand : 6 graded stone aggregate 20 mm nominal size)	Kg	146.55	29310.00
7	9.27.1.1.1	10.80	Providing and fixing wire gauge shutters using galvanized M.S. wire gauge of average width of aperture 1.4 mm in both directions with wire of dia 0.63 mm, for doors, windows and clerestory windows with hinges and necessary screws : 35 mm thick shutters with ISI marked M.S. pressed butt hinges bright finished of required size Second class teak wood.	Sqm	4342.30	46896.84
8	9.48.1	150.00	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete. Fixed to steel windows by welding.	Kg	181.00	27150.00
9	14.85	10.00	Taking out existing wooden door shutter, repair by cutting, painting etc. and refixing of repaired door shutters to existing door frames, including replacement of hinges with screws, etc. as required, all complete as per the direction of the Engineer-in-charge.	Each	325.95	3259.50
10	15.13.1	20.00	Taking out doors, windows and clerestory window shutters (steel or wood) including stacking within 50 metres lead Of area 3 sq. metres and below.	Each	118.30	2366.00
11	9.21.1	20.00	Providing and fixing ISI marked flush door shutters 35 mm thick including ISI marked Stainless Steel butt hinges with necessary screws.	Sqm	2015.75	40315.00
12	9.9.1.1	10.80	Providing and fixing glazed shutters for doors, windows and clerestory windows using 4 mm thick float glass panes, (weight not less than 10 kg per sqm) fixing with ISI marked M.S. pressed butt hinges bright finished of required size with necessary screws. Second class teak wood, 35 mm thick.	Sqm	4458.40	48150.72
13	9.66.1	60.00	Providing and fixing ISI marked oxidised M.S. handles conforming to IS:4992 with necessary screws etc. complete : (copper oxidized as per IS: 1378) 125 mm	Each	35.20	2112.00

14	9.100.1	10.00	Providing and fixing aluminium handles, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868) transparent or dyed to required colour or shade, with necessary screws etc. complete : 125 mm	Each	60.05	600.50
15	9.97.2	10.00	Providing and fixing aluminium tower bolts, ISI marked, anodised (anodic coating not less than grade AC 10 as per IS : 1868 ) transparent or dyed to required colour or shade, with necessary screws etc. complete : 250x10 mm	Each	104.40	1044.00
16	9.63.3	80.00	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete : (copper oxidized as per IS: 1378) 150x10 mm	Each	53.05	4244.00
17	9.63.1	10.00	Providing and fixing ISI marked oxidised M.S. tower bolt black finish, (Barrel type) with necessary screws etc. complete : (copper oxidized as per IS: 1378) 250x10 mm.	Each	74.65	746.50
18	9.62.1	20.00	Providing and fixing ISI marked oxidised M.S. sliding door bolts with nuts and screws etc. complete : (copper oxidized as per IS: 1378) 300x16 mm	Each	180.55	3611.00
<b>Total=</b>						<b>341926.73</b>
<b>Gr. Total=</b>						<b>341926.73</b>

इसमें उल्लिखित निर्माण कार्य (दिनांक)—30.08.2027—को अथवा उसके पहले पूरे होने चाहिए। इसमें अनुमानित है और संविदा की सामान्य शर्तों की धारा 42 के अन्तर्गत इसमें घट और बढ सकती है।  
दिनांक—

  
सी.से.इंजी.(कार्य)  
पीलीभीत

सहायक मण्डल इंजी०  
पीलीभीत

वरि० मण्डल इंजीनियर(१) इज्जतनगर  
क्षेत्र भारत के राष्ट्रपति

यहाँ नक्की रेखाओं के अनुरूप पूर्वोक्तलिखित क्षेत्र—संविदा सम्बन्धी सामान्य व विशेष शर्तों (यदि कोई हो ) यथा विनिर्देशों के अनुसार यहाँ उल्लिखित निर्माण कार्यों के उपर्युक्त तिथि को अथवा उसके पूर्व करने का करार करता हूँ ।

गयाह हस्ताक्षर \_\_\_\_\_  
दिनांक \_\_\_\_\_

(टेकेंदार/टेकेंदारों का हस्ताक्षर) \_\_\_\_\_  
दिनांक.....