

Contractor has to deploy atleast one set of machines/gantry etc. for PQRS working within 21 days of issuance of LOA. However, he may be instructed by Rly administration in writing to provide 1 more set of machines/ gantry etc. for opening simultaneous 2 different sites of PQRS working. He should provide sets of machines/gantry etc. for PQRS working within 21 days of intimation in writing. For locations having availability of sleepers at site or due to unavailability of BRNs for PQRS working or as per decision of DEN/Sr. DEN, manual CTR may be done at site which will be governed and paid as per Part A of the tender schedule in place of NS item of Part B or vice-versa. Contractor shall not be entitled for any claim on this account. Contractor should reconfirm with all the stipulations laid for NS item 1 under Annexure A (final product of part B) before submitting their offer. Submission of offer by the contractor shall be deemed as a consent to all the laid therein for NS-item 1. TSR (P) or CTR (P) work will be paid under same item NS 1 only. Contractor shall not have any claim whatsoever in case of increase/decrease of TSR/CTR items as per railway requirements.

Total B

81543248.37



DRM (W) JBP

CONTRACTOR

47

## SPECIAL CONDITIONS OF CONTRACT

Name of Work: CTR 33.109 Km and TSR 33.396 Km (Total 66.505 Kms) by contractors PQRS Machine and manually at obligatory points on STA-REWA and KTE-MKP section and TRR 16.75Kms, TFR 5.00Km and TFR-(R-only rubber pad)-30.014 Km on STA-REWA and KTE-MKP section under Sr. DEN (N) Jurisdiction.

### 1: PQRS DEPOT:

Work consists of CTR (P)/TSR (P) of about 66.505 Km by contractor's PQRS. Before starting the CTR/TSR work, contractor will have to prepare PQRS Depot (minimum 3 No.), in which contractor may have to lay two number of Track of the standard as per IRPWM of about 250m to 1000m in each PQRS Depot. Contractor will have to lay auxiliary Track as well. PQRS Depots will be at Patwara, Kaima, Hinauta Ramban yard or any other place as found suitable (as per operational suitability and/or proximity of location of Work from depot Contractor will have to do work as per direction of engineer In-charge as per typical layout plan of base depot given in Para 407 of Indian Railway Track Machine Manual with all earth work (Railway/Contractor's Earth), Railway ballast and other associated works as required. SH rails, sleepers, fittings, Ballast etc. will be provided by Railway at some suitable location which will have to be loaded at source, transported and unloaded by the Contractor at his/her own cost.

### 2: WORKLOCATIONDETAILS

- (i) Tenderers or their representative should visit the site of work (PQRS Depot/running track) with or without the concerned SSE (P. Way) / ADEN, to ascertain the nature of work, site conditions, availability of approach roads, availability of labours, water, electricity, land etc. for making various arrangements for execution of work to arrive at reasonable cost required to be offered for bidding purpose.
- (ii) Locations of work: Work is to be done between Katni-Manikpur and Satna-Rewa Section of Jabalpur Division. However railway administration may add/delete worksites anywhere in Jabalpur Division. Contractor shall have no claims on this account.

### 3: GENERAL:

Unless otherwise, specified the West Central Railway General Conditions of Contract for material and works as amended and or corrected from time to time and obtaining at the time of acceptance of the Tender and at the time of execution of the agreement shall be binding on the tenderer/contractor. In the event of any conflict or contradiction between the provisions of the conditions of the said General Conditions of Contract and the Special Conditions, the Special Conditions shall prevail and the decision of Engineer In-Charge in this connection shall be final and binding on the contractor.

### 4: TECHNICAL SUPERVISION & SAFETY AT WORK SITE:

- (i) The tenderer/contractor shall employ adequate number of authorized Technical Supervisors who are adequately qualified & well experienced in execution of permanent way works to the satisfaction of the Railway Engineer (ADEN of the section). Before start of the work, knowledge of these



Supervisors will be tested and if not found properly trained, will be trained for one week by ADEN/SSE (P. Way) free of cost.

(ii) The Tenderer/contractor shall intimate in writing the names of Tech. Supervisors to be engaged in the work and ensure their presence within 07 days from issue of LOA, in the office of Assistant Divisional Engineer of Rly, before starting of the work & their deployment will be as per Para 4(1) above.

(iii) The acts of omission & commission by contractor's supervisors shall be considered as the omission & commission of the contractor.

(iv) The Tenderer/Contractor will be required to take all necessary precautions and steps for proper and safe working and safe movement of trains on track on which work is being executed and adjoining tracks. In case if it is noticed that due precautions and care is not being taken by the Contractor, then Rly may take action as considered necessary depending on the field condition and the cost for the same will be recovered from the contractor's dues. For the first default a written warning will be issued through letter/site order book. In second/further defaults for same item, a **token penalty of Rs.2,000/- will be imposed at every instant.**

(v) As the work is to be executed in the UP, DN & Single line section & traffic on the adjoining lines will run at full speed, hence the contractor shall make his own arrangements including sound of hooter alarm for looking after his labour and other persons from the danger of traffic on the other lines.

(vi) In case a train derailment happens at the work spot, the findings of the enquiry committee set up by the Railway to investigate the case of the accident shall be final & binding on the contractor. **In the event of the findings, the contractor is held responsible for the accident, the contract is liable to be terminated forthwith and further action will be taken accordingly.**

(vii) The contractor shall not start any work on the open line track without presence of the competent Railways supervisor at site. In case, the contractors or his representative starts any work in absence of the Railway supervisor, it shall be treated as un-authorized and illegal tempering with the track and shall be liable for action under the Indian Railway Act.

(viii) From Railway side, necessary protection arrangement as per IRPWM 2024 with latest correction slip will be made and for that only four Railway Employees (excluding Railway Supervisors) will be deployed. Tenderer/Contractor will have to arrange necessary labour to work for safety protection in the guidance of Railway Employee.

(ix) It will be the prime responsibility of the Tenderer/Contractor to ensure safe running conditions and avoiding of any unusual during their working on the track/ base depot. In case of any unusual incident occurring due to default of the contractor, the contractor will be liable to pay the cost of damage done to Railways during their working, as decided by Railway administration.

5: **MACHINERY, PLANTS & EQUIPMENTS:**

  
DRM (W) JBP

CONTRACTOR



(i) All the works included in the tender schedule shall be done by contractor's own PQRS, gantry, tools, plants and machinery and labour etc. Railway will provide Wagons and Locomotive free of cost.

(ii) The Tenderer/contractor shall keep four Disc Cutters for cutting of rail but will also keep two gas cutting machines at the site of work at all times. In case of emergency at this site, the Railway shall be at liberty to use these disc cutter/gas cuttings arrangements without any extra payments.

(iii) 100 Nos. of wooden blocks of size 100x30x30cm, will have to be arranged by the Tenderer/contractor at his own cost

**6: ACCOUNTAL OF RELEASED MATERIAL:**

(i) The contractor shall take joint inventory of the P. Way material likely to be released from existing old track. The inventory is to be taken before start of fieldwork. The contractor shall have to carry out dismantling and stacking of released material under the supervision of site engineer. Before handing over the site of work to the contractor, both contractor and Engineer, representing the Railway shall have to produce a joint certificate for complete accountal of the material to be released. This inventory should be jointly signed in triplicate and two copies of which shall be retained by the Railway and one by the Contractor. On work completion, if any discrepancy / shortfall occur in the material accountal then the same shall be recovered from contractor's bill as per extant rules and procedure. The contractor shall be responsible for any short fall in the released material and its cost being recoverable from him considering the same as loss to the Railway Administration.

(ii) The payment of running bills of the contractor shall be subject to collection, lifting/transportation, sorting, stacking & accountal of the released material at sites nominated by the Engineer's representative and to his satisfaction. **The previous day's released material will be transported by the contractor before executing the next day's work.** The procedure adopted by the engineer-in-charge to hand over the new material from stores and to transport released materials from site to depot shall be binding on the contractor.

(iii) At the time of making the final bill, all the released materials shall again be tallied with the joint inventory already made and payment of final bill will be subject to proper accountal of released material as per this original inventory. **This accountal issue will be addressed by SSE (P.Way) & ADEN in their certificate in measurement book of work.**

(iv) Released rails must be expeditiously collected and transported to PQRS Depot/other agreed location where proper stack can be made and these stacks of scrap rails can be lifted by purchaser by road. Material will be stacked properly after crossing the number of yard lines if required. Decision of Engineer will be final about stacking location. Contractor will not have any dispute in this regard. Till stacks are made at designated place, contractor will be responsible for any theft/loss/miscreant activity related to released rail. This will have to be done by Contractor at his/her own cost.

(v) The released material is to be stacked in layers of 1.5-2.0 m high so as to occupy minimum stacking ground. The rails and sleepers shall be guarded



by contractor at his own cost till it is stacked as per direction of Engineer-In-Charge, or his representative. The stacked materials shall be suitably measured and recorded with paint with stack number/quantity in it, and the same shall be taken over by railways, after which Railway shall be responsible for its guarding.

(vi) The fittings for replacement will be supplied by Railway at nearest railway station/manned level crossing/SSE (P. Way) store where truck can reach. Contractor will have to load/transport/unload fittings from these locations to PQRS Depot or vice versa. No extra payment will be done for this.

## 7: WORK EXECUTION:

(i) **Expected progress of renewal by PQRS is 5 km per month.** The contractor will have to arrange the labour accordingly. To achieve this progress, contractor will have to keep minimum 60 panels ready all the times. If rake of 30 BRNs is provided by Railway, minimum 60 panels will kept ready for loading.

(ii) The loading/unloading of fabricated panels is to be done by the contractor's own gantry or any other arrangement. This will have to be done as per "Sequence of activities" provided with Tender documents.

(iii) **Contractor will provide round the clock, one non-AC road vehicle (four wheeler) like Mahindra Bolero/Tata Sumo or equivalent for inspection of the work in PQRS Depot/running track site during currency of contract with condition that it will not be used for more than 2500 Kms per month / 6500 Kms in each quarter. No payment is to be done by Railway for this. Log Book for the engaged vehicle should be attached in the running bills for the accountal of the same.**

(iv) **Sleeper rake will be unloaded in PQRS depot at a rate of minimum 10 BRNs per day. Time will start, the moment rake is placed in unloading line of PQRS depot. A penalty of Rs.5,000/- per day will be levied for extra days taken in unloading.** Contractor will have to make his own arrangement of lighting for day and night unloading.

(v) **Fabrication of panel will include intermediate stacking of panels in 3-4-5 layers on ground prior to loading panels into BFR/BRN.**

(vi) **The work of fitting renewal will be carried out simultaneously with TRR by contractor. No extra payment will be made for fitting renewal.**

(vii) **Grease, paint, anticorrosive paint etc. consumable required in the works shall be deposited by the contractor in advance to SSE (P. Way) In-Charge depot and the same shall be issued to contractor for work as per requirement. The contractor shall transport the same at his own cost.**

(viii) **Level of track at level crossing will not be lifted from road level, if not directed by Railway supervisor. If final track level is lifted above road level, contractor will repair/remake approach road to match the level of road with track. All other necessary work like asphaltting, lifting of barrier etc. will be carried out by contractor at his own cost.**



## For Part B

- (ix) The Contractor should note that during the process of removing fittings they may find some jammed pandrol clips, two way Keys, Cotters, tie bars etc. also which have to be suitably taken out without damaging the sleepers. Jammed ERCS shall be removed by heating the insert or other suitable means approved by ADEN without damaging the sleepers. No extra payment shall be made for this activity.
- (x) The block will be granted subject to availability and margin in train operations. **No claim on account of not granting the traffic block will be entertained by the Railway.**
- (xi) As traffic block result in traffic detention, hence any failure to optimally utilize the granted block will be viewed very seriously. **During block working the contractor failure will be fined Rs.5,000/- per block for PQRS/TRR/SEJ work.** Block of minimum 120 minutes duration will be provided for these works. The decision of Engineer-In-Charge in this matter shall be binding on contractor.
- (xii) The work will be carried out during day time and there has to be no infringement to the Railways schedule of dimensions (IRSOD 2022).
- (xiii) The Engineer In-Charge at site is empowered to decide the required lifting of track in order to ensure minimum 300 mm clean cushion under the sleeper. The depth of cushion will be measured from the bottom of sleeper.
- (xiv) Re-fixing of KM Posts, Gradient Posts, Hectometer Posts, LWR Boards, Curve Boards, W/L Boards etc., disturbed behind TSR work will be done by contractor. No extra payment shall be made for this.
- (xv) Contractor may have to work in station yard also, where falling of water, human wastes, other wastes etc. are common feature. If required, contractor will have to engage his/her own safaiwala etc. to clear/clean all these wastes for proper progress of the work. No extra payment will be made to contractor for this.
- (xvi) If any load is stabled on working line in yard, work progress may be affected. No any claim will be given by Railway to contractor.
- (xvii) Contractor will provide labour, for shifting & fixing of all informatory boards (Caution board, Speed board, T/P, T/G etc.) related to work as per direction of SSE/P. Way/In-Charge on the same day as the caution is revised. **A penalty of Rs.2,000/- will be imposed each time, if contractor fails to provide labour, and work is carried out by Railway by any other means.**
- (xviii) **If any fish plated joint found with un-chamfered rail hole, a penalty of Rs.5,000/- will be imposed for each un-chamfered hole.** Decision of ADEN will be final in this regard.
- (xix) Depending upon the temperature conditions, rail tensors may also be used during De-Stressing. Extra labour if required will be provided by contractor accordingly, without extra payment.

(xx) The contractor may be required to make use of modern telecommunication mode e.g. mobile phones etc. for proper communication in the field for optimum use and utilization of traffic block.

(xxi) No work shall be done unless & until the contractor's technical supervisor & Railway's supervisor are present at site.

**8: TRANSPORTATION OF MATERIAL:**

(i) The contractor shall be required to submit the necessary indemnity bond on requisite Performa with transit insurance policy, if required, as per the direction of Engineer In-Charge on account of theft or damage/loss during transportation of Railway material.

(ii) The contractor will be advised through a memo or by recording in Site Order Book by the Engineer representative about the need for arranging transportation. The contractor is supposed to arrange the transportation arrangement at the requisite point within three days of such intimation. In case of delay or default, the Railway is entitled to imposed liquidated damages in addition to other remedies available in General Conditions of Contract.

(iii) Truck/Trailer may be loaded from one or more places and unloaded at one or more places as per requirement. Safe loading/unloading of the material will be done by the contractor. Necessary loading/unloading arrangement and handling of material to make it convenient for loading/unloading will also be done by contractor for which no extra payment will be made to the contractor.

(iv) The transportation will have to be made on material challan as per prescribed procedure. The challans will be verified by the Railway stockholder after satisfactory transportation of material of prescribed quantity.

(v) The transportation of material, safety will be entire responsibility of the contractor. Any damage, wastage or loss to Railway material in any manner should be totally avoided and in case of any shortage/damage is found, the recovery will be made from the contractors in accordance with Railway rule. Cost for P. Way material will be taken from latest rate supplied by WCR HQ.

(vi) The Railway will not be responsible for any damage or accident to any labour working during the contract execution.

(vii) All terms and conditions as per West Central Railway General Condition of Contracts are applicable to this contract.

(viii) Portable cranes/chain pulley block or any other equipment required for loading, unloading and stacking will have to be arranged by the contractor at his own cost.

(ix) The bill for payment will be prepared by the Railway on the basis of verified copies of advice note/challan after recording the same in measurement books.



(x) Sleepers, rail and other material shall be unloaded and kept stacked at the available safe location in PQRS Depot.

## 9: PENALTY PROVISIONS:

(i) The Tenderer/Contractor will be required to take all necessary precautions and steps for proper and safe working and safe movement of trains on track on which work is being executed and adjoining tracks. In case if it is noticed that due precautions and care is not being taken by the Contractor, then Rly may take action as considered necessary depending on the field condition and the cost for the same will be recovered from the contractor's dues. For the first default a written warning will be issued through letter/site order book. In second default for same item, a token penalty of Rs. 2000/- will be imposed at every instant.

(ii) As traffic block result in traffic detention, hence any failure to optimally utilize the granted block will be viewed very seriously. During block working the contractor failure will be fined Rs.5000/- per block for PQRS/TRR / SEJ work. Block of minimum 120 minutes duration will be provided for these works. The decision of Engineer-in-charge in this matter shall be binding on contractor.

(iii) Expected progress of renewal by PQRS is 5 km per month. The contractor will have to arrange the labour accordingly. Railway will ensure providing minimum 15 days block of 120mins per month and Tenderer/Contractor will have to achieve minimum progress of 5 km per month. A penalty of Rs.1,00,000/-per km of shortfall will be imposed on Tenderer/Contractor if he fails to achieve minimum progress of 5 km per month per PQRS site even after providing minimum 15 days blocks of 120minutes each per month.

(iv) Sleeper rake will be unloaded in PQRS depot at a rate of minimum 10 BRNs per day. Time will start; the moment rake is placed in unloading line of PQRS depot. A penalty of Rs.5,000/- per day will be levied for extra days taken in unloading. Contractor will have to make his own arrangement of lighting for day and night unloading.

(v) In case Contractor fails to ensure availability of 60 panels all the time, after availability of SH rail and wider base sleepers /revised wider base sleepers, penalty of Rs. 2000/- per deficient panel for that day will be imposed.

(vi) If Contractor does not load required number of SH rails from source, transport and unload SH rails as provided by Railway in nearby location (10 to 100 Kms from actual site of work) within 7 days from the time when Railway make available these SH rail for lifting by Contractor, then a penalty of Rs.10,000/- per day of delay will be imposed.

(vii) If auxiliary track is not made within 30 days from the date of issue of LOA then a penalty of Rs.5,000/- per day of delay so done will be imposed.

(viii) If Contractor fails to use traffic block due to fault of the Contractor, then a penalty of Rs. 20,000/ per traffic block wasted will be imposed.





## For Part B

(ix) If ERC greasing is not done, then a penalty of Rs.20/- per non greased ERC will be imposed.

(x) If De-Stressing is not done, then a penalty of Rs.20,000/ per TKm will be imposed.

(xi) If ERC is not inserted properly, then a penalty of Rs.5/- per ERC which is not inserted properly will be imposed.

(xii) If boxing & dressing is not done as per IRPWM, then a penalty of Rs.15,000/- per TKm will be imposed every time when boxing & dressing is required and not done after tamping in the CTR/TSR location. Tamping may be done, two times or more with ballasting/without ballasting for lifting of track.

(xiii) In case, cess is damaged during work, the same will have to be repaired by the Contractor at his own cost.

(xiv) If any fish plated joint found with un-chamfered rail hole, a penalty of Rs.5,000/- will be imposed for each un chamfered hole. Decision of ADEN will be final in this regard.

(xv) Contractor will provide labour, for shifting & fixing of all informatory boards (Caution board, Speed board, T/P, T/G etc.) related to work as per direction of SSE/P. Way/In-Charge on the same day as the caution is revised. A penalty of Rs.2,000/- will be imposed each time, if contractor fails to provide labour, and work is carried out by Railway by any other means.



DRM (W) JBP

CONTRACTOR

**Final Product:**

Replacing old sleepers/old rails with wider base sleepers / revised wider base sleepers and new/old rails on running track with the use of new wider base sleepers / revised wider base sleepers and rails provided by Railway wagons at PQRS depot or site and **making running track as good as earlier one after rail replacement (including boxing, tamping, dressing of ballast & de-stressing of track)** except welding of rail which will be done by the Railway. This product will have to be provided by contractor with the help of contractor's own PQRS set of machines/ other machines and all other tools and plants including all other resources as required for replacing old sleepers with new wider base sleepers / revised wider base sleepers on running track in nominated section. **No other SOR/NS item is allowed to be added in this schedule of single composite NS item, for achieving this final product.**

**NOTES:**

- (i) Wider base sleepers / revised wider base sleepers in PQRS depot will be provided by Railway in Railway wagons which will have to be unloaded and stacked properly for smooth formation of panels using loose SH rail and wider base sleeper / revised wider base sleeper by contractor, using crane/gantry in PQRS depot (unloading to be done within the stipulated time as and when loaded BFRs are received so as to hand over empty BFRs without demurrage, otherwise demurrage shall be borne by the Contractor). Crane & other tools will have to be arranged by the contractor at his/her own cost.
- (ii) All materials required for sleeper renewal which are to be arranged by Railway like rubber pad, ERCs, liner, fish plates etc. will be available at SSE/Stores/Depot and which will have to be brought to the running track site/PQRS Depot, by contractor. **Expenditure on this will be borne by the Contractor.**
- (iii) No other payment for any other activity which may be required for achieving final product will be made except the payment which is given in the schedule for (01) one Tkm of CTR/TSR with wider base sleepers / revised wider base sleepers.
- (iv) All Bidders should visit the site and read tender document carefully (especially special conditions of the tender document) before offering the bid and should offer single rate for all the activities which are required for replacing old sleepers with wider base sleeper / revised wider base sleeper (TSR/CTR), replacing old rails with new rails and making the track fit for 30 kmph (welding of rail will be done after providing new rail).



**SPECIAL CONDITIONS AND SPECIFICATION OF CONTRACT**

Name of Work: CTR 33.109 Km and TSR 33.396 Km (Total 66.505 Kms) by contractors PQRS Machine and manually at obligatory points on STA-REWA and KTE-MKP section and TRR 16.75Kms, TFR 5.00Km and TFR-(R-only rubber pad)-30.014 Km on STA-REWA and KTE-MKP section under Sr. DEN (N) Jurisdiction.

**1.0 CONDITIONS IN GENERAL:-**

- 1.1 Before submitting the tender, the tenderers are required to satisfy themselves by actual inspection of site and locality of the work and that all the conditions liable to be encountered during the course of execution of works are taken in to account and the rates entered in tender schedule are adequate and all inclusive for completion of the works to the entire satisfaction of the Engineer.
- 1.2 Unless otherwise specified in the Special Conditions, all the tools, plants and machinery and equipments shall be arranged by the contractor as are necessary for execution of the work.
- 1.3 Housing accommodation and watering facilities for Contractor's labour will have to be arranged by the contractor. Cess and Water charges will be recovered from contractor's bills as per extant rules.
- 1.4 Block work should be done in daytime only between sun rise to sunset, under traffic block/speed restriction as necessary, which shall be arranged by the Engineer's representative at site.
- 1.5 Except otherwise required, all works under CTR/TSR such as lifting of track, sleeper renewal etc. will be executed under caution order which will be imposed by the sectional SSE/P.WAYS as per necessity. Caution watchman as necessary during day and night would be arranged by Railway free of cost.
- 1.6 Safeguard of materials released from track and new material as handed over to the contractor from SSE/P.WAYS depot/Stores shall be the contractor's responsibility and his / their responsibility shall cease only when:-
  - (i) Sorting and stacking in lots is completed in the SSE/P.WAY's depot or any other place as directed and verified by the SSE/P.WAY /Stock holder and material is handed over back to the SSE/P.WAY / stock holder against a proper Hand Receipt (HR).
  - (ii) Laying of new materials in track is completed and surplus materials are handed over to the SSE/P.WAY/Stock holder at his stores/depot against a proper HR.
- 1.7 Before removal of sleepers or any other P. Way materials, a joint inventory should be prepared by contractor along with SSE/P.WAYincharge of the work for particular strip where work will be taken in hand within short period showing details of existing track and nature of replacement showing exact quantity of the requirement of new materials for replacement and released materials. The inventory with contractor's authorised representative should be prepared well in advance before starting the work, and recorded in a register to be kept with SSE/P.WAYincharge.



- 1.8 In case of any loss, damage or shortage to any materials (either released or new) from the custody of contractor, recovery will be made from the contractor's bills as per prevailing rates of disposal/procurement of such items by the Railway, depending upon the released or new materials as the case may be.
- 1.9 Loading and unloading of materials would be done in safe manner as per direction of Railway Officials. It shall be ensured that at no point of time the dismantled materials infringe the track. Immediate and prompt action shall be taken by the contractor in stacking the material at a safe distance from the track.
- 1.10 Whenever a train is to be passed during the progress of work, immediate on hearing the whistle from the lookout man, the site should be kept free from man and tools by the contractor after making necessary arrangements for safe passage of the train including insertions of wooden blocks, where necessary, as per direction of the Railway's representative at site and resume the work again as soon as the train passes. The contractor shall deploy the lookout man for this purpose
- 1.11 Observation of bonded labour system (Abolition) Ordinance -1975:- The contractor shall have to observe the provision of bonded labour system (Abolition) Ordinance -1975.
- 1.12 Contractor shall ensure the all P. Way materials are properly used and no damage is done to P. Way materials new or released. In the event of any damage to P. Way materials contractor shall be responsible for damage.
- 1.13 Contractor shall be responsible for proper maintenance of track within the restricted portion of length of track. Restriction will only be removed when track is fully maintained by contractor up to specification and satisfaction of the Engineer's representative in Charge at site, for 30 KMPH & 45 KMPH.
- 1.14 Before commencement of the work, contractor alongwith his supervisors and labour should get clear "Know how" of the work from the Railway Officials to avoid confusion during the progress of work.
- 1.15 The entire work is to be done in workman like manner and the track shall be handed over to Railway for maintenance after completion of work.

**1.16 Safe Working Methods:-**

All or some of the works executed under this contract involves works on or alongside the Railway track on which the Railway Traffic is kept operative during or immediately after the completion of one or more phases of the contract. In view of the position, maintaining safe working conditions at work site at all times for the safe passage of the Railway traffic is a primary & over riding condition required to be fulfilled by the contractor at all time.

For this purpose, it is understood and agreed to by the contractor that the work executed by him under this contract shall at all time fulfill all the safety conditions in force on the Railway from time to time to operate the Railway Traffic.

**1.17 Instructions/directive of the Engineer's representative:-**

  
DRM (W) JBP

CONTRACTOR



The contractor shall at all time, execute the contract work only in the presence of and under the supervision of Engineer's representative of a Railway Employee specially appointed on his behalf. No work under the contract shall, therefore, be commenced by contractor without the permission of Engineer's representative.

(i). The contractor shall always execute the work under contract in strict compliance with the instructions or directive by the Engineer's representative of Railway. Act of non-compliance with the instructions, directives issued by the Engineer's representative shall be considered as a default of the contractor and the Railway shall be free to take further appropriate action as provided in the contract for dealing with such default of the contractor. The decision of the Engineer's representative where there has been an act of non-compliance with the instructions/directives of the Engineer's representative for the purpose of this clause shall be final and conclusive.

(ii). The instructions/directives by the Engineer's representative shall not however, absolve the contractor of his responsibility or reduce his responsibility in any manner whatsoever in regard to maintaining the safe working condition at the work site.

#### **1.18 Protection at the work site:-**

- (i) On Railway Track where the train traffic will be operational during the execution of the contract work, the protection of the work site as considered appropriate and adequate shall be arranged by the Engineer's representative at the Railway's cost. Flagman will be given by Railway on Speed Restriction of 20 KMPH.
- (ii) Notwithstanding the aforesaid mentioned protection at the work site provided the Engineer's representative, the contractor shall be responsible for providing appropriate and adequate system of warning the contractor's workmen about the train traffic on or in the vicinity of the site of work. The decision of Engineer's representative whether the facilities provided by the contractor in this regard are appropriate and adequate or not shall be final and conclusive.

#### **1.19 Non-Compliance with the instructions/directive of the Engineer's representative:-**

- (a) The contractor shall always comply with the instructions/directive issued by the Engineer's representative from time to time. In the event of any non-compliance with such instructions/directives apart from and in addition to other remedies available to the Railway as specified herein above, the Engineer's representative may employ at the work site the Railway workman with necessary equipments as considered appropriate and adequate by him to provide the requisite condition for the safe and unhampered movement of Railway traffic. The decision of the Engineer's representative in regard to the need, appropriate and adequacy of the deployment of the Railway workmen with necessary equipments shall be final and conclusive.
- (b) When the workman with necessary equipments are deployed in the above manner, recovery at the following rates shall be made from the contractor's

  
DRM (W) JBP

CONTRACTOR



dues under this contract or any other money of the contract available with the Railway under this contract or any other contract. The recovery for the total workmen hours employed at the work site for the above purpose shall be made at the rate of Rs. 30/- (Rupees Thirty Only) per workman hours irrespective of the type and grade of the Railway employee actually employed. The aggregate period of the workmen hours for the above recoveries shall be reckoned from time the Railway workman are actually deployed at the site till the work is completed to the satisfaction of the Engineer's representative, whose decision in this regard shall be final and conclusive. The decision of the Engineer in charge shall be final and binding on the contractor.

- (c) If the contractor does not comply with the instructions, directives of the Engineer's representative, as part from an in addition to the remedies available to Railway as specified herein above without prejudice to the Railway's right in this regard, the Engineer's representative, which for the purpose of this clause shall exclude suspended the contractor work till the Engineer's representative is satisfied that the contractor is in a position/will comply with the instructions/directives issued by the Engineer's representative.
  - (d) Similarly if the contractor fails to transport the material, the Railway, if it so desires, shall deploy its own transport means for carrying out the necessary transportation and in addition to the labour deployed for which deduction shall be made at the rate of Rs. 30/- per man hour, deduction at the rate of Rs. 10/- per tonne per Km. for lead up to 30Kms. and at the rate of Rs. 5/- per tonne per Km. for lead beyond 30Kms. shall be made.
  - (e) The decision of Engineers' representative in this regard shall be final and conclusive. The Contractor shall not have any claim whatsoever against the Railway for such a short terms/long terms suspension of the contacted work.
  - (f) During the above-mentioned period of suspension of work, the contractor shall not in any manner attempt to carry out any work at the work site. Any such attempt of the contractor shall than be liable for further appropriate action under the relevant provision of Indian Railway Act.
- 1.20 Contractor shall not start any work without the personal presence of the SSE/P.WAY at site. In case the contractor's representative starts any work in absence of SSE/P.WAY, it shall be treated as unauthorized and illegal tampering with track and shall be liable for action under the Indian Railway Act.
- 1.21 Penalties shall be imposed in case there is an accident, negligence, careless, oversight etc. for which the contractor is responsible and contractor shall have to pay such amounts as determined by the Engineer in charge at site and to be recoverable from the contractor's due.
- 1.22 Railway administration reserves the right to terminate the contract with immediate effect if the contractor is found responsible for the accident without giving any further notice to the contractor.



**1.23 Speed Restriction and disconnection:-**

- (i) Necessary speed restrictions will be imposed by SSE/P.WAY in charge of the work for execution of through Sleeper Renewal of girder bridges sleeper, points and X-ing sleepers, deep screening, lifting, re-alignment of curves etc.
- (ii) Contractor after ensuring that speed restriction is imposed where he has to do the work, should progress with the work in a systematic manner keeping in view the speed restriction will be for minimum period and should be utilised in most progressive manner for which before starting the work, the contractor in consultation with Railway representative should check out the programme date wise and operation wise. Any delay on account of contractor's negligence will be taken up seriously and necessary action will be taken as per G.C.C. and extant rules which may amount to termination of the contract and awarding the same to other contractor. Signal-man as necessary during day and night will be arranged by Railway free.

**1.24 Safety Hazards:-**

- (i) The work should be done in the presence of the authorized Railway supervisor not less than rank of an SSE/P.WAY.
- (ii) No work should be carried out during rains and foggy weather or when working conditions do not permit.
- (iii) He should ensure for providing sufficient number of technical supervisors including retired SSE/P.WAY having sufficient experience constantly during the progress of work at site.
- (iv) The contractor will ensure that no obstructions are caused which may endanger to safety of track while working at site. Any loss caused to Railways due to negligence of the contractor will be recoverable from the contractor, as decided by the Railway Administration.
- (v) The work will be done during speed restriction as and when imposed. No compensation will be payable for idling of the labour.

**1.25 Safety at work site**

1.1 Before permitting the execution of certain works like earth work, supply of ballast for new or existing rail line, gauge conversation or laying of concrete sleepers and rails etc. where it is necessary to used road vehicle/machinery, Open lines Engineering -in-charge (ADEN/DEN) of the section shall ensure that he receives the prior intimation/Confirmation of the following aspects from Assistant Engineer/Assistant Officer in-charge of the work of the executing agency i.e. construction, electrification, S&T etc.

1.1.1 Name & address of the contractor assigned to execute the work.

1.1.2 Contractor's list of the number(s) of individual vehicle(s) names and license particulars of the driver(s) proposed to be used.

1.1.3 Information regarding location, during & timings during which the vehicles are planned to be plied.

- 1.1.4 Training to supervisor/staff of contractor. Competency certificate to be issued by Assistant Engineer in charge of site.
- 1.1.5 Survey of site by supervisor of contractor & Railway's supervisor to assess the precautions to be taken at site for working of trains and material required for protection.
- 1.1.6 Draw and advice to sectional ADEN/SE (P. Way) & SE (Works) about the detailed planning of work including protection of track and safety measures proposed to be adopted.
- 1.2 Information as indicated in item 1.1.2 to 1.1.6 shall be obtained from contractor prior to the start of the work if the work is directly supervised by open line.
- 1.3 Sectional Sr. DEN should know the names of supervisors of constructor organization/other organizations who are going to be In-Charge/ In-Charge of work site.
- 1.4 Before the start of work, the land strip adjacent to running track where road vehicle/machinery is to ply for the work shall be demarcated by line in advance at the appropriate distance from the center of existing track in consultation with railway supervisor.
- 1.5 Barricading as per the design shall be provided in full length at work area along the track at specified distances.
- 1.6 The work site shall be suitable demarcated to keep public and passengers away from work area. Necessary signage boards such as 'Work in progress' etc shall be provided at appropriate locations to warn the public/passengers.
- 2.0 Measures to be ensured during the execution of the work.
- 2.1 Contractor has deputed trained supervisors at work sites duly certified by ADEN/ Incharge of the work.
- 2.2 Drivers of vehicle have been briefed about the safety and precautions to be taken while moving/working close to traffic.
- 2.3 The contractor shall not allow any road vehicle belonging to him or his suppliers etc. ply within 6 meters of center of running line without presence of Railway supervisor.
- 2.4 Contractor shall ply road vehicles Only between Sunrise and Sunset. In case of emergency where it is necessary to work during night hours, sufficient lighting shall be ensured in the complete work area for the safety of public and passengers. Also additional staff shall be posted as necessary for night working.
- 2.5 Wherever provided the engineering indicator boards shall be as per the provisions of P.way manual.



2.6 Contractor shall ensure that road vehicle/machinery ply in a way so that these do not infringe the line of demarcation.

2.7 Look Out man shall be posted where necessary.

2.8 In unusual circumstances, where operator apprehends infringement to track while working truck/machinery near running track, following action shall be taken.

a) The contractor/supervisor/vehicle operator immediately advises the situation to railway official and assists him in protecting the track.

b) Protection shall be done as done for other emergencies.

2.9 Individual vehicle/machinery shall not be left unattended at site of work. If it is unavoidable and becomes necessary to stable the road vehicle/machinery at plant near running track, these shall be properly secured against any possible roll-off and always be manned even during non-working hours.

2.10 All temporary/ arrangement required to be made during execution of work shall be made in such a manner that moving dimension do not infringe. Necessary checks shall be exercised by site in charge from time to time.

2.11 In case, work has been planned to be done within 6 M of center of track but at more than 3.5 M it shall be ensured that.

2.12 Necessary precautions for protection of track have been taken and caution order issued to trains.

2.13 Look out man has been posted along the track at a distance of 800 M from the location of work with red flag and whistle to warn the road vehicles regarding approaching trains.

2.14 In case, work is planned to be done within 3.5M of centerline of running track, it shall be ensured that the work is done under block protection only and necessary safety precautions for protection as per Para No.806 and 807 of IRPWM are taken.

2.15 While digging in station area, if any cable is found, digging should be stopped and concerned signaling/electrical staff should be informed immediately.

2.16 Mobile phones or Walkie Talkie sets where necessary should be provided at works sites.

3.0 Precaution required to be taken during execution of work requiring traffic blocks.

3.1 Any work, when infringes the moving dimensions, shall be started only after the traffic block has been imposed and track protected

3.2 At locations where night working is unavoidable, proper lighting arrangement should be made.

3.3 Before closing the work the track shall be left with the proper track geometry so that the trains run safety.

3.4 After completion of work, the released sleepers and fittings should be properly stacked from the track to be kept clear of moving dimensions.

3.5 Block shall be removed only when all the temporary arrangement machineries, tools, plant etc have been kept clear of moving dimensions.

#### **4.0 Stacking of material along railway track**

4.1 The sites for material stacking shall be selected in advance ensuring that no part of the stacked material would infringe the standard Moving dimensions. A plan of proposed stacking locations be made and signed jointly by an authorized Railway's representative and contractor's representative.

4.2 The selected location shall be marked by lime in advance.

4.3 Presence of an authorized railways representative unloading and stacking shall be ensured.

4.4 The material shall be stacked such a height, which will not cause infringement to SOD in case of accidental roll off.

#### **5.0 Safety aspects to be observed while working in OHE area.**

5.1 No electrical work close to running track shall be carried out without permission of railway representative.

5.2 A minimum distance of 2m has to be maintained between live OHE wire and body part of worker or tool of metallic support etc.

5.3 No electric connection etc. can be tapped from OHE

5.4 Authorized OHE staff should invariably be present when the relaying work or any major work is carried out.

5.5 Power block is correctly taken and 'Permit to work' is issued.

5.6 The structure bonds, track bonds cross bonds, longitudinal rail bonds are not disturbed and if disconnected for the work they are reconnected properly when the work is completed.

5.7 The track level is not raised beyond the permissible limit during the work. Note: For items of barricading, Sign Board like "work in progress" walkie - Talkie sets, mobile phones, look out man etc, suitable provision may be incorporated in the tender conditions as per site requirement.

5.8 Safe working of contractors – A large number of men and machinery are deployed by the contractors for track renewals, gauge conversions, doublings, bridge, rebuilding etc. It is therefore essential that adequate safety measures be taken for safety of the trains as well as the work force. The following measures should invariably be adopted:-



- (i) The contractor shall not start any work without the presence of railway supervisor at site.
- (ii) Wherever the road vehicle and/or machinery are required to work in the close vicinity of railway line, the work shall be so carried out that there no infringement to the Railway's schedule of dimensions. For this purpose, the area where road vehicles and or/ machinery are required to ply shall be demarcated and acknowledged by the contractor. Special care shall be taken for turning/ reversal of road vehicles/ machinery without infringing the running track. Barricading shall be provided wherever justified and feasible as per site condition.
- (iii) The look out and whistle caution orders shall be issued to the trains and speed restrictions imposed where considered necessary. Suitable flagmen/detonators shall be provided where necessary for protection of trains.
- (iv) The supervisors/ workmen should be counseled about safety measures. A competency certificate to the contractor's supervisor as Performa annexed shall be issued by AEN, which will be valid only for the work for which it has been issued.
- (v) The unloaded ballast/ rails/ sleepers/other P.way materials after unloading along the track should be kept clear off moving dimension and stacked as per the specified heights and distance from the running track.
- (vi) Supplementary site-specific instruction, wherever considered necessary shall be issued by the Engineer in Charge.

  
DRM (W) JBP

**CONTRACTOR**

**LINKING OF AUXILIARY TRACK WITH 60Kg / 52Kg 15/20 RAIL PANELS OR  
ANY OTHER RAIL LENGTH:**

- (a) Rail panels of 10/20 rails or any other length panels available along the side of track in advance will be used for formation and auxiliary track centrally with B.G. running track at 3.4 meters gauge on CST-9 Pots/Wooden/ST blocks at spacing of 1.5 to 2.0 meters (as decided by Engineer In-charge of the work). Sleepers will be properly packed with ballast. The contractor shall link these rails over CST-9 Pots / Wooden / ST blocks after pairing them if required and fasten the rail ends with fish plates. Provision of rail closure for linking of auxiliary track will have to be done by the contractor. Pulling of rails if required up to 52 meters will have to be done by the contractor at his own cost under supervision of Railways representative using cess rollers. He will also provide fish plates and bolts which will be supplied by the Railways free of cost. The quality of auxiliary track will be certified by the SSE/PW/In-charge at site on the basis of packing conditions, levels and alignment as per the laid down standards of the Railways.
- (b) To avoid buckling of auxiliary track due to rise in temperature distressing of the same may have to be done by the contractor at high temperature if so directed by the Engineer incharge of the work. Nothing extra shall be paid to the contractor on this account.
- (c) The fabricated sleeper panels will then be laid by Railways using PQRS replacing old panels by 12.6 meter or other rail length panels.
- (d) Rail panels of 10/20 rail panels or any other length from auxiliary track will now be dismantled for putting in track releasing 13.2/12.6 meter (or any other length) panels. This will release CST-9 pots/wooden/ST blocks from auxiliary track. All these released CST-9 Pots/wooden/ST blocks will have to be lead ahead by the contractor for auxiliary track. The rate of linking auxiliary track will include this job of leading CST-9 Pots/Wooden/ST blocks and nothing extra shall be paid on this account.
- (e) The contractor shall always ensure that sufficient length of auxiliary track is available ahead of the actual relaying work.
- (f) CST-9 Pots/Wooden/ST blocks used for formation of auxiliary track after being released shall be taken ahead for subsequent use and formation and auxiliary track. Normally one Km. of auxiliary track shall be made prior to start of the work of renewal of PQRS and daily 30 to 40 panel length shall be laid ahead for day to day work. While the work is in progress the contractor shall ensure that no material/tools and plants are kept in such a way that these foul the tracks.

**1.1 PAIRING OF 60KG RAIL PANELS FOR WORK BY BRINGING THEM IN UPRIGHT POSITION, SHIFTING LONGITUDINALLY TO ELIMINATE THE GAP IN BETWEEN AS REQUIRED TO CARRYOUT THE WORK OF RAIL RENEWAL/MAKING AUXILIARY TRACK ETC.**

- (a) The work will be under taken between sunrise to sunset.
- (b) 20 rails or shorter panels of 60Kg rails will be unloaded alongside the track by Contractor/Railway in advance. These panels will first be brought on the shoulders after leveling the ballast on shoulders. The panels will then be brought in upright position. The upright position means the similar position of rails as in normal track. The panels should not be tilted.



DRM (W) JBP

CONTRACTOR



- (c) For pulling of rails panels, contractor will arrange non-infringing rollers as per standard adopted by Railways so that panels are not damaged. Direct hitting / pushing of panels are not permitted.
- (d) After brining the panels in upright position, these will be shifted longitudinally by pulling the panels by the contractor at his own cost. The pulling will be done to eliminate the gap in between the panels. A gap up to 52 meters will be eliminated by pulling the panels, after which, rail closure will be given to the contractor within 200 meters of work site.
- (e) Adjacent panels will be kept side ways so that they do not touch each other in normal circumstances and can be joined with fish plates by slight side shifting of panels. Wooden blocks will be provided between two panels at the joint so that they do not touch each other.
- (f) Temporary bonding of panels will be done by the Railways whenever continuous length becomes more than 300 meters. The contractor will also ensure that unless proper bonding is done, fish plating will not be done to make continuous panels of 300 meters or more. If work is stopped on this account, nothing extra will be paid to the contractor.
- (g) This work is part of rail renewal/auxiliary track making and nothing extra shall be paid. Tenderer is supposed to do the work of pairing at his own cost.
- (h) The P.Way fittings shall be supplied to the contractor at the base depot. He shall be responsible for its proper storing, guarding etc.

**2.0 REMOVING SERVICE RAILS AND PUTTING BACK RAIL PANELS:**

- (a) After laying of panels has been done with PQRS, the contractor will do the work of replacement of these panels with 60Kg new panels.
- (b) After laying of PRC panels by the Railways the contractor will use the disconnected the rails of auxiliary track. He will correctly place 60Kg / 52Kg rails released from auxiliary track or rail panels lying outside the track in position as directed by the SSE/P.WAY of the Railways so that the rail renewal is done properly. For this purpose the contractor may be required to do up to a maximum of 52 meters of pulling of these rails outside the track to bring them in position. All these works will have to be done by the contractor at his own cost and nothing extra shall be payable to him on this account.
- (c) After the rails lying outside have been placed in the correct position, the contractor will remove the fish plates and bolts / clamps of the rail joints of the panels lying inside the track. All the released fish plates, bolts & clamps will be stacked properly. Simultaneously the fastenings of the sleepers with the rails like ERCs, liners etc. will also be removed. The rails are thus made free of sleepers. These rails then be taken out of the rail seats.
- (d) The rail panels of 10/20 rails or any other length lying outside the track will now be brought into the track sleepers and put at correct position over rail seat of the sleepers. While doing this, the contractor will ensure that the rubber pads are placed in position correctly. The joints of all these rails put in track will be fastened by providing fish plates and bolts with proper expansion gaps as directed by SSE/P.WAY of the Railways.
- (e) After linking both rails in the track with approved fastenings the contractor will do alignment of the track as directed by the site incharge.
- (f) The work of rail renewal will be done in a traffic block only.



- (g) The contractor will keep all the fish plates, bolts, nuts, clamps etc. in safe custody and plates, bolts, nuts, clamps etc. will be deposited by the contractor in SSE/P.WAY's store.
- (h) Any other works as applicable out of following Item No.2.1 shall also be carried out at contractor's costs.

**2.1 REPLACEMENT OF EXISTING 52/60KG RAILS IN MAIN LINE WITH 60KG RAILS IN MAIN LINE WITH 60/52KG 10/20 RAIL PANELS SWP WITH OR WITHOUT RENEWAL OF FITTINGS:**

- (a) The contractor will do the work of replacement of existing rails with 60KG./52KG 10/20 rail panels/SWP rails. The work will not be started by the contractor till such time a SSE/P.WAY of the Railways is present at site of work and has allowed the contractor to start the work. Before starting the work, the site will be protected by display of flag, flagman for this purpose will be provided by the Railways free of cost.
- (b) The work will be under taken between sunrise to sunset.
- (c) Rail panel of 10/20 rails/Short Welded Panels shall be made available by Railways along the track. Contractors will correctly place these 60Kg/52Kg 10/20 rail panels / SWP rails in position as directed by the SSE/P.WAY so that the rail renewal is done properly. For this purpose, the contractor may be required to do pairing / pulling of 60/52Kg panels by bringing the unloaded panels in upright position shifting longitudinally to eliminate the gaps (up to 52meters) in between the panels outside the track to bring them in position. All these works will have to be done by the contractor at his own cost and nothing extra shall be paid to him on this account.
- (d) After the rail lying outside have been placed in correct position, the contractor will remove the fish plates and bolts / clamps of the rail joints of the panels lying in track. All the released fish plates bolts and clamps will be stacked properly. Simultaneously the fastenings of the sleepers with the rails like ERCs liners etc. will also be removed. The rails are thus made free of sleepers. These rails will then be taken out of the rail seats.
- (e) The rail panels of 10/20 rails/SWP of 52Kg/60Kg lying outside the track will now be brought on the sleepers and put at correct position over the rail seats of the sleepers. While doing this, the contractor will ensure that the rubber pads are placed in position correctly. The joints of all these rails now put in track will be fastened by providing fish plates and bolts with proper expansion gaps as directed by the SSE/P.WAY of the Railways. Holes in rails if required will however, be drilled by the Contractor at its own cost and nothing extra shall be paid on this account.
- (f) The rail on one side will be fastened with the sleeper by providing sleeper fittings like ERC etc. The contractor will be responsible to provide all the sleeper fittings in correct position. The rail on the other side will then be fastened to the sleepers at square with respect to the other rails already fastened. Squaring of sleepers if required shall be done by contractor at his own cost and nothing extra shall be paid on this account.
- (g) Renewal of fitting rubber pad, liners, pandrols shall be done along with rail renewal. For this purpose, existing rubber pads shall be removed and new rubber pads shall be provided in correct position at this stage. Similarly new liners and pandrols shall be provided. All fittings / fastenings shall be fixed in correct way, complete and tight on the same block day before sunset.

  
DRM (W) JBP

CONTRACTOR



Rates of fastening renewal are included in through rail renewal. Nothing extra shall be paid.

- (h) After linking both rails in the track the contractor will do alignment of the track as directed by SSE/P.WAY of the Railways.
- (i) The work of rail renewal will be done in a traffic block only.
- (j) The contractor will hand over duly stacked all the fish plates bolts, clamps, rubber pads, pandrols, liners released by him from rail renewal to the SSE/P.WAY of the Railways at the site of work / PQRS base depot store as directed.
- (k) The contractor will classify combination liners, compound fish plates and hand over these to the place where these are required in the block section. Nothing extra shall be paid for this.
- (l) Site must be made fit for 30 Kmph speed restrictions after renewal.
- (m) Any gap at the F/P joints will be properly closed by putting suitable length 52Kg closures and rail pieces in 52Kg portion only. Compound fish plate 60/52Kg shall be fixed at junction point.
- (n) A suitable length rail closure of 60Kg / 52Kg may be provided at the end of new panels as directed by site engineer.
- (o) Fish plated 60Kg / 52Kg joints will be properly supported by wooden blocks till they are welded.
- (p) If any work require, shifting of adjoining sleepers for cutting of rails, the work of shifting of sleepers and packing will be done by the contractor at his own cost.
- (q) When the work is completed the contractor shall return all fish plates, bolts and clamps surplus to the requirement for future working to the Railways at the SSE/P.WAYS base depot store. For any shortage of fittings the cost of the same will be recovered from him @ book rate or purchase rate whichever is higher + 5% freight + 2% incidental charges + 12.5% supervision charges on this rate.

### **3.0 DISMANTLING OF AUXILIARY TRACK:**

Contractor will dismantle the auxiliary track by removing sleepers, fastenings and take out the rails from CST-9 pots/Wooden/ST blocks laid under these rails.

### **4.0 LEVELLING / LOWERING BY 25MM TO 75MM OF BALLAST BED:**

All items incidentals to Item No. 21 shall be carried out by the contractor as per schedule to complete the work. Decision of site in-charge in this regard will be final.

### **5.0 CUTTING OF RAILS:**

- (a) The above item of work envisages cutting of rails on cess / running track as specified in the schedule at isolated locations / Railways nominated depots / stacks as per Railway's requirements and / or as directed by the engineer or his representative complete with handling of rails and all incidental works.
- (b) It is presumed that the nominated depots / stacks / locations for the purpose of this work shall have been inspected by the contractor before submitting the tender and the accepted rate is deemed to be inclusive of all leads, lifts & descent and incidental works.



- (c) Without in any way restricting or modifying the provision of the General Conditions of Contract in this regard the rate for the above work shall be inclusive of all cost of contractor's labour, materials like blades etc. consumables, tools & plant and machinery including rail cutting machines etc. complete.
- (d) The measurement for payment shall be for each complete cut at correct locations and accepted by the engineer or his representative.
- (e) The work shall be carried out strictly as per instructions of the engineer or his representative whose decision in this regard shall be final and conclusive.
- (f) In addition to the above, the work shall confirm to the following :
  - (i) The cut shall be made in a plane truly at right angle to the foot as well as running edge of the rail.
  - (ii) Cut pieces of rails shall have to be returned by the contractor at Railway's nominated depots / locations at his own cost.
  - (iii) The burr, if any, shall have to be removed by the contractor by using his own chisel and hammer, de-burring kits.
  - (iv) Flame / Gas cutting is forbidden except given in schedule by gas cutting.
  - (v) For preventing longitudinal movement of sleepers notching of rail foot of guard rail is to be done on every alternate sleepers when guard rails are fixed in wooden sleepers. The size of notch should be such as to accommodate stem of dog spike / rail screw and should be able to effectively arrest relative movement between rail and sleeper. The payment for notching of guard rail shall be in number of notches cut. The size of dog spike stem is 16mm x 16mm and that of rail screw 20mm dia. Notches of 19mm x 19mm for dog spike and 22mm x 22mm for rail screw would serve the purpose.
- (g) For all works on the running track or adjacent to running track, the protection of work site shall be ensured by the Railways at its own cost. However, the contractor in addition will provide the necessary lookout men to ensure safety of his workmen/workwomen and the instructions given by engineer or his representative in this regard and as stipulated in special conditions of contract should be strictly adhered.

**6.0 GAS CUTTING OF RAIL IN / OUT SIDE OF TRACK VERTICALLY, GAS CUTTING OF RAIL THROUGH WEB / FLANGE INCLUDING ANY STEEL PLATE OF THICKNESS UP TO 10MM AND BENDING OF 52KG RAILS FOR MAKING FLARE IN CHECK RAILS AT LEVEL CROSSINGS:**

- (a) The contractor shall keep his own gas cutting arrangement at site of work at all times. This will consist of at least three cutters. In case of emergency the Railway shall be at liberty to use these gas cuttings arrangements and the payment to be made to contractor will be limited to the reimbursement of the cost of consumed gas only if the item of work done is not covered by this schedule.
- (b) No work on track shall be started by the contractor unless a SSE/P.WAY of railway is present at the site of work and he has allowed the contractor to start the work after imposing suitable speed restriction if required and protection of site of signals. The signalman shall be provided by the Railway free of cost. In case the contractor starts the work without the presence of an





authorization from a Railway SSE/P.WAY, he shall be liable for criminal prosecution for endangering public life.

- (c) The contractor shall be responsible for taking all precautionary measures to ensure safe storage, transport, working maintenance etc. of gases, correct and proper usage of gas and shall abide by all the rules / laws of the Central / State Govt., Local bodies as are in force. In case of any failure on this account the entire responsibility will rest on the contractor. The contractor shall also be responsible to ensure safe working at site and in case loss / damage to life or property of the Railway or anyone else taken place on account of contractors working the entire responsibility will rest on the contractor who will have to bear all such losses / damages / compensations etc. arising out of such incidents. The decision of the Engineer on this account shall be final and binding on the contractor.
- (d) All equipment / machinery, gases, trained staff and labour for gas cutting of rails including transport to site of work and back will have to be done by the contractor at his own cost. Nothing extra shall be paid on this account.
- (e) All materials / rails removed by gas cutting shall be the property of the Railway and the contractor shall not be entitled to take away any cut rails / part thereof etc.
- (f) The contractor shall be responsible for safe custody of tools and plants being used by him and his labour. He shall ensure that the labour on work keep their tools clear off the track on the approach of the train. In no case labour be permitted to make tools to their homes and they should be asked to deposit them in proper tools boxes. The contractor should secure these tools in proper tools boxes, in such way that tools issued do not fall in unwanted hands who can temper with the railway track.
- (g) Gas cutting of rails will be required during block also and gas cutter with equipment and gas will remain available with throughout the block. The contractor will not claim any reasons, the work of contractor may be reduced / stopped decided by the engineer. The contractor shall not be entitled to prefer any claims for loss / damage suffered on this account.
- (h) The cuts should be vertical.
- (i) Above conditions apply for hacksaw cutting also. In above conditions, word gases, equipments shall be treated as hacksaw blade / mechanical cutting arrangements.
- (j) Longitudinal gas cutting if required shall be also done by contractor on his own expense.

#### **6.1 LONGITUDINAL GAS CUTTING:**

- (a) Longitudinal cutting will normally be required outside the traffic block but in some cases it may be in traffic block also.
- (b) The contractor may be asked to cut in any shape as per marking done by the SSE/P.WAY. Nothing extra will be paid for non straight cutting also.

#### **7.0 DRILLING HOLES IN RAILS:**

- (a) The above item of work envisages drilling of holes in rails on cess / running track of diameter as specified in the schedule at isolated locations / railway's nominated depots / stacks as per Railway's requirement and / or as directed





by the Engineer's his representative complete with handling of rails and all incidental works.

- (b) The nominated depots / stacks / locations for the purpose of this work shall have been inspected by the contractor before submitting the tender and the accepted rate is deemed to be inclusive of all leads, lifts, descents and incidental works.
- (c) Without in any way restricting or modifying the provisions of the General Conditions of Contract in this regard, the rates for the above quoted work shall be inclusive of all costs of contractor's tools & plants and machinery including drilling machines, drill bit, consumables, chamfering equipment etc. complete for the above.
- (d) The work shall be carried out strictly as per the Railways standard drawings and / or as given in the Indian Railway Track Manual and instructions laid down in IRPWM and the instructions of engineer or his representative whose decision in this regard shall be final and conclusive.
- (e) The finished diameter of the hole in the rail shall be as follows:
 

Rail Section	Hole diameter
60Kg., 52	32mm
90R, 75R, 60R	28mm
- (f) In addition to above following shall be adhered to:
  - (i) No punch or reaming / drifting will be permitted.
  - (ii) After drilling the hole, the same shall be chamfered with chamfering tools to remove burrs and for work hardening the hold as per directions of engineer's representative. (iii) The use of flame / gas cutting equipment is for hidden.
- (g) For all works on the running track or adjacent to running track, the protection of work site shall be ensured by the railway at its own cost. However, the contractor in addition will provide the necessary lookout men to ensure safety of his workmen/workwomen and the instructions given by Engineer or his representative in this regard and as stipulated in special conditions of contract should be strictly adhered to.

**8.0 SPECIFICATIONS OF FOLLOW UP (POST ATTENTION WORK) TO TSR, TRR & BEFORE EACH ROUND OF TTM PACKING i.e. SPACING, SQUARING OF SLEEPERS, GAUGING, BALLAST BOXING & DRESSING:**

- (a) All items incidentals to NS Item No. 1 shall be carried out by the contractor as per schedule to complete the work. Decision of site in-charge in this regard will be final.
- (b) Payment will be made per meter of track attended completely only once irrespective of no. of TTM.
- (c) The follow up work will be done after the rail renewal, TSR and before each round of TTM packing.

NOTE-A : Contractor should keep in mind that after each unloading of DMT ballast is required to be boxed along the sleepers, but ballast profiling shall be done in final round only.

NOTE-B : TTM packing shall be taken for granted for 4-5 rounds per C.T.R. sites. During each round, contractor shall be required to depute 8-10 staffs for pre-post TTM attention works.



- (d) All the PRC sleepers laid will be checked for the spacing and squaring. Sleeper spacing will be corrected so that it becomes  $60\text{cms} \pm 2\text{cm}$ . Squaring of sleepers will also be done simultaneously and it should not be more than 1cm out of square.
- (e) The work of correcting the spacing and squaring may be started on the day of laying itself and it must be completed within two days after laying. For example sleepers laid on 10th day must be completed by 12th day. If the work is not completed within this period, ballast may be unloaded and TTM packing may be done by the Railway and the labour input for doing correction of spacing and squaring may increase, for which nothing extra shall be paid.
- (f) In case the work of spacing and squaring is not completed within two days after laying, the Railway will be free to use its own labour for which penalty will be imposed @ Rs.2/- per meter.
- (g) Following instruction of pre-requisites, pre-tamping and post-tamping precautions shall be completed by contractor as per requirement.
- (h) PRE-REQUISITES FOR TAMPING: Adequate ballast shall be available in the cribs and shoulders to allow for a general lift (about 20mm in each tamping operations) and packing of sleepers.
- (i) PRE-TAMPING PRECAUTIONS:
  - (i) Rails shall be kept clear of ballast for about half of their height to ensure proper clamping of the rail head by lifting / lining rollers of the machine.
  - (ii) Rail clamps of the machine are not avail to grip the rail head wherever joggled fish plates are provided at the welds. These plates should be removed temporarily ahead of machine working and replaced after tamping.
  - (iii) Visibility of the end top of sleepers to the machine operator should be ensured.
  - (iv) Spacing and squaring of the sleepers should be checked and corrected.
  - (v) Gauge corrections should be carried out in advance to avoid alignment errors.
  - (vi) The fastenings must be complete and properly driven missing / defective ones' should be recouped / replaced.
  - (vii) Wooden blocks which are sometimes used as supports under the AT welds and at other isolated spots should be removed.
  - (viii) Unserviceable sleepers should be replaced with good ones.
  - (ix) Guard rails at the approaches of the girder bridges should be removed to enable the machine to tamp the approach of bridges.
- (j) CESS CLEANING/ DRESSING:
  - (a) The cess level shall be required to be maintained up to 650-700mm below rail level up to a width of 1.0m from toe of ballast. For this, required earth work will be done by the contractor subject to 150mm average cut / fill.
  - (b) Excess loose earth / vegetation on entire width shall be dressed and low lying area shall be filled up.
  - (c) All excess earth shall be thrown on the slope of cess.



**(k) POST TAMPING ATTENTIONS:**

- (i) The contractor will mark standard sleeper spacing on the foot of one rail by paint (the spacing is at present 60cm). The work will be transferred to the opposite rail with the help of P. Way T square.
- (ii) The contractor will then bring the sleeper to these marks of sleeper spacing by planting the crow bar firmly against the sleepers and pushing it. Under no circumstances should sleeper be hammered.
- (iii) Whereas the correct sleeper spacing is to be achieved as standard sleeper spacing some adjustment may have to be done to ensure that no sleeper should come under the welded joints. For this purpose Railway's representative of the site of work will give directives to contractor to adjust the sleeper spacing in such area as affected by the welded joints. No claim, whatsoever in this regard if made by the contractor will be entertained.
- (iv) Before taking the work of spacing and squaring in hand the contractor or his authorized representative should inspect the sleepers with the site in-charge of the work and if they find out any sleeper broken in the length of work in hand, the same will have to be changed at the time of doing spacing and squaring. The sleepers for replacement if required will be arranged and made available within 200m of the site of work by the Railways. Nothing extra shall be paid to the contractor for this work. If due to any reason the Railways are not in a position to supply sleepers on the day of post attention work the contractor will have to change such broken sleepers on any other day when the sleepers are made available by the Railways at the site. However, this should be done any day of the work of post attention after contractor may refuse to do this work.
- (v) After the sleepers are correctly spaced and squared contractor will provide standard complete fittings in sleepers. All the fittings, so required will, however, be given by the Railways at the SSE/P.WAY's store if such fittings are not already existing on any sleepers. For the correct accountal, daily counting of the existing fittings will be done by the contractor's representative jointly with Railways representative at the site of work to find out as to how many fittings are short. Only after this counting is done and entered into a proper register, the contractor will start his working.
- (vi) For proper follow up work, the contractor will remove all released / new rails lying along with the track in the length in which the work is to be done. (vii) After the operations of spacing, squaring and providing fittings, the contractor will correct the gauge to specified tolerances. (viii) The contractor will then pick up the ballast available in the shoulders, screen it with the help of 25mm square sieves and put it in between the two sleepers in the tamping zone for TTM working, where required. This work will be done as per directives of Railways representatives at the site who will have the sole authority to decide about the quantum and location of this work. This will however, depend on the availability of ballast in between the sleepers and outside. The remaining muck after sieving will be thrown on the cess slopes, nothing on the cess or in the side drains. The contractor will ensure that no ballast of size 25mm above is thrown away with the muck.

**9.0 INSERTION OF 60KG NEW SEJ:**
  
 DRM (W) JBP

CONTRACTOR



## For Part B

All items incidentals to NS Item No. 1 shall be carried out by the contractor as per schedule to complete the work. Decision of site in-charge in this regard will be final.

  
DRM (W) JBP

CONTRACTOR

**10.0 REMOVAL AND INSERTION OF PRC SLEEPERS (WITHOUT DEEP SCREENING):**

- (a) The above item of the work envisages interlacing of new sleepers in between the existing sleepers and removal of old sleepers along with complete fastening related work and packing of sleepers as specified in the schedule in the existing track at locations as per Railway's requirements and / or as directed by the Engineer or his representative complete with providing of rail sleeper fastenings etc. and all incidental works.
- (b) The tenderers in their own interest should visit the site of work with the concerned SE/P-Way / ADEN or with their authorized representative after fixing an appointment with them on advance and ascertain the nature and quantum of work, site conditions, availability of approach roads, availability of labours, water, electricity, land for labour camps etc.
- (c) Without in any way restricting or modifying the provisions of the General Conditions of Contract in this regard, the rate for the above quoted work shall be inclusive of all costs of contractor's labour, materials, consumables, tools and plants and machinery etc. complete for the schedule.
- (d) The measurements for payment shall be per schedule (Per Track Meter) and accepted by the Engineer or his representative.
- (e) The work shall be carried out strictly as per Railway's standard drawings, instructions laid down in IRPWM and the instructions of the Engineer or his representative whose decision in this regard shall be final and conclusive.
- (f) The work shall be carried out under the supervision of the Engineer incharge or his authorized representative under speed restriction.
- (g) Work will be done without traffic block, hence, all precautions are to be taken by the contractor so that trains can pass safely at 20 / 30 Km/h speed from site, without causing any detention to them. At least two sleepers must be available well packed on either side of sleeper being tackled for renewal.
- (h) Lifting of track is not permitted for inserting/removing PRC sleepers from track.
- (i) No damaged sleepers are to be put in track.
- (j) Removed 52Kg sleepers will be stacked properly on cess and not to be thrown haphazardly causing damage to them.
- (k) SH & U/S released PRC sleepers will be placed separately.
- (l) Disposal of muck/soil will be done within a lead of 200m as directed by site engineer.
- (m) The through sleeper renewal work shall be primarily done in following sequence. First, interlacing the new sleeper by removing shoulder and crib ballast from in between two sleepers and placing new sleepers there, fixing the inserted sleepers with new 60Kg/combinator/old fastenings as per availability. Thereafter removing the old 52Kg sleepers fastenings, removing shoulder ballast coming in the way of sleepers and lastly removing the sleeper without lifting the track at all and putting back the ballast and again packing.





- (n) The sleeper positions shall be marked on the rail foot by the contractor and sleeper should be inserted exactly at these locations without infringing the Railways SOD.
- (o) For handling sleepers standard equipments should only be used and it must be ensured that no damage is caused to the sleeper. In case of damage to the sleepers due to contractor's negligence, recovery will be made as per prevailing rates.
- (p) While laying concrete sleepers necessary steps have to be ensured to prevent seizure of ERCs in MCI inserts. All the ERCs and MCI inserts should be thoroughly cleaned. Grease to IS 408 1981 should be applied on the central leg of the ERC and eye of MCI insert and then these clip should be driven at the time of making the panels. The grease will be arranged by the contractor at his own cost.
- (q) Removing sleeper-rail fastenings and removing the sleepers from the track (including here, minimum removal of 50mm ballast below the bottom of sleeper being inserted if work is not possible by interlacing first).
- (r) Putting back the ballast so removed into track after the insertion of the sleeper.
- (s) Initial packing of the sleeper so inserted so as to maintain track geometry as directed by engineer-in-charge.
- (t) Sleepers and the fittings removed during the operation should be stacked as directed by the engineer in-charge. Payment for extra leads for more than 200m, if any will be made under the relevant items of the schedule.
- (u) For all works on the running track or adjacent to running track, the protection of work site and the workmen shall be ensured at all times and the instructions given by Engineer or his representative as given in special conditions of contract should be strictly adhered to.
- (v) All scattered ballast of crib and shoulder shall be put back by contractor at his own cost.
- (w) Sleepers shall be packed to ensure safety of track for 30 Kmph.
- (x) The released fittings shall be stacked at one place (within 200m of lead).
- (y) In case combination liners are not available, at the time of sleeper renewal, then old 52Kg/new 60Kg fastening shall be used. While doing so contractor shall follow the instructions : "Here every 5th old sleepers shall be left in the track till combination liners for at least these sleepers are arranged by Railways." However, these sleepers shall be replaced by 60Kg sleeper before rail renewal by 60Kg by contractor.
- (z) T-3741 and T-3742 (T-3707 and T3708) : Combination liners shall be painted by red colour and yellow colour respectively for easy identification and fixing on rail sleepers. This work will be done by Railways.
- (zi) Work of fixing of combination liners may be required to be done at later stage subject to its availability at site, for which no extra payment shall be made to the contractor.

**12.0 SPREADING OF PRC SLEEPERS AND FABRICATION OF 12.6 TM LONG RAIL PANELS:**



## For Part B

The work of fabrication of panels will include spreading of PRC sleepers and linking of 52Kg / 60Kg 12.6 meters rail or any other suitable length panels as specified by the Engineer with PRC sleepers linked with standard fastenings i.e. pandrol clips, rubber pads and liner etc. at correct spacing of 60cms center to center of sleepers.

- (i) The rubber pads will be fixed to PRC sleepers using Khandelwal synthetic glue or any other glue approved by the Engineer. The glue will be arranged by the contractor at his own cost.
- (ii) Spacing for linking will be marked on the rails with a fine paint by the contractor under the supervision of SSE/P.WAY in-charge of fabrication depot and the sleepers will have to be laid at the specified spacing of 60cms each (center to center of sleepers). One panel will mean 2 rails of 52Kg/60Kg 12.5m length (or any other length as specified by the Engineer linked with PRC sleepers with standard fastening at specified spacing of 60cms. The contractor will ensure that the PRC sleepers are laid square in the rail. The contractor will also ensure that ends of rails are also kept square.
- (iii) The contractor shall first lift PRC sleepers from stacks & spread them on the same track by using mechanical equipments. Mechanical means like road crane, mechanical gantries etc. The contractor shall lift PRC sleepers from the track, carry them to the site specified for fabrication of panels on the same track and put them over the rail / panels centrally so that PQRS portals can pass over them without any infringement. The spreading of PRC sleepers will be done by the contractor on the existing or over already linked PRC panels up to a maximum of 8 tiers (one tier for this purpose will mean a rail linked on PRC sleepers). The maximum lead of PRC sleepers from the stack to the site of spreading will be limited to 600 meters. Nothing extra shall be paid to the contractor for lift and lead as specified above. The contractor shall therefore, quote his rates keeping in view that all machinery like gantries etc. operators, labours, fuel etc. will have to be arranged by him at his own cost for lifting PRC sleepers from stacks, leading them to site and spreading them as specified including all lead & lift and nothing extra shall be paid on any account. In case the contractor does not spread the sleepers centrally to track and his causes infringement to the movement of portal cranes on that track, necessary adjustment of PRC sleepers shall be made by deploying departmental labour, the cost of which shall be recovered from the contractor. The decision of Engineer-in-charge of the work shall be final in this regard and shall be binding on the contractor.
- (iv) After spreading PRC sleepers, the contractor shall bring service rails with a maximum lead up to 600 meters along the same track, lift service rails from ground, put them over PRC sleepers spread by him and link the rails and sleepers at correct spacing after providing rubber pads and fittings. The linking of panels will be done up to maximum of 8 tiers one over the other. Nothing extra shall be paid for leading, lifting, adjustment, slewing of rails / sleepers / fittings for fabrication of panels except for spreading of PRC sleepers. This aspect should therefore, be kept in mind by the tenderer while quoting rates. Minor slewing / shifting of PRC sleepers may be done manually.
- (v) The elastic rail clips (ERC) shall be lubricated by the contractor with grease of approved quality before fixing the rails on the sleepers with the help of ERC. The material required for the greasing shall be arranged by the contractor at his own cost. Nothing extra shall be paid to the contractor on this account.



- (vi) The contractor shall be required to fabricate adequate number of panels per day as instructed by SSE/P.WAY / ADEN Incharge of the work. In the initial stage service rails for linking of panels will be supplied at site by the Railways. Later on these will be available from dismantled panels.
- (vii) The quality of fabricated panels i.e. squaring and spreading of sleepers, proper positioning of fittings lubrication of ERCs, squaring of rail ends shall be to the entire satisfaction of SSE/P.WAY / Fabrication depot and the engineer in-charge to the work.
- (viii) Grease, paint, anticorrosive paint etc. consumable required in the works shall be deposited by the contractor in advance to SE/P-Way In-charge depot and the same shall be issued to contractor for work as requirement. The contractor shall transport the same at their own cost.

### **13.0 LOADING OF FABRICATED PANELS OF 12.6 TM LENGTH PANELS ETC.**

- (i) Fabricated panels which are stacked one above the other will be lifted carried and loaded on the BFRs / BRHs placed on the same track.
- (ii) The contractor will have to load panels in such a way every day so that total no. of panels on PQRS rake are not less than 40, if otherwise not prevented by Railway's representative.
- (iii) Panels will be loaded on BFRs / BRHs in maximum of 4 layers.
- (iv) Maximum lead involved will be 450 meters only.
- (v) The PQRS rake will be placed in the yard any time after the block. The contractor will first unload released panels and then load fabricated panels.
- (vi) The loading of fabricated panels must be completed before 5.00 hrs. In case the rake is placed after sun set, the contractor will have to work during night for which he shall make his own arrangements for lighting.
- (vii) Fabricated panels will include intermediate stacking of panels in 3-4-5 layers on ground prior to loading panels into BFR.

### **14.0 UNLOADING OF 12.6 TM LONG RELEASED PANELS ETC. :**

- (i) After the block, the PQRS rake will be placed in the PQRS yard and the contractor will unload the released panels and stack them on the same track at specified place.
- (ii) Portals or mechanical gantries required for unloading of released panels will be arranged by the contractor at his own cost.
- (iii) The unloading of 40 released panels will have to be done every day.
- (iv) The unloading of released panels will be done soon after placement and will be completed in such a manner that fabricated panels are also loaded before 05.00 hrs. for next day block.

### **15.0 DISMANTLING OF 12.6M LONG RELEASED PANELS ETC. :**

- (i) Simultaneously, contractor shall do the work of dismantling released panels received from site 12.6 meter or any other length of 52Kg / 60Kg panels with PRC sleepers after they are unloaded by portals / mechanical gantries. The contractor will sort out U.S. and S.S. materials out of released as per direction of SSE/P.WAY In-charge and will then stack released PRC sleepers at places specified for staking by the SSE/P.WAY Incharge of the depot in the yard (but within 500 meters of the place of dismantling).



- (ii) In addition the contractor shall remove service rails from the released panels and will lead them to the place where fabrication of panels with PRC sleepers is to be done. (Nothing extra shall be paid on this account) and the rates for dismantling of released panels must include dismantling out, leading stacking as well as leading of service rails, to fabrication points. The leading of service rails including extra rails brought over the panels will, however, be along the same track and up to a maximum of 450 meters (xing of track other than the one on which work is being done will not be required to be done by the contractor). Nothing extra shall be payable for handling leading and stacking of extra rails brought over the panels.
- (iii) The work will normally be done during sun rise to sun set if dismantling of released panels and formation of new panels is done at night at contractor's choice, lighting arrangement if needed will be arranged by the contractor at his own cost and nothing extra shall be payable on this account.
- (iv) The released material shall be stacked on the space earmarked for stacking purposes by the SSE/P.WAYIncharge of the work. One released panel will mean 2 rails of 52Kg linked with PRC sleepers. In addition 2 to 4 more service rails of 52Kg / 60Kg may be brought loaded over these panels which will also be handled by the contractor without any extra payment. The fittings and fastenings of rails with sleepers released from panels will be stacked at places specified by SSE/P.WAYIn-charge.
- (v) New materials required for fabrication of panels will be issued to contractor by SSE/P.WAY / Fabrication depot in the PQRS yard.
- (vi) The contractor will be required to dismantle 30 panels per day (depending upon availability of released panels for dismantling).

#### **16.0 MECHANICAL / MANUAL LOADING OF RAILS :**

- (i) The entire work of loading of rails will be done in base depot either in BFR's or trailorunder the same item NS-1 under the supervision of railway's representative. The contractor should closely examine and inspect the site of work and condition prevailing therein before quoting his rates.
- (ii) The work will be under taken between sun rise to sun set. However, the contractor will be free to do loading during night but for this purpose no lighting arrangement will be made by the Railways. Any lighting arrangements if required will be arranged by the contractor. Nothing extra shall be payable to the contractor on this account.
- (iii) The loading of rails will be done by the contractor in Railway BFR/BRH/other type of open stock. In every case the wagons/BFRs so supplied for loading will be open from the top, so that the rails can be kept on them from the top.
- (iv) The rails which are required to be loaded will be available either inside the track or near the track in the PQRS base depot.
- (v) The rails required to be loaded will be brought by the contractor and loaded directly on to the BFR/BRH/other wagons supplied for this purpose. (The overall lead of the stack of the rails from which the rails are required to be picked up and loaded, will be confined to a maximum of 450 meters. The distance will be measured from the center of the BFR / BRH or other stock in which the rails are to be loaded to the point along with the track where the rails are lying.



- (vi) The Railway shall ask the contractor to load only ordinary rails which can be directly put on the BFR / BRH / other stock from top. If the rails are longer in length, the cutting required, if any, will be done by the contractor shall be paid separately.
- (vii) The BFR / BRH / Wagons will be placed by the Railway as available and required for loading. The contractor will have no claim for a regular supply of BFR / BRH / Wagons for loading as the same will be arranged as available and no claim on this account will be entertained. The contractors should, therefore, quote their rates keeping this aspect in view. Further the BFR / BRH / Wagons may be placed in any line as convenient to the railways and contractor shall have no claim for any particular placement of wagons for loading.
- (viii) Handling of service rails etc. brought or released panels shall be done by contractor for which no extra shall be paid.

**17.0** (i) All the released fittings will be deposited in the store of SSE/P.WAY In-charge.

- (ii) Loss of any tool / plant if any will have to be made good by the contractor at the following rates:

"Either in book rate or purchase rate of the particular items whichever is higher + 5% freight, 2% incidental charges and 12-1/2% supervision charges on the rates."

The contractor shall be responsible for safe custody of tools and plants used by him and his labour. He should ensure that labour on work remove their tools clear of the track on the approach of the train. After the day work, the contractor should secure tools in proper tools to their homes. Tools issued shall not be allowed to go in unwanted hands, who can tamper with the Railway track.

- (iii) The contractor shall employ one suitable supervisor at the site of work at his own cost. The name along with technical qualifications of such supervisor should be advised to engineer incharge. If in the opinion of the engineer incharge of the work, the supervisor is not fit to be incharge of the work, he should be forthwith replaced. In the matter the opinion of the engineer incharge will be final & binding on the contractor.
- (iv) The contractor will be responsible to ensure the safety of his workmen and tools during the operation of work and nothing will be left infringing the track at the time of passing of train. Safety of contractor's men working on the track is the responsibility of the contractor and railway will in no case be responsible for compensation required to be paid to the contractor's men in the event of any accident / mishap.

**18.0 UNLOADING OF RAILS/SLEEPERS FROM DMT / HD, QRS. AT SITE :**

- (a) The contractor will be required to unload PRC sleepers normally from KCMs/BFRs/other stocks during traffic block either in block section or in yards etc.
- (b) Sleepers will be unloaded as per direction of SSE/P.WAY/In charge who will decide the location and no. of PRC sleepers to be unloaded in block section. Approximate 110 sleepers shall be unloaded in between OHE / Masts = (70m).



- (c) The work will not be continuous and will be done only when engine and PRC sleepers are available. The contractor will have no claim due to this.
- (d) Traffic block may not be given when unloading is planned and it may cause wastage of labour of the contractor but nothing extra will be paid on this account.
- (e) All the PRC sleeper unloaded must be kept clear off ballast section of the track. No sleeper will be left on shoulders of ballast. Sleeper shall be stacked on cess approx. parallel to existing sleeper in track.
- (f) All the rails unloaded from rail DMT 10/20 rail panels must be put at safe distance from running track while unloading. Sufficient labours should be provided for unloading as well as for clearing the track.

**19.0 DESTRESSING OF TRACK:**

Destressing of track involves following items :-

- (i) Work shall only be undertaken after Speed restriction of 30 Kmph shall be imposed by the Railways.
- (ii) Closure rails shall be introduced in a traffic block by Railways.
- (iii) Fastening on alternate sleepers are loosened under the speed restriction of 30 Kmph.
- (iv) Traffic block of adequate length shall be arranged at such a time when rail temperature is within distressing temperature, then no tensor is required. Otherwise tensor shall be used. Labour for tensor operation only shall be provided by Railways.
- (v) When the block is taken then closure rail shall be removed, SEJ adjusted and fastened in their mean position by contractor.
- (vi) The sleeper fastening on the both running rails shall be removed and rail shall be lifted and placed on rollers at every sleeper to permit the rails to move freely. The rails shall be struck horizontally with heavy wooden mallets to assist their horizontal movement. After this operation, if extension is required then required extensions shall be done by SSE/P.WAY with tensor.
- (vii) If rubber pads are required to be changed then these should be changed at this stage while the rails are still on lifted position by contractor.
- (viii) The rollers shall then be removed, the rail lowered to alignment and other same or new fastenings (pendrols, liners etc.) are provided and tightened as directed by SSE/P.WAY.
- (ix) Cut rails between SEJ & LWR shall be provided simultaneously and welding etc. shall be done by Railways.
- (x) No Extra payments for renewed of rubber pads, shall be made to the contractor. The contractor shall not start any work without personal presence of the SSE/P.WAY at site. In case the contractor or his representative starts any work in absence of SSE/P.WAY, it shall be treated as unauthorized and illegal tampering with the track and shall be liable for action under Indian Railway Act.

**PENALTIES:**

- (a) In the event of accident at the work site, the departmental enquiry will be held and in case it is established with that the derailment has occurred on





account of the contractor's negligence or the negligence of his men, penalties up to an upper limit of 10% of the total cost of the work shall be imposed in case there is accident for which the contractor is responsible. All losses and compensation as a result of Court's orders in case of accident due to fault of contractor or his men will be responsibility of contractor, irrespective of value.

- (b) Railway administration reserves the right to terminate the contract with immediate effect if the contractor is found responsible for the accident without giving any further notices to the contractor.
- (c) In the event of loss of any of the existing fittings and fastening in track due to contractor's working, the contractor will have to pay cost of materials at the prevailing rates fixed by the Railways + 19.5%.

#### 20.0 TOOLS & PLANTS:

- (i) The contractor shall make his own arrangements for all the tools required for the work.
- (ii) The wooden handles subsequently required for replacement will have to be arranged by the contractor at his own cost. Cane baskets for loading of small fittings will have to be procured by the contractor at his own cost.
- (iii) Loss of tools and plants due to contractor, if any will have to be made good by the contractor at the following rates: Either the book rate or purchase rate of that particular item whichever is higher + 5% freight + 2% incidental charges + 12.5% supervision charges on this rate.
- (v) The contractor shall be responsible for the safe custody of tools and plants being used by him or his labour. He shall ensure that the labour on the work keep their tools safe and are not permitted to take tools to their homes and they should be asked to deposit them in proper tool box before they leave the Railway premises. The contractor should ensure that these tools are not kept in such a way that they fall in unwanted hands who can tamper with the railway track.
- (vi) The tools / rail dolly / diplorry / roller etc. issued to the contractor will have to be repaired by the contractor at his own cost for which a temporary workshop may have to be set up at site. All materials required for reconditioning of these tools will have to be arranged by the contractor at his own cost and nothing will be paid on this account.
- (vii) Tarpaulins / choldaries required for accommodating contractor's staff will have to be provided by the contractor at his own cost.