

Scope of work

Name of work:- Dadar (NSG 1) PF 12 / Kurla (SG 1) PF 1, 2, 3, 4-5 & 6, 7 & 8 / Mankhurd (SG 1) PF 1 & 2 / Nahur (SG 2) PF 1/2 / Mulund (SG 1) PF 1, 2/3, 4 / Thane (NSG 1) PF 7/8 and Kalva (SG2) PF 1 & PF 2 (Total 7 Stations) - Raising / Resurfacing of Platforms.

Raising and resurfacing at PF 1 & 2 / Nahur (SG 2) PF 1/2 / Mulund (SG 1) PF 1, 2/3, 4 / Thane (NSG 1) PF 7/8 and Kalva (SG2) PF 1 & PF 2.

1. Raising to be done of platform height as per IRSOD provision.
2. Provision of kota stone tiles, chequered tiles etc.
3. Provision of tactile tiles for indication of disabled passenger.
4. Provision of RCC coping to increase the suitable height as per IRSOD provision.
5. Adjustment of coping distance from track center as per IRSOD provision.
6. Repairs to the water booths at platform.
7. Replacement of damaged COP drainage pipes.
8. Repairs to COP chambers.
9. Plastering of platform walls.
10. Muck removal from site.


J. S. S. E. / W. K. S. T. N. A.

Scope of work

NAME OF WORK: - Raising and Resurfacing of Platform Surface of Platform No 12 at Dadar Station Under SSE (WKS) DR Under ADEN (Wks) BY

1. Repair precast coping
2. PCC Work
3. Repair chamber work
4. Repair Down take pipe
5. Coping tile work
6. Platform surfacing with Kota stone work
7. Repairs seating arrangement
8. Coping wall finishing and painting work
- 9 . Repairs to water stand
10. Coping wall plaster


SSE(Wks)Dadar
वरिष्ठ सेक्शन इंजिनि. (कार्य) दादर, मध्य रेल
SSE (W), Dadar Central Railway

SCOPE OF WORK

NAME OF WORK :- Raising and Resurfacing of Platforms at Mankhurd PF No. 1/2,

CLA PF No 1/2 , 3/4 ,5/6 7/8 under ADEN (Wks) BY

1. Repair Precast coping.
2. PCC work.
3. Repair Chamber work
4. Repair down take pipe
5. Coping tile work
6. Platform surfacing with Kota work
7. Repairs seating arrangement
8. Coping wall finishing and painting work
9. Repairs to water stand
10. Coping wall plaster

by law
SSE(Wks)CLA