

Tender Schedule No: **EL\_TRD\_06\_26-27**

Name of Work:-Electrical TRD work inconnection with "OHE Non-core activity work under jurisdiction of ADEE/TRD/NJP (OHE depot NJP, AUB, DLK & BORA) of katiyar division for a period of 24 months."(OHE Non-core activity related work)

I/We agree to execute the above work mentioned as per general & special condition of Contract and as per RDSO's approved specification for Electrical works of N.F.Railway.

SN	Description of work	Qty.	Unit	Unit Rate ( In Rs. )	Total amount ( In Rs. )
<b>Schedule-I (OHE Non-core activity related work)</b>					
1	Tree trimming to maintain a minimum clearance from OHE. One big branches consisting of 5 small sub branches	2000	Branches	74.14	148280.00
2	Providing and laying of concrete for repairing of muffing, foundation and plinth of mast.	160	Cum	10752.61	1720417.60
3	Supply of Longitudinal bond (including black painted MS Flat and required nut,bolts spring washer.	3000	Nos.	693.15	2079450.00
4	Supply of structure bond(including black painted MS Flat and required nut,bolts spring washer	5000	Nos.	1129.51	5647550.00
5	Supply of cross/tranverse bond and special bond (including black painted MS Flat and required nut, bolts, spring washer)	1500	Nos.	1115.03	1672545.00
6	Replacement/Erection labour cost of various type of damaged or rusted bond	9500	Nos.	144.23	1370185.00
7	Supply & erection of Galvanised steel flexiblewire bond for traction with lug as perRDSO's Drg (For Lug) TI/DRG/GTHLUG/RDSO /00001/04/0duly crimped on both ends of eachbonds and RDSO SPCN No.TI/SPC /OHE/GALSTB /0040 with A&Cslip no. 1/(8/2005) for various lengthof each bond complete with lugs- 4.5Mtr	1000	Each	3047.83	3047830.00
8	Supply & erection of Galvanised steel flexiblewire bond for traction with lug as perRDSO's Drg (For Lug) TI/DRG/GTHLUG/RDSO /00001/04/0duly crimped on both ends of eachbonds and RDSO SPCN No.TI/SPC /OHE/GALSTB /0040 with A&Cslip no. 1/(8/2005) for various lengthof each bond complete with lugs- 7.0Mtr	750	Each	4214.35	3160762.50

9	Supply & erection of Galvanised steel flexible wire bond for traction with lug as per RDSO's Drg (For Lug) TI/DRG/GTHLUG/RDSO/00001/04/0 duly crimped on both ends of each bonds and RDSO SPCN No.TI/SPC/OHE/GALSTB/0040 with A&C slip no. 1/(8/2005) for various length of each bond complete with lugs- 3.0Mtr.	1200	Each	2103.15	2523780.00
10	Supply & erection of Galvanised steel flexible wire bond for traction with lug as per RDSO's Drg (For Lug) TI/DRG/GTHLUG/RDSO /00001/04/0 duly crimped on both ends of each bonds and RDSO SPCN No.TI/SPC /OHE/GALSTB /0040 with A&C slip no. 1/(8/2005) for various length of each bond complete with lugs- 3.5Mtr	600	Each	2494.36	1496616.00
11	Supply of Paint & Painting of various types of bonds.	1000	Litres	282.29	282290.00
12	Stencilling of OHE parameters on OHE structures.	3750	Locations	125.08	469050.00
13	Extra Earthwork/soil in filling at SWS, TSS and OHE Foundations	120	Cum	322.63	38715.60
14	Removing bird nest/kites/plastics from OHE (10Nos./Month x 24 Months = 240 Nos.	2000	Nos	82.76	165520.00
15	Supply and ATD counter weight and guy rod and guy tube painting in electrified section with Aluminium paint from any of RDSO approved brand paint. i.e; Asian/Berger make paint confirming to IS:2339 or latest.	700	litres	111.02	77714.00
16	Dead section caution board (Retro reflective type) Caution unwired turnouts) as per RDSO spec. ETI/OHE/33A rev.6 or latest.	50	Nos.	2845.59	142279.50
17	Enamelled warning board (caution live wire) as per RDSO spec. ETI/OHE/33(8/85) or latest.	50	Nos.	897.87	44893.50
18	General caution board (enameled) for staff as per RDSO spec. No ETI/OHE/33(8/85) or latest.	50	Nos.	389.18	19459.00
19	Supply & erection of retro-reflective structure number plate .ETI/OHE/33A(12/97) Rev-6.	100	Nos.	983.49	98349.00
<b>Sub total Schedule-I</b>					<b>2,42,05,686.70</b>

I/We offer to do the work

1. At Par, or

2. ( + ).....% (in fig.)...

( In words) above, or,

3. ( - ).....% ( in fig.)...

( In words) below the

Railway's Rate of each and every item of Schedule of Work.

Rebate if any on (a) Schedule of

Strike out whichever is inapplicable.

**Special Conditions:-**

- 1 All damage caused during the execution of work shall be made good to original finish.
- 2 The approximate estimated quantities of various items of works are included in schedule of quantities and rate.  
However , quantities can be increased /decreased beyond 25% if required and decided by competent authority as per extant variations rules.
- 3 The contractor shall remain fully responsible for ensuring safety his staff while working. In case of any injury/death occurs, no compensation will be paid by Railway.
- 4 The contractors are advised to provide / mention their contact nos. (Telephone/Mobile nos of self, their supervisor and staffs) to Railway officials as soon as Contract is awarded. The contact Telephone/Mobile no. should be in working for 24 x 7.
- 5 The contractor may be terminated by the Rly administration by giving 07 days notice prior if the service is not found satisfactory. Decision of officers incharge / Railway official incharge of the above work in this regard shall be final and binding.
- 6 Railway is not liable, in any way, to give bonus, advance or any other mode of payment to the contractor's staff. These liabilities will be upon the contractor only.
- 7 No TA/DA or any sort of other traveling facility will be provided to the contractor or to his authorized staff for undertaken Railway journey in connection with this contract.
- 8 The Contractor shall comply with the provision of the i) contract labour (Regulation and Abolition) Act, 1970 ii) Contract labour (Regulation and Abolition) Central Rules 1971 iii) provisions of Para 30 & 36-B of the Employees Provident Fund Scheme, 1952 iv) provisions of Section 12 Sub-Section (1) of the Workmen's Compensation Act 1923 and follow all Labour's law / rules as given in Standard General Conditions Of Contract 2014 of Indian Railway with latest amendments.

- 9 Contractors shall not in any capacity employ any person of bad character or any person whose antecedents have not been investigated by the Police. A copy of the Police verification certificate of all the labour engaged shall be submitted with the concerned CPS. He shall issue an appointment certificate, which shall contain a photograph of the employee specifying the employee's name, father's name, address and the place at which employed, with/his/her left/right hand thumb impression affixed thereon in printer's ink which he will carry with him/her while on duty. The expenses for such verification as is necessary shall be borne by the Contractor.
- 10 The contractor should provide proper uniform and I/Card to each of the loaders. Labours should be in proper uniform and Identity Cards are to be prominently displayed. Cost of such incurrence would be borne by the contractor and no extra cost would be paid by the Railways.
- 11 The Contractor shall provide at his own cost all his labourers and his employees with necessary tools, instruments and equipments regarding the nature of works of schedule.
- 12 Contractor has to keep their tools, instruments and equipments in their own custody at the space to be provided by railways. Theft or any unusual occurrence will be the full responsibility of the contractor.
- 13 Senior section engineer (in charge) of concern or their nominated representative shall be responsible for inspection of material and supervision of this contract and for certifying the quantum for purposes of payment of the contractor's bills.
- 14 Contractor shall be liable to compensate the Railway administration for all damages and losses that may be caused to electrical or other property belonging to the Railway Administration whether in his possession or not, through his negligence, misconduct, default or any other act of commission or omission or that of his agents, servants or employees.
- 15 There shall not be any deviation from Electrical drawing and specification with out prior approval of Competent Authority.
- 16 Only RDSO/CORE approved vendor material should be used. Material test certificate/report of approved vendor will be required while installation and handing over the material to railway.
- 17 As per RB's guidelines, RITES inspection / company inspection to be carried out by contractor with own cost. If applicable. The material should be pre inspected by RITES/Third party as per railway board letter no 2000/RS(G)/379/2 dated 06.09.2017 ,the cost of which shall be borne by the contractor.
- 18 All the released material shall be handed over to the concerned SSE/TRD of the section in the safe condition after completion of work/before final bill. The contractor will submit the certificate jointly signed by concerend SSE/TRD of section and contractor stating that all the released material has been received correctly in safe condition.
- 19 **Penalty:-**
  - i) Rs.5000/-for adopting any misconducting, alcohol consumption
  - ii) Rs.1000/- will be recovered for not wearing specified uniformor safety gadget per staff per day.
  - iii) In case of any damage of Railway property, same amount will be recovered from the contractor.

- 20 If there is any conflict between “Special conditions” and “General conditions of contract for services -2018 and its amendments”, the conditions laid down in “General conditions of contract for services -2018 and its latest amendments” will be sustained.

**Signature:**