

SPECIAL CONDITIONS REGARDING THE EXTENSION, RAISING & RESURFACING

1. Traffic block will be provided, as per availability, for unloading of stone/quarry dust. Sufficient numbers of skilled labours (minimum 50 Nos.) must be available to obtain the maximum output in a block.

In case block is not availed due to non-provision/inadequate numbers of labours by the contractor, then operating cost including hire charges of Engine and crew etc. will be deducted.

2. Bar chart corresponding to the milestone showing detailed deployment plan of required resources to be submitted.
3. Work must be started at all locations simultaneously & must be in progress simultaneously at all locations. Delay in execution of work at any site will be treated as delay of the whole contract irrespective of work done/progress at other locations in same contract.

4.1 Milestone to be followed at **Bahanagabazar, where 'D' = Date of LoA.**

- (i) Survey and preparation of working drawings including PF, toilet blocks etc. – D + 10 days
- (ii) Physical start of work at site – D + 15 days
- (iii) Construction of PF wall & retaining wall – D + 75 days
- (iv) Casting & placement of coping – D + 105 days
- (v) Backfilling – D + 145 days
- (vi) PF shelter including sheeting, painting & PF benches – D + 190 days
- (vii) Water supply – D + 205 days
- (viii) Cable duct at edge of PF & construction of toilet – D + 230 days
- (ix) Final finishing and painting – D + 240 days

4.2 Milestone to be followed at **Ranital, where 'D' = Date of LoA.**

- (i) Survey and preparation of working drawings including PF, toilet blocks etc. – D + 10 days
- (ii) Physical start of work at site – D + 15 days
- (iii) Construction of PF wall & retaining wall – D + 75 days
- (iv) Casting & placement of coping – D + 105 days
- (v) Backfilling – D + 145 days
- (vi) PF shelter including sheeting, painting & PF benches – D + 190 days
- (vii) Water supply – D + 205 days
- (viii) Cable duct at edge of PF & construction of toilet – D + 230 days
- (ix) Final finishing and painting – D + 240 days

4.3 Milestone to be followed at **Nilgiri, where 'D' = Date of LoA.**

- (i) Survey and preparation of working drawings including PF, toilet blocks etc. – D + 10 days
- (ii) Physical start of work at site – D + 15 days
- (iii) Construction of PF wall & retaining wall – D + 75 days
- (iv) Casting & placement of coping – D + 105 days
- (v) Backfilling – D + 145 days

- (vi) PF shelter including sheeting, painting & PF benches – D + 190 days
- (vii) Water supply – D + 205 days
- (viii) Construction of toilet – D + 230 days
- (ix) Final finishing and painting – D + 240 days

4.4.1 Milestone to be followed at Khantapara (PF-1), where ‘D’ = Date of LoA.

- (i) Survey and preparation of working drawings including PF, toilet blocks etc. – D + 10 days
- (ii) Physical start of work at site – D + 15 days
- (iii) Construction of PF wall & retaining wall – D + 75 days
- (iv) Casting & placement of coping – D + 105 days
- (v) Backfilling – D + 145 days
- (vi) PF shelter including sheeting, painting & PF benches – D + 190 days
- (vii) Water supply – D + 205 days
- (viii) Cable duct at edge of PF & construction of toilet – D + 230 days
- (ix) Final finishing and painting – D + 240 days

4.4.2 Milestone to be followed at Khantapara (PF-2), where ‘D’ = Date of LoA.

- (i) Survey and preparation of working drawings including PF, toilet blocks etc. – D + 10 days
- (ii) Physical start of work at site – D + 75 days
- (iii) Construction of PF wall & retaining wall – D + 135 days
- (iv) Casting & placement of coping – D + 165 days
- (v) Backfilling – D + 205 days
- (vi) PF shelter including sheeting, painting & PF benches – D + 250 days
- (vii) Water supply – D + 265 days
- (viii) Cable duct at edge of PF & construction of toilet – D + 290 days
- (ix) Final finishing and painting – D + 300 days

4.4.3 Milestone to be followed at Khantapara (PF-3/4), where ‘D’ = Date of LoA.

- (i) Survey and preparation of working drawings including PF, toilet blocks etc. – D + 10 days
- (ii) Physical start of work at site – D + 135 days
- (iii) Construction of PF wall & retaining wall – D + 195 days
- (iv) Casting & placement of coping – D + 225 days
- (v) Backfilling – D + 265 days
- (vi) PF shelter including sheeting, painting & PF benches – D + 310 days
- (vii) Water supply – D + 325 days
- (viii) Cable duct at edge of PF & construction of toilet – D + 350 days
- (ix) Final finishing and painting – D + 365 days