

**MUMBAI- CST-DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-DRMWBB-2026-32-01

Closing Date/Time: 14/07/2026 15:00

DRM W BB acting for and on behalf of The President of India invites E-Tenders against Tender No **CR-DRMWBB-2026-32-01** Closing Date/Time 14/07/2026 15:00 Hrs. Bidders will be able to submit their original/revised bids upto closing date and time only. Manual offers are not allowed against this tender, and any such manual offer received shall be ignored.

1. NIT HEADER

Name of Work	Raising / Resurfacing of Platforms at Ambivli (SG 2), Vasind (SG 3), Asangaon (SG 3), Khadavali (SG 3), Thansit (SG 3), Umbermali (SG 3) & Khardi (SG 3) (Total 7 Stations).		
Bidding type	Normal Tender		
Tender Type	Open	Bidding System	Single Packet System
Tender Closing Date Time	14/07/2026 15:00	Date Time Of Uploading Tender	13/06/2026 14:03
Pre-Bid Conference Required	No	Pre-Bid Conference Date Time	Not Applicable
Advertised Value	75918409.43	Tendering Section	SR DEN NE
Bidding Style	[Decision at Schedule level]	Bidding Unit	
Earnest Money (Rs.)	1518400.00	Validity of Offer (Days)	60
Tender Doc. Cost (Rs.)	0.00	Period of Completion	9 Months
Contract Type	Works - General	Contract Category	Expenditure
Bidding Start Date	30/06/2026		
Are JV allowed to bid	No	Number of JV Member Allowed	0
Are Consortium allowed to bid	No	Number of Consortium Member Allowed	0
Ranking Order For Bids	Lowest to Highest	Expenditure Type	Capital (Works)

2. SCHEDULE

S.No.	Item Code	Item Qty	Qty Unit	Unit Rate	Basic Value	Escl.(%)	Amount	Bidding Unit
Schedule () 1-- Ambivli (SG 2), Vasind (SG 3), Asangaon (SG 3), Khadavali (SG 3), Thansit (SG-3), Umbermali (SG-3) & Khardi (SG-3) (Total 7 Stations) - Raising / Resurfacing of Platforms.							75918409.43	
1	Please see Item Breakup for details.				51573307.00	(-) 24.59	38891430.81	Above/ Below/Par
	Description:- Part-A DSR-2023:- Raising / Resurfacing of Platforms at Thansit,Umbermali & Khardi							
2	Please see Item Breakup for details.				49100886.65	(-) 24.59	37026978.62	Above/ Below/Par
	Description:- Part-B DSR ITEM:- Raising / Resurfacing of Platforms at Ambivali, Vashind, Asangaon, Khadavali							

3. ITEM BREAKUP

Schedule	Schedule 1-- Ambivli (SG 2), Vasind (SG 3), Asangaon (SG 3), Khadavali (SG 3), Thansit (SG-3), Umbermali (SG-3) & Khardi (SG-3) (Total 7 Stations) - Raising / Resurfacing of Platforms.					
Item- 1	Part-A DSR-2023:- Raising / Resurfacing of Platforms at Thansit,Umbermali & Khardi					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
	2.0	EARTH WORK				
	2.1S	General				
	2.6	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge.				

**MUMBAI- CST-DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-DRMWBB-2026-32-01

Closing Date/Time: 14/07/2026 15:00

1	2.6.1	All kinds of soil	cum	250	177.5	44375
2	2.25	Filling available excavated earth (excluding rock) in trenches, plinth, sides of foundations etc. in layers not exceeding 20 cm in depth, consolidating each deposited layer by ramming and watering, lead up to 50 and for all lift.	cum	60	196	11760
	4.0	CONCRETE WORK				
	4.1S	CEMENT CONCRETE (CAST IN SITU)				
	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
3	4.1.3	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	1575	7878.5	12408637.5
4	4.1.5	1:3:6 (1 Cement : 3 coarse sand (zone-III) derived from natural sources : 6 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	20	7294.7	145894
	5.0	REINFORCEMENT CEMENT CONCRETE				
	5.9S	FORM WORK				
	5.9	Centering and shuttering including strutting, propping etc. and removal of form for				
5	5.9.1	Foundations, footings, bases of columns, etc. for mass concrete	Sqm	100	392.15	39215
6	5.9.3	Suspended floors, roofs, landings, balconies and access platform	Sqm	200	927.25	185450
7	5.9.5	Lintels, beams, plinth beams, girders, bressummers and cantilevers	Sqm	60	736.4	44184
8	5.9.6	Columns, Pillars, Piers, Abutments, Posts and Struts	Sqm	90	961.3	86517
	5.12S	PRE-CAST RCC				
9	5.12	Providing, hoisting and fixing above plinth level up to floor five level precast reinforced cement concrete work in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like, including the cost of required centering, shuttering but , excluding cost of reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	cum	220	10585.9	2328898
	5.22S	STEEL REINFORCEMENT				
	5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
10	5.22.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	17500	107.85	1887375
	6.0	MASONRY WORK				
	6.1S	General				
	6.2	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in:				
11	6.2.2	Cement Mortar 1:6 (1 cement : 6 coarse sand).	cum	164	6295.15	1032404.6
	8.0	CLADDING WORK				

**MUMBAI- CST-DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-DRMWBB-2026-32-01

Closing Date/Time: 14/07/2026 15:00

	8.1S	General				
	8.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels				
	8.2.2	Granite stone slab colour black, Cherry/Ruby red				
12	8.2.2.1	Area of slab upto 0.50 sqm	Sqm	155	5413.5	839092.5
13	8.2.2.2	Area of slab over 0.50 sqm	Sqm	250	5136.3	1284075
	8.20S	STONE WORK DRY CLADDING				
14	8.31	Providing and fixing 1st quality ceramic glazed wall tiles conforming to IS: 15622 (thickness to be specified by the manufacturer), of approved make, in all colours, shades except burgundy, bottle green, black of any size as approved by Engineer-in-Charge, in skirting, risers of steps and dados, over 12 mm thick bed of cement mortar 1:3 (1 cement : 3 coarse sand) and jointing with grey cement slurry @ 3.3kg per sqm, including pointing in white cement mixed with pigment of matching shade complete.	Sqm	150	1267.95	190192.5
	9.0	WOOD AND P.V.C. WORK				
	9.40S	MISCELLANEOUS-WOOD WORK				
	9.48	Providing and fixing M.S. grills of required pattern in frames of windows etc. with M.S. flats, square or round bars etc. including priming coat with approved steel primer all complete.				
15	9.48.2	Fixed to openings /wooden frames with rawl plugs screws etc.	Kg	180	238.35	42903
	9.105S	GYPSUM BOARD PARTITIONS				

**MUMBAI- CST-DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-DRMWBB-2026-32-01

Closing Date/Time: 14/07/2026 15:00

	9.120	Providing and fixing factory made panel PVC door shutter consisting of frame made out of M.S. tubes of 19 gauge thickness and size of 19 mm x 19 mm for styles and 15x15 mm for top & bottom rails. M.S. frame shall have a coat of steel primers of approved make and manufacture. M.S. frame covered with 5 mm thick heat moulded PVC 'C' channel of size 30 mm thickness, 70 mm width out of which 50 mm shall be flat and 20 mm shall be tapered in 45 degree angle on both side forming styles and 5 mm thick, 95 mm wide PVC sheet out of which 75mm shall be flat and 20 mm shall be tapered in 45 degree on the inner side to form top and bottom rail and 115 mm wide PVC sheet out of which 75 mm shall be flat and 20 mm shall be tapered on both sides to form lock rail. Top, bottom and lock rails shall be provided both side of the panel. 10 mm (5 mm x 2) thick, 20 mm wide cross PVC sheet be provided as gap insert for top rail & bottom rail, panelling of 5 mm thick both side PVC sheet to be fitted in the M.S. frame welded/ sealed to the styles & rails with 7 mm (5 mm+2 mm) thick x 15 mm wide PVC sheet beading on inner side, and joined together with solvent cement adhesive. An additional 5 mm thick PVC strip of 20 mm width is to be stuck on the interior side of the 'C' Channel using PVC solvent adhesive etc. complete as per direction of Engineer-in-charge, manufacturer's specification & drawing.				
16	9.120.2	30 mm thick pre laminated PVC door shutters	Sqm	18	3663.8	65948.4
	10.0	STEEL WORK				
	10.15	General				
17	10.2	Structural steel work riveted, bolted or welded in built up sections, trusses and framed work, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	5550	133.7	742035
	11.0	FLOORING				
	11.16S	TILE FLOORING				
	11.20	Chequered precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand).				
18	11.20.4	Ordinary cement without any pigment	Sqm	2000	1056.35	2112700
	11.26S	KOTA STONE FLOORING				
	11.26	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) :				
19	11.26.1	25 mm thick	Sqm	6900	1948.25	13442925
	11.41S	VITRIFIED FLOOR TILES				
	11.41	Providing and laying vitrified floor tiles in different sizes (thickness to be specified by the manufacturer) with water absorption less than 0.08% and conforming to IS: 15622, of approved make, in all colours and shades, laid on 20mm thick cement mortar 1:4 (1 cement : 4 coarse sand), jointing with grey cement slurry @ 3.3 kg/ sqm including grouting the joints with white cement and matching pigments etc., complete.				

**MUMBAI- CST-DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-DRMWBB-2026-32-01

Closing Date/Time: 14/07/2026 15:00

20	11.41.2	Size of Tile 600x600 mm	Sqm	50	1553.45	77672.5
	12.0	ROOFING				
	12.37S	RAIN WATER SPOUT AND PIPE				
	12.41	Providing and fixing on wall face unplasticised Rigid PVC rain water pipes conforming to IS : 13592 Type A, including jointing with seal ring conforming to IS : 5382, leaving 10 mm gap for thermal expansion, (i) Single socketed pipes.				
21	12.41.2	110 mm diameter	Metre	20	377.4	7548
	13.0	FINISHING				
	13.7S	CEMENT PLASTER WITH A FLOATING COAT OF NEAT CEMENT				
	13.7	12 mm cement plaster finished with a floating coat of neat cement of mix :				
22	13.7.2	1:4 (1 cement: 4 fine sand)	Sqm	3415	425.55	1453253.25
	13.44S	EXTERIOR FINISHING				
	13.82	Wall painting with acrylic emulsion paint, having VOC (Volatile Organic Compound) content less than 50 grams/ litre, of approved brand and manufacture, including applying additional coats wherever required, to achieve even shade and colour.				
23	13.82.2	Two coats	Sqm	200	137.45	27490
	13.99	Painting with synthetic enamel paint of approved brand and manufacture of required colour to give an even shade :				
24	13.99.1	One or more coats on old work	Sqm	290	102.8	29812
	15.0	DISMANTLING AND DEMOLISHING				
	15.1S	General				
	15.2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
25	15.2.1	Nominal concrete 1:3:6 or richer mix (including equivalent design mix)	cum	500	2434.25	1217125
	15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.				
26	15.23.1	For thickness of tiles 10 mm to 25 mm	Sqm	150	73.4	11010
27	15.23.2	For thickness of tiles above 25 mm and up to 40 mm	Sqm	60	113.35	6801
28	15.59	Dismantling of flexible pavement (bituminous courses) by mechanical means and disposal of dismantled material up to a lead of 1kilometre, as per direction of Engineer-in-charge.	cum	20	420.8	8416
29	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	cum	1600	263.95	422320
	16.0	ROAD WORK				
	16.42S	CONCRETE PAVEMENTS				

**MUMBAI- CST-DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-DRMWBB-2026-32-01

Closing Date/Time: 14/07/2026 15:00

	16.43	Providing and laying design mix cement concrete of M-30 grade, in roads/taxi tracks/runways, using cement content as per design mix, using coarse sand and graded stone aggregate of 40 mm nominal size in appropriate proportions as per approved and specified design criteria, providing dowel bars with sleeve/ tie bars wherever required, laying at site, spreading and compacting mechanically by using needle and surface vibrators, levelling to required slope/ camber, finishing with required texture, including steel form work with sturdy M.S. channel sections, curing, making provision for contraction/ expansion, construction and longitudinal joints (10 mm wide x 50 mm deep) by groove cutting machine, providing and filling joints with approved joint filler and sealants, complete all as per direction of Engineer-in-charge (Item of joint fillers, sealants, dowel bars with sleeve/ tie bars to be paid separately).				
30	16.43.2	Cement concrete manufactured in automatic batching plant (RMC plant) including transportation to site in transit mixer	cum	125	11098.45	1387306.25
	16.49S	MISCELLANEOUS				
31	16.75	Providing and laying C.C. pavement of mix M-25 with ready mixed concrete from batching plant. The ready mixed concrete shall be laid and finished with screed board vibrator , vacuum dewatering process and finally finished by floating, brooming with wire brush etc. complete as per specifications and directions of Engineer-in-charge. (The panel shuttering work shall be paid for separately).	cum	585	9823.8	5746923
32	16.90	Providing and laying tactile tile (for vision impaired persons as per standards) of size 300x300x9.8mm having with water absorption less than 0.5% and conforming to IS:15622 of approved make in all colours and shades in for outdoor floors such as footpath, court yard, multi modals location etc., laid on 20mm thick base of cement mortar 1:4 (1 cement : 4 coarse sand) in all shapes & patterns including grouting the joints with white cement mixed with matching pigments etc. complete as per direction of Engineer-in-Charge.	Sqm	500	2017.6	1008800
	17.0	SANITARY INSTALLATIONS				
	17.1S	General				
	17.2	Providing and fixing white vitreous china pedestal type water closet (European type W.C. pan) with seat and lid, 10 litre low level white P.V.C. flushing cistern, including flush pipe, with manually controlled device (handle lever), conforming to IS : 7231, with all fittings and fixtures complete, including cutting and making good the walls and floors wherever required :				
33	17.2.1	W.C. pan with ISI marked white solid plastic seat and lid	Each	6	6515.55	39093.3
	17.7	Providing and fixing wash basin with C.I. brackets, 15 mm C.P. brass pillar taps, 32 mm C.P. brass waste of standard pattern, including painting of fittings and brackets, cutting and making good the walls wherever require:				
34	17.7.4	White Vitreous China Flat back wash basin size 550x 400 mm with single 15 mm C.P. brass pillar tap	Each	3	1879.2	5637.6
35	17.22	Providing and fixing G.I. inlet connection for flush pipe connecting with W.C. pan.	Each	6	142.85	857.1

**MUMBAI- CST-DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-DRMWBB-2026-32-01

Closing Date/Time: 14/07/2026 15:00

	17.28	Providing and fixing P.V.C. waste pipe for sink or wash basin including P.V.C. waste fittings complete.				
	17.28.2	Flexible pipe				
36	17.28.2.2	40 mm dia	Each	12	119.55	1434.6
	17.70	Providing and fixing PTMT Bottle Trap for Wash basin and sink.				
37	17.70.2	Bottle trap 38 mm single piece moulded with height of 270 mm, effective length of tail pipe 260 mm from the centre of the waste coupling, 77 mm breadth with 25 mm minimum water seal, weighing not less than 263 gms	Each	6	375.65	2253.9
	18.0	WATER SUPPLY				
	18.7S	C.P.V.C. PIPES				
	18.8	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply, including all CPVC plain & brass threaded fittings and fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge. Concealed work, including cutting chases and making good the walls etc.				
38	18.8.2	20 mm nominal dia Pipes	Metre	250	537.6	134400
	18.12	Providing and fixing G.I. pipes complete with G.I. fittings including trenching and refilling etc. External work				
39	18.12.6	50 mm dia nominal bore	Metre	900	762.15	685935
40	18.12.8	80 mm dia nominal bore	Metre	996	1041.7	1037533.2
	18.13	Making connection of G.I. distribution branch with G.I. main of following sizes by providing and fixing tee, including cutting and threading the pipe etc. complete :				
41	18.13.1	25 to 40 mm nominal bore	Each	50	911.9	45595
42	18.13.2	50 to 80 mm nominal bore	Each	4	1785.35	7141.4
	18.31S	C.I. SLUICE VALVES/ FIRE HYDRANTS & FIXTURES				
43	18.48	Providing and placing on terrace (at all floor levels) polyethylene water storage tank, IS : 12701 marked, with cover and suitable locking arrangement and making necessary holes for inlet, outlet and overflow pipes but without fittings and the base support for tank.	Per Litre	20000	11	220000
	19.0	DRAINAGE				
	19.1S	STONE WARE PIPES AND FITTINGS				
	19.1	Providing, laying and jointing glazed stoneware pipes class SP-1 with stiff mixture of cement mortar in the proportion of 1:1 (1 cement : 1 fine sand) including testing of joints etc. complete :				
44	19.1.3	200 mm diameter	Metre	30	970.35	29110.5
	19.6	Providing and laying non-pressure NP2 class (light duty) R.C.C. pipes with collars jointed with stiff mixture of cement mortar in the proportion of 1:2 (1 cement : 2 fine sand) including testing of joints etc. complete :				
45	19.6.5	450 mm dia. R.C.C. pipe	Metre	610	1620.95	988779.5
	21.0	ALUMINIUM WORK				
	21.1S	General				

**MUMBAI- CST-DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-DRMWBB-2026-32-01

Closing Date/Time: 14/07/2026 15:00

	21.1	Providing and fixing aluminium work for doors, windows, ventilators and partitions with extruded built up standard tubular sections/ appropriate Z sections and other sections of approved make conforming to IS: 733 and IS: 1285, fixing with dash fasteners of required dia and size, including necessary filling up the gaps at junctions, i.e. at top, bottom and sides with required EPDM rubber/ neoprene gasket etc. Aluminium sections shall be smooth, rust free, straight, mitred and jointed mechanically wherever required including cleat angle, Aluminium snap beading for glazing / panelling, C.P. brass / stainless steel screws, all complete as per architectural drawings and the directions of Engineer-in-charge. (Glazing, panelling and dash fasteners to be paid for separately) :				
	21.1.1	For fixed portion				
46	21.1.1.2	Powder coated aluminium (minimum thickness of powder coating 50 micron)	Kg	25	530.9	13272.5
	21.1.2	For shutters of doors, windows & ventilators including providing and fixing hinges/ pivots and making provision for fixing of fittings wherever required including the cost of EPDM rubber / neoprene gasket required (Fittings shall be paid for separately)				
47	21.1.2.2	Powder coated aluminium (minimum thickness of powder coating 50 micron)	Kg	32	634.45	20302.4
	21.8	Filling the gap in between aluminium frame & adjacent RCC/ Brick/ Stone work by providing weather silicon sealant over backer rod of approved quality as per architectural drawings and direction of Engineer-in-charge complete.				
48	21.8.1	Upto 5mm depth and 5 mm width	Metre	30	96.75	2902.5
					Total	51573307.00
Item- 2	Part-B DSR ITEM:- Raising / Resurfacing of Platforms at Ambivali, Vashind, Asangaon, Khadavali					
S No.	Item No	Description of Item	Unit	Qty	Rate	Amount
	2.0	EARTH WORK				
	2.1S	General				
	2.1	Earth work in surface excavation not exceeding 30 cm in depth but exceeding 1.5 m in width as well as 10 sqm on plan including getting out and disposal of excavated earth upto 50 m and lift upto 1.5 m, as directed by Engineer-in-Charge:				
1	2.1.1	All kinds of soil	Sqm	3240	129.85	420714
	2.6	Earth work in excavation by mechanical means (Hydraulic excavator)/manual means over areas (exceeding 30 cm in depth, 1.5 m in width as well as 10 sqm on plan) including getting out and disposal of excavated earth lead upto 50 m and for all lift, as directed by Engineer-in-charge.				
2	2.6.1	All kinds of soil	cum	350	177.5	62125
	2.33	Felling trees of the girth (measured at a height of 1 m above ground level), including cutting of trunks and branches, removing the roots and stacking of serviceable material and disposal of unserviceable material.				
3	2.33.3	Beyond 120 cm girth upto and including 240 cm girth	Each	12	11020.15	132241.8
4	2.33.4	Above 240 cm girth	Each	8	22075.2	176601.6
	4.0	CONCRETE WORK				
	4.1S	CEMENT CONCRETE (CAST IN SITU)				

**MUMBAI- CST-DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-DRMWBB-2026-32-01

Closing Date/Time: 14/07/2026 15:00

	4.1	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering - All work up to plinth level :				
5	4.1.2	1:1 1/2:3 (1 Cement: 1 1/2 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	126	8340.85	1050947.1
6	4.1.3	1:2:4 (1 cement : 2 coarse sand (zone-III) derived from natural sources : 4 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	1640	7878.5	12920740
	4.5S	CEMENT CONCRETE PRECAST				
	4.7	Providing and fixing up to floor five level precast cement concrete solid block, including hoisting and setting in position with cement mortar 1:3 (1 cement : 3 coarse sand), cost of required centering, shuttering complete :				
7	4.7.1	1:1 1/2:3 (1 Cement: 1 1/2 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	cum	125	17889.25	2236156.25
	5.0	REINFORCEMENT CEMENT CONCRETE				
	5.1S	CAST IN SITU				
	5.1	Providing and laying in position specified grade of reinforced cement concrete, excluding the cost of centering, shuttering, finishing and reinforcement - All work up to plinth level :				
8	5.1.2	1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources)	cum	155	9045.75	1402091.25
	5.9S	FORM WORK				
	5.9	Centering and shuttering including strutting, propping etc. and removal of form for				
9	5.9.1	Foundations, footings, bases of columns, etc. for mass concrete	Sqm	2260	392.15	886259
	5.12S	PRE-CAST RCC				
10	5.12	Providing, hoisting and fixing above plinth level up to floor five level precast reinforced cement concrete work in string courses, bands, copings, bed plates, anchor blocks, plain window sills and the like, including the cost of required centering, shuttering but , excluding cost of reinforcement with 1:1.5:3 (1 cement : 1.5 coarse sand (zone-III) derived from natural sources : 3 graded stone aggregate 20 mm nominal size derived from natural sources).	cum	160	10585.9	1693744
	5.22S	STEEL REINFORCEMENT				
	5.22	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.				
11	5.22.6	Thermo-Mechanically Treated bars of grade Fe-500D or more.	Kg	9300	107.85	1003005
	6.0	MASONRY WORK				
	6.1S	General				
	6.2	Brick work with common burnt clay modular bricks of class designation 7.5 in foundation and plinth in:				
12	6.2.2	Cement Mortar 1:6 (1 cement : 6 coarse sand).	cum	41	6295.15	258101.15
	8.0	CLADDING WORK				
	8.1S	General				

**MUMBAI- CST-DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-DRMWBB-2026-32-01

Closing Date/Time: 14/07/2026 15:00

	8.2	Providing and fixing 18 mm thick gang saw cut, mirror polished, premoulded and prepolished, machine cut for kitchen platforms, vanity counters, window sills, facias and similar locations of required size, approved shade, colour and texture laid over 20 mm thick base cement mortar 1:4 (1 cement : 4 coarse sand), joints treated with white cement, mixed with matching pigment, epoxy touch ups, including rubbing, curing, moulding and polishing to edges to give high gloss finish etc. complete at all levels				
	8.2.2	Granite stone slab colour black, Cherry/Ruby red				
13	8.2.2.1	Area of slab upto 0.50 sqm	Sqm	100	5413.5	541350
14	8.2.2.2	Area of slab over 0.50 sqm	Sqm	280	5136.3	1438164
	8.3	Providing edge moulding to 18 mm thick marble stone counters, Vanities etc., including machine polishing to edge to give high gloss finish etc. complete as per design approved by Engineer-in-Charge.				
15	8.3.2	Granite work	Metre	500	510.95	255475
	10.0	STEEL WORK				
	10.15	General				
16	10.1	Structural steel work in single section, fixed with or without connecting plate, including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer all complete.	Kg	9000	117.35	1056150
	10.16	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses etc., including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete.				
17	10.16.2	Hot finished seamless type tubes	Kg	8000	206.35	1650800
18	10.28	Providing and fixing stainless steel (Grade 304) railing made of Hollow tubes, channels, plates etc., including welding, grinding, buffing, polishing and making curvature (wherever required) and fitting the same with necessary stainless steel nuts and bolts complete, including fixing the railing with necessary accessories & stainless steel dash fasteners , stainless steel bolts etc., of required size, on the top of the floor or the side of waist slab with suitable arrangement as per approval of Engineer-in-charge, (for payment purpose only weight of stainless steel members shall be considered excluding fixing accessories such as nuts, bolts, fasteners etc.).	Kg	600	772.4	463440
	11.0	FLOORING				
	11.16S	TILE FLOORING				
	11.20	Chequered precast cement concrete tiles 22 mm thick in footpath & courtyard, jointed with neat cement slurry mixed with pigment to match the shade of tiles, including rubbing and cleaning etc. complete, on 20 mm thick bed of cement mortar 1:4 (1 cement: 4 coarse sand).				
19	11.20.2	Medium shade pigment using 50% white cement 50% Grey cement	Sqm	2250	1328.35	2988787.5
	11.26S	KOTA STONE FLOORING				

**MUMBAI- CST-DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-DRMWBB-2026-32-01

Closing Date/Time: 14/07/2026 15:00

	11.26	Kota stone slab flooring over 20 mm (average) thick base laid over and jointed with grey cement slurry mixed with pigment to match the shade of the slab, including rubbing and polishing complete with base of cement mortar 1 : 4 (1 cement : 4 coarse sand) :				
20	11.26.1	25 mm thick	Sqm	4000	1948.25	7793000
	11.41S	VITRIFIED FLOOR TILES				
	11.55	Providing and laying flamed finish Granite stone flooring in required design and patterns, in linear as well as curvilinear portions of the building all complete as per the architectural drawings with 18 mm thick stone slab over 20 mm (average) thick base of cement mortar 1:4 (1 cement : 4 coarse sand) laid and jointed with cement slurry and pointing with white cement slurry admixed with pigment of matching shade including rubbing, curing and polishing etc. all complete as specified and as directed by the Engineer-in-Charge :				
21	11.55.1	Flamed finish granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.	Sqm	1600	3186.7	5098720
	13.0	FINISHING				
	13.7S	CEMENT PLASTER WITH A FLOATING COAT OF NEAT CEMENT				
	13.7	12 mm cement plaster finished with a floating coat of neat cement of mix :				
22	13.7.2	1:4 (1 cement: 4 fine sand)	Sqm	2400	425.55	1021320
	15.0	DISMANTLING AND DEMOLISHING				
	15.1S	General				
	15.2	Demolishing cement concrete manually/ by mechanical means including disposal of material within 50 metres lead as per direction of Engineer - in - charge.				
23	15.2.1	Nominal concrete 1:3:6 or richer mix (including equivalent design mix)	cum	100	2434.25	243425
	15.23	Dismantling tile work in floors and roofs laid in cement mortar including stacking material within 50 metres lead.				
24	15.23.1	For thickness of tiles 10 mm to 25 mm	Sqm	4100	73.4	300940
25	15.23.2	For thickness of tiles above 25 mm and up to 40 mm	Sqm	8100	113.35	918135
26	15.59	Dismantling of flexible pavement (bituminous courses) by mechanical means and disposal of dismantled material up to a lead of 1kilometre, as per direction of Engineer-in-charge.	cum	330	420.8	138864
27	15.60	Disposal of building rubbish / malba / similar unserviceable, dismantled or waste materials by mechanical means, including loading, transporting, unloading to approved municipal dumping ground or as approved by Engineer-in-charge, beyond 50 m initial lead, for all leads including all lifts involved.	cum	2000	263.95	527900
	16.0	ROAD WORK				
	16.49S	MISCELLANEOUS				

**MUMBAI- CST-DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-DRMWBB-2026-32-01

Closing Date/Time: 14/07/2026 15:00

28	16.90	Providing and laying tactile tile (for vision impaired persons as per standards) of size 300x300x9.8mm having with water absorption less than 0.5% and conforming to IS:15622 of approved make in all colours and shades in for outdoor floors such as footpath, court yard, multi modals location etc., laid on 20mm thick base of cement mortar 1:4 (1 cement : 4 coarse sand) in all shapes & patterns including grouting the joints with white cement mixed with matching pigments etc. complete as per direction of Engineer-in-Charge.	Sqm	1000	2017.6	2017600
	18.0	WATER SUPPLY				
	18.7S	C.P.V.C. PIPES				
	18.10	Providing and fixing G.I. pipes complete with G.I. fittings and clamps, including cutting and making good the walls etc. (Internal work - Exposed on wall)				
29	18.10.1	15 mm dia nominal bore	Metre	350	366.4	128240
30	18.10.3	25 mm dia nominal bore	Metre	500	551.7	275850
					Total	49100886.65

4. ELIGIBILITY CONDITIONS

Special Financial Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The tenderer must have minimum average annual contractual turnover of V/N or V whichever is less; where V= Advertised value of the tender in crores of Rupees N= Number of years prescribed for completion of work for which bids have been invited. The average annual contractual turnover shall be calculated as an average of "total contractual payments" in the previous three financial years, as per the audited balance sheet. However, in case balance sheet of the previous year is yet to be prepared/ audited, the audited balance sheet of the fourth previous year shall be considered for calculating average annual contractual turnover. The tenderers shall submit requisite information as per Annexure-VIB(Placed at Page No.35 of tender form and document attached), along with copies of Audited Balance Sheets and Profit and loss statement duly certified by the Chartered Accountant/ Certificate	No	No	Allowed (Mandatory)
1.1	For more details refer attached documents	No	No	Not Allowed

Special Technical Criteria

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Work experience certificate from private individual shall not be considered. However, in addition to work experience certificates issued by any Govt. Organisation, work experience certificate issued by Public listed company having average annual turnover of Rs 500 crore and above in last 3 financial years excluding the current financial year, listed on National Stock Exchange or Bombay Stock Exchange, incorporated/registered at least 5 years prior to the date of closing of tender, shall also be considered provided the work experience certificate has been issued by a person authorized by the Public listed company to issue such certificates. In case tenderer submits work experience certificate issued by public listed company, the tenderer shall also submit along with work experience certificate, the relevant copy of work order, bill of quantities, bill wise details of payment received duly certified by Chartered Accountant, TDS certificates for all payments received and copy of final/last bill paid by company in support of above work experience certificate	No	No	Allowed (Mandatory)
1.1	Similar nature of work:- Any type of civil work viz building and structures work, pipelines underground and overhead tanks, foundation treatment works in any Railway embankment/cutting, any earthwork, cover over platform, bore wells, level crossing works including lifting barriers, cement concrete apron works, etc.	No	No	Not Allowed

**MUMBAI- CST-DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-DRMWBB-2026-32-01

Closing Date/Time: 14/07/2026 15:00

1.1.1	For more details refer attached documents	No	No	Not Allowed
-------	---	----	----	-------------

Bidders shall confirm and certify on the behalf of the tenderer including its constituents as under:

S.No.	Description
1	I/we the tenderer (s) am/are signing this document after carefully reading the contents.
2	I/We the tenderer(s) also accept all the conditions of the tender and have signed all the pages in confirmation thereof.
3	I/we hereby declare that I/we have downloaded the tender documents from Indian Railway website www.ireps.gov.in . I/we have verified the content of the document from the website and there is no addition, no deletion or no alteration to the content of the tender document. In case of any discrepancy noticed at any stage i.e. evaluation of tenders, execution of work or final payment of the contract, the master copy available with the railway Administration shall be final and binding upon me/us.
4	I/we declare and certify that I/we have not made any misleading or false representation in the forms, statements and attachments in proof of the qualification requirements.
5	I/We also understand that my/our offer will be evaluated based on the documents/credentials submitted along with the offer and same shall be binding upon me/us.
6	I/We declare that the information and documents submitted along with the tender by me/us are correct and I/we are fully responsible for the correctness of the information and documents, submitted by us.
7	I/we certify that I/we the tenderer(s) is/are not blacklisted or debarred by Railways or any other Ministry / Department of Govt. of India from participation in tender on the date of submission of bids, either in individual capacity or as a HUF/ member of the partnership firm/LLP/JV/Society/Trust.
8	I/we understand that if the contents of the certificate submitted by us are found to be forged/false at any time during process for evaluation of tenders, it shall lead to forfeiture of the Bid Security and may also lead to any other action provided in the contract including banning of business for a period of upto two year. Further, I/we and all my/our constituents understand that my/our offer shall be summarily rejected.
9	I/we also understand that if the contents of the certificate submitted by us are found to be false/forged at any time after the award of the contract, it will lead to termination of the contract, along with forfeiture of Bid Security/Security Deposit and Performance guarantee and may also lead to any other action provided in the contract including banning of business for a period of upto two year.
10	I/We have read the clause regarding restriction on procurement from a bidder of a country which shares a land border with India and certify that I am/We are not from such a country or, if from such a country, have been registered with the competent Authority. I/We hereby certify that I/we fulfil all the requirements in this regard and am/are eligible to be considered (evidence of valid registration by the competent authority is enclosed)

Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc.

S.No.	Description
1	Partnership firm/Joint Venture (JV) / Hindu Undivided Family (HUF) / Limited Liability Partnership (LLP) etc. Please submit a certificate in the prescribed format (please download the format from the link given below). Non submission of the certificate, or submission of certificate either not properly filled in, or in a format other than the prescribed format shall lead to summary rejection of your offer. (Click here to download the Format of Self Certification)

5. COMPLIANCE

Commercial-Compliance

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	The Bid Security shall be deposited either in cash through e-payment gateway or submitted as Bank Guarantee bond from a scheduled commercial bank of India or as mentioned in tender documents.	Yes	Yes	Allowed (Optional)

**MUMBAI- CST-DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-DRMWBB-2026-32-01

Closing Date/Time: 14/07/2026 15:00

1.1	The Bank Guarantee bond shall be as per Annexure- VIA (Placed at Page No. 35-36 of tender form), and shall be valid for a period of 90days beyond the bid validity period. In case, submission of Bid Security in the form of Bank Guarantee, following shall be ensured: (i).A scanned copy of the Bank Guarantee shall be uploaded on e-Procurement Portal (IREPS) while applying to the tender. (ii).The original Bank Guarantee should be delivered in person to the official nominated as indicated in the tender document before closing date for submission of bids. .(i.e. excluding the last date of submission of bids) (iii).Non submission of scanned copy of Bank Guarantee with the bid on e-tendering portal (IREPS) and/or non submission of original Bank Guarantee within the specified period shall lead to summary rejection of bid. (iv).The Tender Security shall remain valid for a period of 90 days beyond the validity period for the Tender. (v).The details of the BG, physically submitted should match with the details available in the scanned copy and the data entered during bid submission time, failing which the bid will be rejected (vi).The Bank Guarantee shall be placed in an envelope, which shall be sealed. The envelope shall clearly bear the identification "Bid for the ***** Project" and shall clearly indicate the name and address of the Bidder. In addition, the Bid Due Date should be indicated on the right hand top corner of the envelope. (vii).The envelope shall be addressed to the officer and address as mentioned in the tender document. (viii).If the envelope is not sealed and marked as instructed above, the Railway assumes no responsibility for the misplacement or premature opening of the contents of the Bid submitted and consequent losses, if any, suffered by the Bidder.	Yes	Yes	Allowed (Optional)
2	All the bidders/tenderers should ensure that they are GST compliant and their quoted tax structure/rates are as per GST Law.	No	Yes	Allowed (Mandatory)
3	Please enter the percentage of local content in the material being offered. Please enter 0 for fully imported items, and 100 for fully indigenous items. The definition and calculation of local content shall be in accordance with the Make in India policy as incorporated in the tender conditions.	No	Yes	Allowed (Optional)
4	Tenderer should mandatory submit documentary proof as per the attached checklist document.	No	No	Allowed (Mandatory)

General Instructions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Tenderers are abiding by the General Conditions of Contract (GCC) April 2022 & any statutory modification thereof and also abide to carry out the work accordingly.	No	No	Not Allowed
2	Documentary proof - Tenderer should submit scanned copy documentary proof in regard for fulfilling the Technical /financial eligibility criteria along-with their offer (for details refer attached documents). If the tenderers do not submit any proof of meeting with the eligibility criteria as laid down in the tender conditions, the offer shall be considered as incomplete and shall be summarily rejected. Documents submitted in support of eligibility criteria after opening of tender will not be considered.	No	No	Not Allowed
3	Document attached - Tender form	No	No	Not Allowed

Special Conditions

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Tenderer please note that price variation clause (PVC) is. Applicable	No	No	Not Allowed

**MUMBAI- CST-DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-DRMWBB-2026-32-01

Closing Date/Time: 14/07/2026 15:00

2	Tenderers should show discount in the rate schedule only, instead of anywhere else in the offer. Discounts not shown at designated place will be summarily ignored for assigning inter-se ranking of offers. Conditional discount will not be considered for adjudging the inter-se position i.e. rate quoted without any conditions attached (viz. Discount/ Rebates having linkages to quantity, rates payment etc.) will only be considered for evaluation purpose. In other words, discounted rates linked to quantities, rates, prompt payment etc. will be ignored for determining inter-se position. Railway, however reserves the right to use the discounted rate/ rates considered workable and appropriate, for counter offer to the successful tenderers.	No	No	Not Allowed
---	---	----	----	-------------

Technical-Compliances

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	Bidder to ensure the contents of para 14(i) to (vi) and 15 of GCC April 2022 corrected up to date as the case may be and upload documents accordingly. (Page No.17 to 19 of GCC). Participation of Partnership Firm in works tenders refer GCC para No. 18.1 to 18.11 of Part-I April 2022 corrected up to date. (Page No.25 to 27). Participation of Joint Venture (JV) in works tenders refer GCC April 2022 para no 17.1 to 17.15.3 of GCC April 2022 corrected up to date (Page No.20 to 25), Participation of Employment/Partnership etc of Retired Railway employees refer Para 16 (a) to (c) of GCC April 2022 corrected up to date (Page No.19 to 20) . These instructions are also included in tender form.	No	No	Allowed (Mandatory)
2	All the Bidders/tenderers while uploading the tender please note the Check list for document to be submitted by the tenderer for Civil Works or Track Works along with the tender. Tenders without these documents will be summarily rejected.	No	No	Allowed (Mandatory)

Undertakings

S.No.	Description	Confirmation Required	Remarks Allowed	Documents Uploading
1	I/ We have visited the works site and I / We am / are aware of the site conditions.	No	No	Not Allowed
2	I have read the entire tender document including uploaded documents.	No	No	Not Allowed
3	I have read page No.121-122 of tender form for Inclusion of letter of credit as mode of payment.	No	No	Not Allowed

6. Documents attached with tender

S.No.	Document Name	Document Description
1	AnnexureVA1.pdf	Annexure VA
2	AnnexureVIB.pdf	Annexure VIB
3	GCC_April-2022_2022_CE-I_CT_GCC-2022_POLICY_27.04.221_1.pdf	GCC2022
4	GCCACS1to6.pdf	GCC1to6
5	GCCACS4.PDF	GCC 7 to 10
6	GCC11.pdf	GCC11
7	ChecklistDocoment.pdf	Chek list
8	SPECIALCONDITIONS1Core.pdf	SPI conditions 1 Core
9	SpecialcondforSafetyRulesatworksitesinElectsections.pdf	spl conditions elect
10	NewcivilCondition1.pdf	civil Condi
11	ADDITIONALSPECIALCONDITIONFORTENDER..pdf	spl Conditions for Tender
12	LettersRegardingDeploymentofcontractorsEngineer.pdf	Letters Regadring Deploy
13	AuditPara.pdf	Audit Para
14	TenderForm1.pdf	Tender Form
15	SafetyCircularSafetyInstructions.pdf	Safety Circular Safety Instruction

**MUMBAI- CST-DIVISION-ENGG/CENTRAL RLY
TENDER DOCUMENT**

Tender No: CR-DRMWBB-2026-32-01

Closing Date/Time: 14/07/2026 15:00

16	Scopeofwork.pdf	Scope of work
----	-----------------	---------------

This tender complies with Public Procurement Policy (Make in India) Order 2017, dated 15/06/2017, issued by Department of Industrial Promotion and Policy, Ministry of Commerce, circulated vide Railway Board letter no. 2015/RS(G)/779/5 dated 03/08/2017 and 27/12/2017 and amendments/ revisions thereof.

As a Tender Inviting Authority, the undersigned has ensured that the issue of this tender does not violate provisions of GFR regarding procurement through GeM.

Signed By: NISHITH KUMAR MALL

Designation : Sr.DEN NE