

Annexure - A

Name of work -Salem Division - (1) Dismantling of condemned Quarters (110 units) in SSE/Works/KRR section (2) Dismantling of condemned station buildings (8 nos) at various stations under SSE/W/KRR section

Dismantling of condemned Quarters & old station building details

(1) Dismantling of condemned Quarters (110 units) in SSE/Works/KRR section

S.No.	Qrs No.	Type	Roof Type	Location	Each Qrs Unit	No of units
1	CVD/4	I	Mangalore tile with wooden reaper	CVD	1	55
2	PAS/9	I	Mangalore tile with wooden reaper	PAS	1	
3	KMD/3	I	Mangalore tile with wooden reaper	KMD	1	
4	PGR/7	I	Mangalore tile with wooden reaper	PGR	1	
5	PGR/9	I	Mangalore tile with wooden reaper	PGR	1	
6	KRR/3	I	Mangalore tile with wooden reaper	KRR	1	
7	KRR/33	I	Mangalore tile with wooden reaper	KRR	1	
8	CVD/8	I	Mangalore tile with wooden reaper	CVD	1	
9	MMH/4	I	Mangalore tile with wooden reaper	MMH	1	
10	MMH/5	I	Mangalore tile with wooden reaper	MMH	1	
11	KLT/11	I	Mangalore tile with wooden reaper	KLT	1	
12	MPLM/5	I	Mangalore tile with wooden reaper	MPLM	1	
13	MPLM/6	I	Mangalore tile with wooden reaper	MPLM	1	
14	MPLM/9	I	Mangalore tile with wooden reaper	MPLM	1	
15	MPLM/11	I	Mangalore tile with wooden reaper	MPLM	1	
16	MPLM/12	I	Mangalore tile with wooden reaper	MPLM	1	
17	KRR/37A-B	I	Mangalore tile with wooden reaper	KRR	2	
18	KRR/38A-B	I	Mangalore tile with wooden reaper	KRR	2	
19	SEV/1A-B	I	Mangalore tile with wooden reaper	SEV	2	
20	LC 28 A 13-A-B	I	Mangalore tile with wooden reaper	LC 28 A ED-TP	2	
21	PGN/15A-B	I	Mangalore tile with wooden reaper	PGN	2	
22	KRR/4A-J	I	Mangalore tile with wooden reaper	KRR	10	
23	MPLM/7A-D	I	Mangalore tile with wooden reaper	MPLM	4	
24	KRR/34A-D	I	Mangalore tile with wooden reaper	KRR	4	
25	MYU/15A-D	I	Mangalore tile with wooden reaper	MY	4	
26	VRQ/9	I	Mangalore tile with wooden reaper	VRQ	1	
27	VRQ/14A-B	I	Mangalore tile with wooden reaper	VRQ	2	
28	VRQ/10A-D	I	Mangalore tile with wooden reaper	VRQ	4	
29	MYU/14A-D	I	Mangalore tile with Steel reaper	MY	4	7
31	MYU/16A-B	I	Mangalore tile with Steel reaper	MYU	2	
32	PGN/9	I	Mangalore tile with Steel reaper	PGN	1	
33	PAS /15A-B	I	RCC roof	PAS	2	23
34	KMD/25A-B	I	RCC roof	KMD	2	
35	MPLM/16A-B	I	RCC roof	MPLM	2	
36	MUQ/6A-B	I	RCC roof	MUQ	2	
37	EL/14 A-B	I	RCC roof	EL	2	
38	VRQ/18 A-C	I	RCC roof	VRQ	3	
39	KRR/65A-D	I	RCC roof	KRR	4	
40	KRR/66A-D	I	RCC roof	KRR	4	
41	E13 at LC 25	I	RCC roof	ED-TP	1	
42	EDU/4	I	RCC roof	EDU	1	
43	KLT/13	I	Hourdis roof	KLT	1	1
44	MYU/12	II	Mangalore tiled roof with steel reapers	MYU	1	1
45	KMD/8	II	Hourdis roof	KMD	1	2
46	MYU/8	II	Hourdis roof	MYU	1	
47	CVD/12	III	Mangalore tiled with wooden reaper	CVD	1	
48	PAS/4	III	Mangalore tiled with wooden reaper	PAS	1	
49	PAS/11	III	Mangalore tiled with wooden reaper	PAS	1	
50	KMD/17	III	Mangalore tiled with wooden reaper	KMD	1	

S.No.	Qrs No.	Type	Roof Type	Location	Each Qrs Unit	No of units
51	KRR/36	III	Mangalore tiled with wooden reaper	KRR	1	15
53	MMH/12	III	Mangalore tiled with wooden reaper	MMH	1	
54	PAS/10	III	Mangalore tiled with wooden reaper	PAS	1	
55	PAS/14	III	Mangalore tiled with wooden reaper	PAS	1	
56	MTNL/12	III	Mangalore tiled with wooden reaper	MTNL	1	
57	URL/5	III	Mangalore tiled with wooden reaper	URL	1	
58	URL/7	III	Mangalore tiled with wooden reaper	URL	1	
59	KMD/21	III	Mangalore tiled with wooden reaper	KMD	1	
60	KMD/16	III	Mangalore tiled with wooden reaper	KMD	1	
61	MYU/7	III	Mangalore tiled with wooden reaper	MYU	1	
62	MMH/3	III	Mangalore tiled with wooden reaper	MMH	1	
63	KLT/17	III	Mangalore tiled with steel reaper	KLT	1	1
64	PLI/6	III	RCC roof	PLI	1	2
65	PGN/8	III	RCC roof	PGN	1	
66	MYU/9	III	Hourdis roof	MYU	1	3
67	KLT/12	III	Hourdis roof	KLT	1	
68	EL/9	III	Hourdis roof	EL	1	
Total Number of condemned Qtrs =						110

(2) Dismantling of condemned station buildings (8 nos) at various stations under SSE/W/KRR section

S.No.	Station	Type	Roof Type	Location	Each Qrs Unit	No of units
1	MKY	old Station building	Mangalore tiled roof	MKY	1	1
2	TRPT	old Station building	RCC roof	TRPT	1	1
3	VBU	old Station building	RCC roof	VBU	1	1
4	Kujiliyamparai	old Station building	RCC roof	Kujiliyamparai	1	1
5	PAS,PGR,MPLM,MTNL	old Station building	Mangalore tiled roof	PAS,PGR,MPLM,MTNL	4	4
Total Number of old station building =						8

S
SOUNDAPP
AN

Digitally signed by
 S SOUNDAPPAN
 Date: 2026.03.18
 17:12:49 +05'30'
 SSE/Works/KRR

(1) Dismantling of condemned Quarters (110 units) in SSE/Works/KRR section

Credit of Released Material (CRRM) Details

ANNEXURE-I				
Statement accompanying DS8 No : 691807 Dt:06.12.2025 of condemned Qrs given below				
SW-I : Dismantling of condemned Type I (Mangalore Tiled Roof with wooden reaper) Qtrs.No. CVD/4, PAS/9, KMD/3, PGR/7, PGR/9, KRR/3, KRR/33, CVD/8, MMH/4, MMH/5, KLT/11, MPLM/5, MPLM/6, MPLM/9, MPLM/11, MPLM/12, KRR/37 A-B, KRR/38 A-B, SEV/1 A-B, 13 A-B at LC 28A, PGN/15 A-B, KRR/4 A-J, MPLM/7 A-D, KRR/34 A-D & MYU/15 A-D, VRQ/9, VRQ/14 A-B & VRQ/10 A-D -55 units				
S.No.	Materials description	Nos	Qty	Unit
1	Doors, windows shutters (60% taken into account)	1	891.00	Nos
2	Mangalore tiles 20% taken into account	354.2	7084	Nos
3	Country wood reeper 50% taken into account	1	1254	m
	1254x0.05x0.50x35.3147=553.56cuft	1	553.56	Cuft
4	Country wood truss 60% takend into account	1	7.76	
	(7.76x35.3147)=274.04cuft	1	274.04	Cuft
5	Steel door	1	44000.0	Kg
6	Rail 95% taken into account	1	3572.76	Kg
7	Brick Work (10% take into account)	1	62148.00	Nos
SW-II Dismantling of condemned Type I(Mangalore Tiled Roof with steel reaper) Qtrs.No. MYU/14 A-D, MYU/16 A-B & PGN/9 -7 units				
S.No.	Materials description	Nos	Qty	Unit
1	Doors, windows shutters (70% taken into account) -TW Door	1	35.00	Nos
2	Mangalore tiles 50% taken into account	1	2254	Nos
3	Steel angle 70% taken into acoount	1	3495.80	Kg
4	Rail 95% taken into account	1	2222.29	Kg
5	Brick Work (30% take into account)	1	36259.50	Nos
6	Steel door	1	22400.00	kg
SW- III : Dismantling of condemned Type-I (R.C.C Roof) Qtrs.No. PAS/15 A-B, KMD/25 A-B, MPLM/16 A-B, MUQ/6 A-B, EL/14 A-B,VRQ/18 A-C, KRR/65 A-D & KRR/66 A-D, E13 at LC 25 & EDU/4 - 23 units				
S.No.	Materials description	Nos	Qty	Unit
1	Doors, windows shutters (80% taken into account) Teak Door	1	250.00	Nos
2	Brick Work (75% take into account)	1	188049.75	Nos
SW IV : Dismantling of condemned Type-I (Hourdis Block) Qtrs.No.KLT/13. - 1units				
S.No.	Materials description	Nos	Qty	Unit
1	Doors, windows shutters (80% taken into account) Teak Door	1	4.00	Nos
2	Brick Work (30% take into account)	1	3306.55	Nos
3	Rail (95% taken into account)	1	1328.78	kg
SW V : Dismantling of condemned Type II (Mangalore tiled roof with steel reapers) Qtrs.No. MYU/12. -1 units				
S.No.	Materials description	Nos	Qty	Unit
1	Doors, windows shutters (60% taken into account)	1	7.00	Nos
2	Mangalore tiles 50% taken into account	35.7	714	Nos
3	Country wood reeper 50% taken into account	1	161.5	m
	161.5x0.05x0.50x35.3147=71.29cuft	1	71.29	Cuft
4	Country wood truss 60% takend into account	1	0.41	
	(0.41x35.3147)=14.48cuft	1	14.48	Cuft
5	Steel door	1	800.0	Kg
6	Rail 95% taken into account	1	508.90	Kg
7	Brick Work (30% take into account)	1	6347.00	Nos

SW VI : Dismantling of condemned Type-II(Hourdis Block) Qtrs.No.KMD/8 & MYU/8 -2 units

S.No.	Materials description	Nos	Qty	Unit
1	Doors, windows shutters (60% taken into account)	1	15.00	Nos
2	Steel door	1	800.0	Kg
3	Rail 95% taken into account	1	3788.45	Kg
4	Brick Work (30% take into account)	1	9320.00	Nos

SW VII : Dismantling of condemned Type III (Mangalore Tiled Roof with wooden reaper) Qtrs.No. CVD/12, PAS/4, PAS/11, KMD/17, KRR/36, MMH/12 ,PAS/10, PAS/14, MTNL/12, URL/5, URL/7, KMD/21, KMD/16, MYU/7 & MMH/3 - 15 units

S.No.	Materials description	Nos	Qty	Unit
1	Doors, windows shutters (60% taken into account)	1	86.40	Nos
2	Mangalore tiles 20% taken into account	184.32	3686.4	Nos
3	Country wood reeper 50% taken into account	1	2419.2	m
	2419.2x0.05x0.50x35.3147=1067.92cuft	1	1067.92	Cuft
4	Country wood truss 60% takend into account	1	6.74	
	(6.74x35.3147)=238.02cuft	1	238.02	Cuft
5	Steel door	1	12800.0	Kg
6	Rail 95% taken into account	1	3437.88	Kg
7	Brick Work (30% take into account)	1	82006.50	Nos

SW VIII : Dismantling of condemned Type III(Mangalore Tiled Roof with steel reaper) Qtrs.No. KLT/17- 1 units

S.No.	Materials description	Nos	Qty	Unit
1	Doors, windows shutters (60% taken into account)	1	6.00	Nos
2	Mangalore tiles 20% taken into account	14.11	282.2	Nos
3	Steel door	1	800.0	Kg
4	Rail 95% taken into account	1	508.90	Kg
5	Brick Work (30% take into account)	1	6193.50	Nos

SW IX : Dismantling of condemned Type-III (RCC Roof) Qtrs.No.PLI/6 & PGN/8 -2 units

S.No.	Materials description	Nos	Qty	Unit
1	Doors, windows shutters (60% taken into account)	1	14.40	Nos
2	Rail 95% taken into account	1	3675.36	Kg
3	Brick Work (30% take into account)	1	9319.50	Nos

SW X : Dismantling of condemned Type-III (Hourdis Block) Qtrs No. MYU/9, KLT/12 & EL/9 -3 units

S.No.	Materials description	Nos	Qty	Unit
1	Doors, windows shutters (60% taken into account)	1	6.00	Nos
2	Mangalore tiles 20% taken into account		194.4	Nos
3	Country wood reeper 50% taken into account	1	174.3	m
	174.3x0.05x0.50x35.3147=76.94cuft	1	76.94	Cuft
4	Country wood truss 60% takend into account	1	0.27	
	(0.27x35.3147)=9.54cuft	1	9.54	Cuft
6	Rail 95% taken into account	1	848.59	Kg
7	Brick Work (30% take into account)	1	16399.50	Nos

(2) Dismantling of condemned station buildings (8 nos) at various stations under SSE/W/KRR section**Credit of Released Materials (CRRM) Details**

ANNEXURE-I			
Name of Work: Dismantling of condemned station buildings (8 nos) at various stations under SSE/W/KRR section			
Statement accompanying DS8 No : 691808 Dt:10.03.2025 of condemned station buildings.			
SW-I : Dismantling of Condemned MKY Halt station building and PF at ADEN/KRR Sub division.			
Sl No	Description	Qty	Unit
1	For door & window 50% taken into account	4.00	Nos
2	Rails	1425.00	Kg
3	Mangalore Tiles	214.00	Nos
4	For Purline & Reepers 60% taken into account	168.00	Cuft
5	Brick (50% taken in account)	28378.00	Nos
6	Concrete Debris (40% taken in account)	40.00	Cum
SW-II : Dismantling of Condemned TRPT Halt station building at ADEN/ KRR Sub division.			
Sl No	Description	Qty	Unit
1	For door & window 50% taken into account	6.00	Nos
2	Brick (50% taken in account)	7303.00	Nos
SW-III : Dismantling of Condemned VBU station building at ADEN/KRR Sub division.			
Sl No	Description	Qty	Unit
1	For door & window 50% taken into account	6.00	Nos
2	Brick (50% taken in account)	7303.00	Nos
SW-IV : Dismantling of Condemned Kujiliyamparai station building and PF at ADEN/KRR Sub division.			
Sl No	Description	Qty	Unit
1	For door & window 50% taken into account	6.00	Nos
2	Brick (50% taken in account)	7303.00	Nos
SW-V :Dismantling of old station building at PAS, PGR, MPLM & MTNL stations.			
1	Doors, windows shutters (60% taken into account)	20.00	Nos
2	Mangalore tiles 30% taken into account	1603.00	Nos
3	Country wood reeper 50% taken into account	786.00	m
	$=50\% \times 786 \times 0.05 \times 0.50 \times 35.3147 = 346.97 \text{ cuft}$	346.97	Cuft
4	Country wood truss 60% taken into account	1.07	
	$(1.07 \times 35.3147) = 37.79 \text{ cuft}$	37.79	Cuft
5	Steel door	45000.00	Kg
6	Rail 95% taken into account	9403.54	Kg
7	Brick Work (30% take into account)	28737.00	Nos

S
SOUNDAPPA
N

Digitally signed by
S SOUNDAPPAN
Date: 2026.03.10
20:46:19 +05'30'

SSE/Works/KRR

(3) Demolition of damaged toilets in platform No.1 at NMKL Station.

S.No	Station	Roof Type	Location	Units
1	NMKL	RCC Roof	NMKL Station PF.1	1 No

Credit value of Released materials (CRRM)

S.NO	Description of Item	Unit	Qty
1	Reinforcement rods Qty	Kg	899.25

Name of work: Dismantling of condemned Quarters (80 Units) in SSE/Works/ATU section.

Dismantling of Condemned Qrs details:

Station	Type of masonry	Type of roof	Qrs No	Type	Year of construction	Number of Qrs
MKSP	BRICK	Hourdis roof	8	IIA	1968	1
	BRICK	Hourdis roof	4	IIA	1931	1
	BRICK	Hourdis roof	3A-D	I	1931	4
	BRICK	RCC roof	2A-C	I	1968	3
KKTI						
	RR	Hourdis roof	10	IIA	1931	1
	RR	Hourdis roof	8	IIB	1931	1
	RR	Hourdis roof	12	I	1961	1
ASAKALTHUR						
	RR	Hourdis roof	4	IIB	1931	1
	RR	Hourdis roof	6	IIA	1931	1
	RR	Hourdis roof	7A-B	I	1931	2
PRV						
	BRICK	RCC roof	11A-D	I	1968	4
	RR	Hourdis roof	3A-D	I	1931	4
	RR	Hourdis roof	5	IIA	1931	1
	BRICK	Hourdis roof	6	IIB	1931	1
CHSM						
	RR	Hourdis roof	5A-D	I	1931	4
	RR	Hourdis roof	6	IIB	1931	1
	RR	Hourdis roof	7	IIA	1931	1
MLYR						
	RR	Hourdis roof	2	IIB	1931	1
	RR	Hourdis roof	3	IIA	1931	1
	RR	Hourdis roof	1	I	1931	1
TVS						
	BRICK	RCC roof	5AC	I	1961	3
	RR	Hourdis roof	6 & 9	IIA	1931	2
	RR	Hourdis roof	4A-D	I	1931	4
KTKT						
	RR	Hourdis roof	4	IIB	1931	1
	RR	Hourdis roof	2	IIA	1931	1
	RR	Hourdis roof	1	I	1931	1
ATU	RR	Hourdis roof	20A-D	I	1931	4
	RR	Hourdis roof	23	I	1931	1
PDKM	BRICK	Mangalore tiled roof	PDKM-5AB	IIA	1969	2
ETP	RR	Mangalore tiled roof	3AB	I	1961	2
	RR	Hourdis roof	6	IIB	1931	1
SNVD		Hourdis roof				
	RR	Hourdis roof	3	IIB	1931	1
	RR	Hourdis roof	5	IIA	1931	1
	RR	Hourdis roof	6	I	1931	1
		Hourdis roof				
	BRICK	Mangalore tiled roof	5	IIB	1931	1

Station	Type of masonry	Type of roof	Qrs No	Type	Year of construction	Number of Qrs
MPLI	RR	Hourdis roof	7&8	IIA	1931	2
	RR	Hourdis roof	9AD	I	1931	4
	Tiled	Hourdis roof	10	I	1931	1
APN						
	RR	Hourdis roof	3	IIB	1931	1
	RR	Hourdis roof	5	IIA	1931	1
SLME	RR	Hourdis roof	6AB	I	1931	2
	RR	Hourdis roof	3	IIA	1931	1
	RR	Hourdis roof	4	IIB	1931	1
SXT						
	Brick	Mangalore tiled roof	21 AD	I	1941	4
	RR	Hourdis roof	18	IIB	1933	1
	RR	Hourdis roof	19	IIA	1941	1
Total						80

M.THIYAGA
RAJAN

Digitally signed by
M.THIYAGARAJAN

SSE/Works/ATU

JAYRAM
RAM

Digitally signed by
JAYRAM RAM
Date: 2026.03.24
10:27:15 +05'30'

ADEN/ATU

(4) Dismantling of condemned Quarters (80 units) in SSE/Works/ATU section

Credit of Released Materials (CRRM) Details

S.No	Item Description	Qty	Unit
1	Wooden Door and windows	6.00	Nos
2	wooden rafter 110x50mm size (2.112 cumX35.3147=74.58 cuft)	74.58	cuft
3	wooden Purlin 50x35mm size (1.008 cumX35.3147 =35.60 cuft)	35.60	cuft
4	Brick	161600.00	No's
5	Rubble stone	370201.00	No's
6	Mangalore tiles	913.00	each
7	Steel	3508.00	Kg

M.THIYAGA
RAJAN Digitally signed by
M.THIYAGARAJAN

JAYRA
M RAM Digitally signed
by JAYRAM RAM
Date: 2026.03.24
10:28:12 +05'30'

ADEN/ATU