

PARTICULARS OF WORK

Name of work :- SC Division-DKJ-MUGR Section- Br no.100 at km.77/7-8 between GLE-PGP Stations, Br no.102 at km.78/13-14 between GLE-PGP Stations, Br no.107 at km.83/3-4 between PGP-MUGR Stations, existing 1x12.20m steel girder Proposed to be replaced with PSC Slab of span 1x12.20m

SITE: Br.No.100 at km.77/7-8, Br no.102 at km.78/13-14, Br no.107 at km.83/3-4 in DKJ-MUGR Section

GENERAL FEATURES:

- 2.1 Casting of PSC Slabs , ballast retainers and footpaths
- 2.2 Jacketting and extension of abutments wherever required.
- 2.3 Delaunching of existing steel girders
- 2.4 Launching of PSC Slabs, ballast retainers, footpaths.
- 2.5 Laying and linking of track.

The tender consists of SIX schedules namely – Schedule – A, B, C, D, E & F

- | | | |
|-----------------|---|---|
| 1. Schedule – A | : | USSOR-2021 Delaunching & Launching Item |
| 2. Schedule – B | : | USSOR-2021 Concrete Items |
| 3. Schedule – C | : | USSOR-2021 Cement Item |
| 4. Schedule – D | : | USSOR-2021 Steel Item |
| 5. Schedule – E | : | USSOR-2021 General items |
| 6. Schedule – F | : | USSOR-2021 Track Items |

Note: As per Railway board Letter No. 2022/CE-III/Bridge Policy (E-3406846) Dt. 29.12.2025, Maintenance period of the work is **48 (Forty Eight)** months from the date of completion of the work.


DEN/South/SC