

SCOPE OF WORK

SC DIV: SC-KZJ Section: Provision of additional COP's in GNP,ALER,WP, BN,MLY and Up gradation of Existing COP's with new sheeting & gutter at GNP, RGP,ALER, BN, MLY stations in DEN /Central Jurisdiction.

Location of work: Secunderabd -Kazipet section

1) General Features:-

- Construction of New COP of approx. 6 bays (96m length) on each platforms on GNP,ALER,WP,BN,MLY & RGP stations- with RDSO standard drawings for Cover over platforms.
- Replacing the existing sheeting's and water gutters of COP with new GI sheeting and Stainless steel water gutter at stations GNP,ALER,WP,BN,MLY & RGP.
- And providing water troughs, seating benches etc, and other miscellaneous works as directed by Engineer-In charge in site.

2) The tender consists of Four Schedules :

Schedule A – DSR 2023- General Items

Schedule B - DSR 2023- Cement Concrete Items


Schedule C - DSR 2023- Steel Items

Schedule D – Ns-items

NOTE:

1. THE MAINTENANCE PERIOD FOR THE WORK IS 36 MONTHS FROM THE DATE OF COMPLETION OF WORK.

Special Conditions applicable for the present work (Building portion)					
S.N o		Applicable			Applicable
1	A). Conditions for Building works.	Yes	6	F). Special Conditions for concrete Mix Design.	Yes
2	B). Conditions for Execution of Earth work.	Yes	7	G). Guide lines for bringing economy in concrete design mix.	Yes
3	C). Specifications for Structural steel.	Yes	8	H). Maintenance of site records in contracts for ensuring quality of work.	Yes
4	D). Defects Liability Clause.	yes	9	I). Site Laboratory Establishment by Contractor.	Yes
5	E). Approved list of Brands / Makes of 161 Items.	Yes	10	J). Applicability of stage payment for steel after receipt at site work.	Yes


DEN/Central/SC