

GUJARAT STATE POLICE HOUSING CORPORATION
LIMITED, RAJKOT

:: ATTACHED SPECIFICATIONS ::

Name of Work: Remaining Work of Fire Fighting Network, Sump & Pump Room at PSQ Cat B-32(P+4) Units at Atkot (Including Electrification) Dist: Rajkot.

ITEM NO. 12:

Providing and fixing Gun metal check or non-return fullway wheel valve/Handle valve. 80mm dia.

1.0 Materials:

1.1 The gun metal check or non return full way wheel valve of specified dia. shall conform to I.S.778-1964. The non return valve shall be of tested quality.

2.0 Workmanship

2.1 The gun metal check or non return valve shall be fully cleared of all foreign matter before fixing.

The fixing of valve shall be done by means of bolts nuts and 3mm. rubber insertions with flanges of spigot and socketed tail pieces, drilled to the same specification as in case of socket and spigot and with flanges in case of flanged pipes. The jointing shall be done leak proof.

3.0 Mode of measurements & payment:

3.1 The rate includes all labour, materials, tools and plant etc. required for satisfactory completion of this item.

3.2 The rate shall be for a unit of one number.

ITEM NO.: 17

Cutting Holes of 200 mm Dia in RCC Floors & Roofs or In Any RCC Member etc. For Passing Pipe etc. And Repairing The Hole After Insertion Of Pipe etc. with Cement Concrete 1:1:2 (1 Cement : 1 Coarse Sand : 2 Graded Stone Aggregate 20 mm nominal) Including Finishing Complete So As To Make It Leak Proof.

❖ **Workmanship**

- The core cutting in RCC Member should be carried out with core cutting tool for size of 200mm etc.

❖ **Mode of measurement:**

- The rate shall be inclusive of labor, machinery cost.

The item shall be measured and paid in Nos

Signature of the contractor

I/c Executive Engineer

GSPHC Ltd., Rajkot