

**DAKSHIN GUJARAT VIJ COMPANY LTD.**  
**RANDER DIVISION, SURAT**

**SCHEDULE-B**

**Name of work:** Providing & Laying of PCC/Paver block/Raising of Plinth for T/C at Various Location for **PAL Sub division under Rander Division**.and if required work to be carried out at Any other sub division under Rander Division.

Sr. No.	Description	Rate in Rs.	Unit	Amount in Rs.
1	Raising transformer plinth of various transformer centers by Providing and fixing RCC block in C.C. 1:2:4 in block of size 600X300X150 mm including carting the block of at various transformer centre lifting the transformer form plinth, raising the plinth by block masonry in Cement mortar (1:6), placing transformer in the position of raising plinth with all cost of materials say cement, sand, centering, labour and curing the block etc. Complete.	220	Nos	
2	Inside fencing area to be finished with 6" thick 1:2:4 cement concrete (All materials required being use like cement bags, sand, kapchi is to be brought by the contractor at this own cost.) (payment will be given is sq.ft. area for which concrete is done at FRP fencing)	81	Sq. ft.	
<b>Total Estimated Amount</b>				<b>Rs. 27,00,000/-</b>
<b>In words: Rs. Twenty Seven Lakh Only.</b>				

- The Rates quoted by Bidder will be exclusive of GST & any escalation in rate of GST during the tenure of the contract will be paid by DGVCL as part of statutory variation.

% Above/Below of Estimate Amount

Stamp & Sign of Contractor

**EXECUTIVE ENGINEER (O&M),**  
**D.G.V.C.L., Rander Division.**