

DAKSHIN GUJARAT VIJ COMPANY LTD.
RANDER DIVISION, SURAT

SCHEDULE-B

Schedule-B for work of Construction of Plinth, Rising of Existing Plinth for Transformer at Various locations within Jurisdiction of **Rander T-2 Sub division and any other Sdn under Rander Division** and if as per requirement – work Require to be done Under any of Sdn under Surat city circle. The work to be carried out in all Scheme.

Sr. No.	Description	Rate in Rs.	Unit	Amount in Rs.
1	Raising transformer plinth of various transformer centers by Providing and fixing RCC block in C.C. 1:2:4 in block of size 600X300X150 mm including carting the block of at various transformer centre lifting the transformer form plinth, raising the plinth by block masonry in Cement mortar (1:6), placing transformer in the position of raising plinth with all cost of materials say cement, sand, centering, labour and curing the block etc. Complete.	220	Nos	
2	Inside fencing area to be finished with 6" thick 1:2:4 cement concrete (All materials required being use like cement bags, sand, kapchi is to be brought by the contractor at this own cost.) (payment will be given is sq.ft. area for which concrete is done at FRP fencing)	81	Sq. ft.	
Total Estimated Amount				Rs. 27,00,000/-
In words : Rs. Twenty Seven Lakh Only.				

Below / Above _____%

Grand Total _____

Note :

1. The Rates quoted by Bidder will be exclusive of GST & any escalation in rate of GST during the tenure of the contract will be paid by DGVCL as part of statutory variation.
2. If required the contractor heva to carry out the work in any sub/div. under Rander Division.
3. Location wise photograph should be attached with bill.

EXECUTIVE ENGINEER (O&M),
D.G.V.C.L., Rander Division.